

STATE BANK OF INDIA

ELECTRICAL WORKS				LAPLACE GUEST HOUSE- B901, B902, B903, B904, B905 & B906	
S.NO.	Description of the work	Unit	Qty	Rate (Rs)	Amount (Rs)
PART A - MODULAR SWITCHES & SHOCKETS					
1.	Supply and installation(Concealed) of double door 4-way TPN DB with MCB having breaking capacity of 10 KA. a) incoming- 1 No 63 Amp ,25KA,4P MCB b)outgoing - 9 Nos. 32 Amp SP MCB C series ecessary blanking plate as required. (FLAT -B901 & B902) (MAKE: Legrand/ SIEMENS/ HAGER/ Schneider)	No.	2		
2 (a)	Supply & fixing of 16 Module S/w board i) 07 Nos 10 amp switch, 02 nos. 10 Amp switch with fan indication, 01 No. 10 amp two-way switch, 01 No 10 amps socket outlet & 02 nos. regulator. ii) 1 No. mounting MS box iii) 1 No. front plate. (For Drawing Hall) (MODULAR SWITCHES, SHOCKETS MAKE: NORISIS/ Legrand-Myrius /MK-Blenze/ Crabtree-Athena /Eq. North West)	Nos.	6		
(b)	Supply & fixing of 08 Module S/w board i) 03 Nos. 10 amp switch, 01 no. 10 Amp switch with fan indication, 01 No. 10 amps socket outlet & 01 no. regulator. ii) 1 No. mounting MS box iii) 1 No. front plate. (Light Point - Bed Rooms/ Common Hall)	Nos.	18		
(c)	Supply & fixing of 8 Module S/w board i) 03 Nos 10 amp switch, 03 No 10 amps socket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (TV Point - Drawing Hall/ Bed Rooms)	Nos.	20		
(d)	Supply & fixing of 6 Module S/w board i) 02 Nos 20 amp switch with RED indication, 02 No 20 amps socket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point (20A)- Common Hall/ Drawing Hall/ Bed Room)	Nos.	24		
(e)	Supply & fixing of 6 Module S/w board i) 01 Nos 20 amp switch with RED indication, 01 nos. 10 Amp switch, 01 No 20 amps socket outlet & 01 nos. 10 Amp shocket. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point (20A/10 A)- Common Hall/ Drawing Hall)	Nos.	6		

(f)	Supply & fixing of 6 Module S/w board i) 02 Nos 10 amp switch, 02 No 10 amps socket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point (10A) - Common Hall/ Drawing Hall)	Nos.	12		
(g)	Supply & fixing of 3 Module S/w board i) 01 Nos 20 amp switch with RED indication, 01 No 20 Amp shocket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point - Drawing Hall/ Common Hall/ Kitchen)	Nos.	30		
(h)	Supply & fixing of 3 Module S/w board i) 01 Nos 20 amp switch with Geyser indication, 01 No 20 Amp shocket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point - Bathrooms)	Nos.	12		
(i)	Supply & fixing of 3 Module S/w board i) 01 Nos 10 amp switch, 01 No 10 Amp shocket outlet. ii) 1 No. mounting MS box iii) 1 No. front plate. (Power Point (10A) - Drawing Hall)	Nos.	12		
(j)	Supply & fixing of 2 Module S/w board a) 01 Nos telephone shocket outlet, 01 No TV outlet. b) 1 No. mounting MS box c) 1 No. front plate. (Telephone & TV Pont - Drawing Hall/ Common Hall/ Room)	Nos.	18		
(k)	Supply & fixing of 2 Module S/w board i) 01 Nos door bell switch, 01 No 10 Amp 2-way switch. ii) 1 No. mounting MS box iii) 1 No. front plate. (Entrance Door)	Nos.	6		
(l)	Supply & fixing of 01 Module S/w board i) 01 Nos 10 Amp switch. ii) 1 No. mounting MS box iii) 1 No. front plate. (Store Room)	Nos.	6		
(m)	Supply & fixing of Power unit in surface box with 32 A, MCB + 25A Plug & Shocket, complete in all respect. i) 01 Nos 10 Amp switch. ii) 1 No. mounting MS box iii) 1 No. front plate.	Nos.	18		

	<p>Distribution wiring (concealed/ partly surface) including new point wiring 660 volt grade 3 x1.5 sq.mm. (cu) PVC flexible FRLS wire in MEDIUM Duty PVC conduit PVC (ISI Marked) conduit along with Conduit accessories circular boxes, MS boxes, 6 Amps <u>Modular Type</u> switch with socket outlets 6 pin, all individual control switch etc. Conduit size & nos of wires in conduit as per code of practice with circuit wiring with (2x2.5 + 1X1.5) sq.mm. copper wire from MCB DB to respective sw board.</p> <p>N.B. (I)Earth & neutral may be looped but from the last point earth & Neutral has to be connected with sw board.</p> <p>(ii)Point wiring should be inclusive of continuous wire length up to the connection block of light fittings/fans.- Switchboard: NORISIS/ Legrand-Myrius /MK-Blenze/ Crabtree-Athena /Eq. North West) PVC CONDUIT: BEC /NIC/AKG/PRICISSION WIRE FRLS : FINOLEX/ NATIONAL / RR KABLE / KEI/POLYCAR</p>				
	a) Light Point (one switch one control)	Nos	60		
	b) Light point (one switch control two lights)	Nos.	30		
SUB-TOTAL (A)					
LIGHT FITTINGS, GEYSER, TV AND FANS					
3 (a)	Supply & installation of 43" SONY Make Full HD LED TV. (MAKE: SONY TV Model- KD-43X75)	Nos	2		
(b)	Tata Sky Full HD Set-top Box with remote & accessories having 01 months free subscription.	Nos	2		
(c)	Tuffen Glass bracket/ stand for set-top Box.	Nos	6		
4.	Supply & installation of 5-star, 25 liter geyser with temperature control. (MAKE: AO SMITH Model- HSE-SDS-025)	Nos	4		
5.	Supply & installation of 1200 mm sweep anti-dust ceiling fan. (MAKE: CROMPTON Model - AURA2 DESIGNER 3D - PERL WHITE)	Nos	10		
6.	Supplying and installation of LED strip 24 watt 5 mtr length with driver Blue/ warm white colour for installation false ceiling cove (Philips/ wipro/Jaguar)	Sets	10		
7.	Supply and installation of Profile Light 45 watt 5 mtr length with driver Blue/ warm white colour for installation false ceiling cove (Philips/ wipro/Jaguar), complete in all respect.	Sets	5		
8.	Supplying and fixing Philips or equ. Make 10 W LED Cool day light/ worm round type downlighter.	Nos.	10		
9.	Supplying and fixing of surface mounted Philips or equ. Make 7 W LED Cool day light/ worm light for wall picture, Mirror.	Nos.	10		
10.	Supplying and fixing Philips or equ. Make 2 W LED Cool day light/ worm recessed round type downlighter.	Nos.	20		

11.	Supply & installation of Philips or equ. Make Wall lamp. NOTE: Presently base rates are fixed. The finalisation of lights shall be made at the time of execution of works & payment shall be made as per actual cost on submission of rate analysis basis.	Nos.	30	2,200.00	66,000.00
12.	Supply & installation of PHILIPS make designer suspension/ Jhoomer lights. NOTE: Presently base rates are fixed. The finalisation of lights shall be made at the time of execution of works & payment shall be made as per actual cost on submission of rate analysis basis.	Nos.	2	20,000.00	40,000.00
13.	Supply & installation of PHILIPS make 12.5/15 Watt round surface/ concealed light	Nos.	8		
14.	Supply & installation of PHILIPS make 18/ 22 Watt batten LED light.	Nos.	12		
15.	Supply & installation of PHILIPS make mirror light	Nos.	12		
16.	Supply & installation of 250/ 300 mm plastic body Exhaust Fan with louvers.	Nos.	6		
17.	Supply & installation of window AC front grills for existing window ACs.	Nos.	12		
18.	Supply & installation of PHILIPS make 7 watt LED bulbs (Natural white/ worm) for suspension lights & wall lamps	Nos.	10		
19.	Dismantling of all existing old light fitting & fixtures, distribution boards etc. complete in all respect.	Job	6		
SUB-TOTAL (B)					1,06,000.00
Total (A+B)					1,06,000.00

NOTE: All rates are exclusive of GST.