

PRICE BID FOR INTERIOR FURNISHING WORKS FOR SETTING UP WEALTH MANAGEMENT HUB AT T B ROAD BRANCH, PALAKKAD UNDER REGION IV, PALAKKAD.

| SI.No | DESCRIPTION OF WORK | Qty | Unit | Rate | Amount |
|-------|--|-----|------|------|--------|
| 1 | Flooring: Providing and fixing 60 x 60 cm or 80x 80 cm vitrified tiles Johnson & Johnson, 'Marbonite" or equivalent approved for flooring and skirting. Tile to be fixed to existing flooring using approved quality adhesive. Basic price of tiles to be taken as Rs.65 per square foot ex showroom (Tiles will be selected by the Bank). The debris if any has to be removed at the cost of contractor.. | 100 | Sq M | | |
| 2 | Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above. | 4.2 | Sq.M | | |
| 3 | Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns. | 50 | Sq.M | | |

| | | | | | |
|---|---|----|------|--|--|
| 4 | <p>Officer Table :- Providing and fixing Branch Manager's table of size 1500x750 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 530 x 320 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.</p> | 4 | No. | | |
| 5 | <p>Side Tables For Officer-Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1200mm x 450 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.</p> | 4 | No. | | |
| 6 | <p>Low Level Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm, 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.</p> | 5 | Sq.M | | |
| 7 | <p>Providing and fixing columns/ wall panelling to detail as per instruction of engineer in charge ,with 18 mm thick plywood finished with 1 mm thick laminate.</p> | 30 | Sq.M | | |

| | | | | | |
|----|--|-----|------|--|--|
| 8 | Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing storage, tables wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. If 1mm laminate without plywood has to be fixed on the storage, tables etc rate will be given only for mica at a reasonable rate. The work has to be executed as per the instruction of Engeneer in charge. | 20 | Sq m | | |
| 9 | Providing and fixing in position of double skin partition, firmly fixed on floor / wall made out of GI rectangular section of 44.5x83.5x2.5 m thick of internal frame structure placed horizontally and vertuically in 60x60 cm interval, which is covered with 6mm thick fire rated cement board on both sides finished with 2 coats of putty and 2 coats of plastic emulsion paint with roller brush of approved colour as per engineer's choice.partly paneled and partly glazed, | 20 | Sq m | | |
| 10 | Scrapping and removal existing paint, surface preparation and applying two coats of interior grade emulsion paint of approved colour and quality (Asian or equivalent) over 2 coats of putty applied over a coat of primer to internal walls, ceiling including labour charges,cost and conveyance of material etc complete | 200 | Sq m | | |
| 11 | Painting windows and related grills using synthetic enamel paint two coats of approved colour including all frameworks and related elements after removing the existing paint with sand paper and thereafter cleaning the surface including all labour charges, material charges etc complete. | 30 | Sq m | | |
| 12 | Providing and Fixing 100 mm wide Vertical Blinds of Vista Levton or approved equivalent make and colour. | 15 | Sq.M | | |
| 13 | Chairs, Medium back, revolving chair, with seat made of PU high density moulded seat, and Back made of metal frame with neted fabric/mesh back, armrest with nylon handle, Dynamic PU Handle, Synchro Mechanism, High pressure Class 3 Hydraulic with Cover, Powder Coated Metal Or Nylon Base with Imported wheel as per satisfaction of Engineer. | 4 | Nos | | |
| 14 | Chairs : Low Back non revolving chair with fixed low back. 1"16 Guage MS Tube,1/4" Flat, 8 mm flat High Tension Spring, density Seat and Back Foam, High Quality Synthetic Leather, 14" Handle PU Pad,1:16 Guage Double side leg, Full Frame Anti Rust treated and powder coated as per satisfaction of Engineer.. | 8 | Nos | | |

| | | | | | |
|----|--|----|----|--|--|
| 15 | Supplying of sofa (3 Seater) having high quality synthetic leather upholstery of make as per vsatisfaction of the Engineer.. | 1 | No | | |
| 16 | Providing round discussion table of size 75-90 cm, with 18mm ply, 1mm laminate and on top 12mm glass with polished edges, centrally placed leg made of 18mm ply and laminate. The table should be made as per the satisfaction of the Engineer in charge. | 1 | No | | |
| 17 | Dismantling the existing tables, partitions, side tables, storage and other items etc and removing the debris away from the site at the cost of the contractor as per the direction of Engineer in charge. (6 tables, 4 side tables, storage to a length of 3.5 m, partitions to the length of 15 m) | LS | | | |
| | Total Amount excluding GST | | | | |

Note: GST at applicable rates will be paid extra in addition to the quoted rates.