



PART – B: PRICE BID

E- REVERSE AUCTION TENDER
FOR INTERIOR WORK
AT STATE BANK OF INDIA,
VOFT GUEST HOUSE AT
SECTOR-42, CHANDIGARH

TENDER SUBMITTED BY :

NAME OF FIRM: _____

ADDRESS: _____

MAIL ADDRESS:- _____

PHONE NO.: _____

**BILL OF QUANTITIES OF INTERIOR WORK FOR SBI VOTF GUEST HOUSE
AT SECTOR 42, CHANDGARH**

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
B	INTERIOR WORK				
1	Plaster of Paris (P.O.P) ceiling including making coves, offsets, cost of GI Frame work, etc. Complete in all respects as per instructions of Architect/ Engineer-in-charge.	Sqm	9.00		
2	POP punning on the wall to give even and smooth finish including making Offset, Grooves etc. complete in all respect.	Sqm	876.00		
3	Wall panelling with 1mm th. Mica over 8mm th. MR Grade Ply over Aluminium Frame made from 25x50mm Aluminium member (18 Gauge) @ 2' c/c both side including making offset, making grooves, Moulding etc. complete as per Architect/ Engineer in Instruction.	Sqm	75.00		
4	Wall panelling with 4mm th. Veneer over 8mm th. MR Grade Ply over Aluminium Frame made from 25x50mm Aluminium member (18 Gauge) @ 2' c/c both side including making offset, making grooves, Moulding and French polish etc. complete as per Architect/ Engineer In Instruction (Cost of Veneer not less then 65/- Sqft)	Sqm	10.00		
5	Wall panelling with Leatherite/ Velvet/ Fabric duly pasted on 12mm th. Foam to fixed 8mm th. MR Grade Ply over Aluminium Frame made from 25x50mm Aluminium member (18 Gauge) @ 2' c/c both side including making offset, making grooves, Moulding and Melamine polish to Moulding etc. Complete as per Architect/ Engineer In Instruction (Leatherite/ Velvet/ Fabric cost not less then Rs. 750 per Mtr)	Sqm	17.00		
6	Providing and fixing Wall paper on Wall & Ceiling of approved design including base preparation etc. complete as per instructions of Architect/ Engineer-in-charge. (Wall Paper Cost not less then 65/- Per Sqft)	Sqm	50.00		
7a	Preparation of Wall surface for painting using ready mixed cement based wall putty by applying two or more coats to get required finish including sand papering the surface, removing old loose wall paint complete in all respect.	Sqm	950.00		
7b	Painting the wall with Premium Quality Plastic Emulation Paint including Priming coat and the two/ three coats of Premium Emulation Paint as per manufacturer's specification complete as per instructions of Architect/ Engineer-in-charge.	Sqm	950.00		
8	Enamel Painting the Existing Windows/ Grills ect with two coats of Enamel paint including base preparation etc. complete as per instructions of Architect/ Engineer -in-charge	Sqm	140.00		
9	French Polish to Existing Window & Door Frames including removing existing enamel paint filling putty making base preparation etc. complete in all respect.	Sqm	140.00		

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
10	Remoulding of Wooden Doors with fixing 1mm th. mica of approved design over 4mm th. MR Grade Ply including fixing new SS Finish handle, Lockset, SS Hinges, Tower bolts, Door Stopper and Side Moulding to Chowkhat etc. including French Polish to Edge Moulding etc. Complete in all Respect as per instructions of Architect/ Engineer-in-charge.	Nos	53.00		
11	Providing and Fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	Nos	15.00		
12	Providing and placing Cupboard with made from 19mm MR ply duly finished with 1mm th. Mica all inside Front door/ Face to have 1mm th Designer Mica complete with Crack Hinges, dividing Partitions, Pull out Drawers 2 Nos and Shelves etc complete in all respect with all necessary Hardware as per Design and instruction of Architect/ Engineer-in-charge.	Sqm	50.00		
13	Providing and Fixing Dressing Mirror 5mm th. complete with SS Studs and 4mm th. Ply Backing	Sqm	17.00		
14	Providing and fixing TV Back Panel made from 19mm MR grade Ply duly finished with 4mm th. Veneer duly French Polished. Panel to have Open storage 8" high & 9" deep at Bottom The work includes all hardware all exposed face of Ply to have teak margin duly polished complete in all respect (Cost of Veneer to be 65/- Sqft)	Rmt	19.00		
15	Renovation of Bed with 1mm th. Mica over 4mm th. Ply on Sides of bed changing Ply/ Board is necessary Complete with French Polish as per Instructions of architect / Engineer Incharge	Each	15.00		
16	Providing and Placing Side Credenza of size 18"x18"x2'0" made from 19mm MR Grade Ply, duly finished with 1mm th. Mica outside and 1mm th. Mica allover inside. Side Credenza to have one Pullout Drawer and one openable storage with Handle, Crack Hinges, Drawer Channel, Edge Moulding to be French Polished as per instructions of Architect/ Engineer Incharge	Each	30.00		
17	Providing and Placing Study table made from 19mm Ply duly finished with 1mm th. Mica all over complete as per architect instructions	Each	15.00		
18	Providing and fixing Kitchen Under Counter Storage made from 19mm th MR grade ply duly laminated with 1mm th. Mica allover (outside & Inside) including internal Dividing partition @ 3' c/c, Shelves, SS Pullout Baskets with all necessary Hardware i.e Drawer Channels, Knob/ Handles, teak wood edging duly Painted/ Polished etc. complete in all respect.	Sqm	4.50		
19	Providing & fixing Kitchen Chimney of exhaust capacity 1200m ³ /Hr complete with Flexible Extension Pipe ect. (Glen/ Kaff/ Elica Make)	Each	1.00		
20	Providing and fixing Kitchen Overhead Storage made from 19mm th MR grade ply duly laminated with 1mm th. Mica allover (outside & Inside) including internal Dividing partition @ 3' c/c, Shelves, with all necessary Hardware i.e Crank Hinges, Knob/ Handles, teak wood edging duly Painted/ Polished etc. complete in all respect.	Sqm	3.00		

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
21	Providing and Fixing Fabric Curtain, as approved design including Sliding channel, Stitching, fixing in position complete in all respect. (Fabric cost 750/- Mtr)	Sqm	60.00		
22	Providing and Fixing Wall Art Painting and Artefacts as per approved design by Architect/ Engineer- In-charge.				
i	Metal Art Artefact of Copper Finish (Size 3'x3'0")	Nos	2.00		
ii	Wall Art Paintings (1'6"x1'6")	Nos	15.00		
ii	Wall Art Paintings (1'0"x1'6")	Nos	15.00		
	TOTAL FOR PART B (INTERIOR WORK)				
	DISCOUNT IF ANY				
	NET AMOUNT AFTER DISCOUNT				
NET AMOUNT IN WORDS :-					