

PRICE BID

BRANCH : Boring Road

UNDER RBO : RBO-II, Patna Central

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1.	<u>12 MM THICK TOUGHENED GLASS DOOR ETC</u> Providing and fixing / fitting mm thick toughened glass of approved make with all necessary hardware accessories patch fittings etc including cost of labours and materials etc as per approved materials Colour etc and specifications .	Sq.m	4.30		
2.	<u>12 MM THICK TOUGHENED GLASS PARTITION (BM CABIN) ETC</u> Providing and fixing / fitting 12 mm thick toughened glass partition of approved make with all necessary hardware accessories patch fittings etc including cost of labours and materials etc as per approved materials Colour etc and specifications	Sqm	23.92		
3.	Providing D-Tel depository cabinet of Godrej make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	Nos.	6.00		
4.	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point only on table top, table front, & designer beads SBI fascia, back black color & rounding of edges to complete in all respect, as per site condition and instruction of R.M/C.M (CS & CM)/ with rounding of edges etc to complete job. (Counters, B.M's table and S.M's table tops with fronts).	Sq.m	25.22		
5.	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	7.00		
6.	<u>ROLLER BLINDS :</u> Providing & fixing ROLLER blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows . All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.	Sq.m	15.00		

7.	Dismantling of existing work station tables etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century / Green or equivalent make & 1mm thick high glosive blue / white laminate of Century/Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction .	Nos.	14.0		
8.	<u>SYNTHETIC ENAMEL PAINTING :</u> Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direction of bank.	Sq.m	110.00		
9.	Refurbishing & remodeling of the existing SWO (including side units) counters as per the direction including giving it curved shape in front portion, repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	No's.	6.00		
10.	Dismantling of low storage cabinets of different sizes etc and re-fixing the same as per the direction of , including repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I	No's.	20.00		
11.	Repairing of full height/low height partly paneled partly glazed / non-glazed / low height partitions etc as per the direction of , including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks, resizing of glass etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Sq.m	105.00		

12.	Repairing of wall / column paneling etc as per the direction of , including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/L.	Sq.m	69.30		
13.	<p>Providing and fixing wall & Column Paneling as per drawing & design :</p> <p>The Paneling shall be fixed on a concealed G I frame framework of required section placed at 600 mm c/c both horizontally & vertically.</p> <p>The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity.</p> <p>The surface is to be finished with 1 mm thick high gloss laminate of approved shade & make.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc.</p> <p>Executed elevation area is to be measured for finished</p>				
(a)	Interior Columns in Banking Hall	Sq.m	Nil		
(b)	With 12 mm thick MDF board fixed on frame finishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall back side of SWO Counters.	Sq.m	96.36		
14	Providing and fixing of 600x600 mm size non skid vitrified flooring of minimum 8mm thick in 1:4 cement mortar (20 mm thick bed)/synthetic adhesive as applicable. all joints filling shall be completed in all respect. Rate shall include the finishing joints joints with matching colour pigments (Basic rates of tiles Rs.625/-per sq.mt.). Rate to include cost of floor leveling properly before fixing of tiles with cement mortar. Double charge Make-RAKKAJARIA/ORIENT/ BELL/SOMANY .Cost to include dismantling existing floor tiles , and disposing off same to dumping yard	Sq.m	368.0		

11	Providing and applying wall putty of 2 mm average thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth complete as per direction of Bank.	Sq.m	205.0		
12	Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.	Sq.m	205.0		
	Total				
	PRICE SHOULD BE QUOTED EXCLUSIVE OF GST , IT WILL BE PAID SEPARATELY BY THE BANK				

Place: -

Date:-