

PRICE BID : HIGH COURT BRANCH PATNA

BRANCH : Highcourt Branch

UNDER RBO : RBO-II, Patna Central

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1.	<u>12 MM THICK TOUGHENED GLASS DOOR ETC</u> Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hardware accessories etc including cost of labours and materials etc all complete as per specification.	Sq.m	5.0		
2.	Providing D-Tel depository cabinet of Godrej make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	Nos.	4.00		
3.	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point only on table top, table front, & designer beads SBI facia, back black color & rounding of edges to complete in all respect, as per site condition with rounding of edges etc to complete job. (Counters, B.M's table and S.M's table tops with fronts).	Sq.m	19.50		
4.	<u>Providing and fixing ACP Cover for Rolling Shutter Box :</u> The cover is to be set with an inner wooden framework of 50 mm x 50 mm well seasoned Malaysian sal wood sections, placed at suitable spacings not exceeding 600 mm c/c. The framework shall be covered by 12 mm thick BWR plywood. The work is to be finished with 3 mm thick exterior/interior grade Aluminium Composite Panel(ACP) cladding of approved shade & make with grooves duly treated with silicon sealant. The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for finished work.	Sqm	3.5		
5.	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	7.00		

6.	<u>VERTICAL BLINDS :</u> Providing & fixing 100 mm wide vertical blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows & opening of B.M's chamber. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.	Sq.m	12.00		
7.	Dismantling of existing work station tables etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century / Green or equivalent make & 1mm thick high glosive blue / white laminate of Century/Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Nos.	3.0		
8.	<u>SYNTHETIC ENAMEL PAINTING :</u> Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direction of bank.	Sq.m	110.00		
9.	Dismantling of SWO counters etc and re-fixing the same as per the drawing , including repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	No's.	4.00		
10	Dismantling of low storage cabinets of different sizes etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I	No's.	9.00		

11.	Repairing of full height partly paneled partly glazed / non-glazed / low height partitions etc as per the drawing including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high gloss blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks, resizing of glass etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Sq.m	40.50		
12	Repairing of wall / column paneling etc as per drawing including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high gloss blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Sq.m	55.00		
13	<p>Providing and fixing wall & Column Paneling as per drawing & design :</p> <p>The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically.</p> <p>The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity.</p> <p>The framework is to be covered by 9 mm thick BWP plywood on exposed side with suitable fixtures.</p> <p>The surface is to be finished with 1 mm thick high gloss laminate of approved shade & make.</p> <p>Provisions are to be made for fixing LED strips.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc.</p> <p>Executed elevation area is to be measured for finished</p>				
(a)	Interior Columns in Banking Hall	Sq.m	Nil		
(b)	With 12 mm thick MDF board fixed on frame finishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall back side of SWO Counters.	Sq.m	96.60		
	Total				

	PRICE SHOULD BE QUOTED EXCLUSIVE OF GST. GST WILL BE PAID SEPARATELY.				

Place: -

Date:-