

**PROVIDING CORIAN TOP/ LAMINATE CHANGE FO MAKING UNIFORM LAYOUT FOR PBB CHERTHALA  
BRANCH**

Sl	Description of work	Quantity	Unit	Rate	Amount
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	20	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface- 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	20	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	6	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete	110	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	5.00	Sq.M		

Sl	Description of work	Quantity	Unit	Rate	Amount
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	3.00	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6.00	Sq.M		
8	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	110.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	100.00	Sq.M		
10	Providing PVC telescopic key boad tray with channel	2.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	2.00	set		
12	Providing and fixing Godrej auto lock	4.00	Nos.		
13	Providing and fixing vertical Blinds	15.00	Sq.m		

Sl	Description of work	Quantity	Unit	Rate	Amount
<b>FOR SBI WEALTH HUB AT PBB CHERTHALA BRANCH PREMISES</b>					
Sl No.	Description of work	Quantity	Unit	Rate	Amount
1	<b>Fixed glass partitions</b> : Providing and fixing of fixed glass partitions with 12mm thick toughened glass using <b>PT</b> Standard fittings like PT 90/PT 92 of <b>Dorma or equivalent make</b> at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including 3M Vinyl sticker / etching as per approved colour design / patterns etc complete.	19	Sq.M		
2	<b>Fully glazed Door-</b> Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	2	Sq.M		

Sl	Description of work	Quantity	Unit	Rate	Amount
3	<p><b>Table for Officers</b> : Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete. Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick to be fixed on front vertical laminated Plywood Board with SS studs.</p>	2	No.		
4	<p><b>Side Tables For Officers</b> : Providing and fixing side unit for Officer table to detail as per drg. of size 1000mm x 450 mm made of 25 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.</p>	2	No.		

Sl	Description of work	Quantity	Unit	Rate	Amount
5	<b>Low Level Storage</b> :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm to 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 25 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	4.5	Sq.M		
6	<b>Gypsum Board False Ceiling</b> : Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough . Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.	16	Sq.M		
7	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shadeover a coat of putty including scrubbing & cleaning the surface.Approved make of paint: Asian, Berger, Nerolac or equivalent	30	Sq.M		

Sl	Description of work	Quantity	Unit	Rate	Amount
8	<b>Custom Made Full Height Partly glazed Solid Partition:</b> Supply and set in position of custom made double skin full height partitions with 12 mm glass panel as per Bank's direction, as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves . Measurement for the partition area shall be considered from floor level to false ceiling level only.	8	Sq.M		
	<b>TOTAL</b>				
	<b>GST at applicable rate will be extra</b>				