

ALTERNATIVE PREMISES OF BISWANATH CHARALI BRANCH

BOQ for Supply, Installation and Annual Maintenance Contract for 5 years of Air-conditioners

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej	No.	5		
2	Supply of 2.0 TR Cassette type split air conditioners with Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Carrier/Daikin /LG	No.	13		
3	Installation charges of the 1.0/1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	5		
4	Installation charges of the 2.0 TR Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	13		
5	For 2.0 TR Copper Cassette type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	year	260		
6	For 1.0 TR/1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	25		
7	Supply and Installation of 4 KVA Stabilizer for 1.0 TR/1.5 TR Split Acs	Nos.	5		
8	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	13		
9	Comprehensive Annual Maintenance Contract(AMC) of above mentioned 5 No. of 1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.(The rate will be applicable for 5 years of AMC.)	year	1		
10	Comprehensive Annual Maintenance Contract(AMC) of above mentioned 13 Nos. of 2.0 TR Copper Cassette type split air conditioners after expiry of defect liability period of 1 year from the date of installation.The rate will be applicable for 5 years of AMC.)	year	1		
	GST will be extra as applicable		Grand Total		