

**BOQ OF INTERIOR WORK OF BRANCH & ON SITE A.T.M. OF "STATE BANK OF INDIA" AT
SHAMGARH, M.P., (MANDSAURE)**

S.No.	Description of Item	Qty	Unit	Rate	Amount
A	Part A : Interior Works :				
	Mode of Measurements : Area of exposed and finished surfaces will be measured.				
1	False Ceilings :				
1.1	Gypsum Board False Ceiling :	81.00	Sqm	0	0
	Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm & a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. ...				
1.2	Cove in ceiling :	68.00	Rmt	0	0
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				
1.3	Mineral Fibre Grid Tile Ceiling :	91.00	Sqm	0	0
	Mineral Fibre Acoustic Ceiling Tiles: Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc or equivalent make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mmx 600mmx 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. ...				
2	Partitions :				
2.1	Full Height Partly Glazed Partly Wooden Double Skin Plywood Partitions :	29.00	Sqm	0	0

	Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/ Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including antitermite treat-ment to all wooden members wherever used. The partition to be sandwiched with 8 mm HDF Board / MR plywood from both the sides and finished with 1.0mm thick approved shades of laminated finish & match the panelling pattern. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals.The cost shall include all labor, materials, strictly as per the given design & drawing etc.				
2.2	Low Height partitions With / Without Glass :	37.00	Sqm	0	0
	Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite to all wooden members wherever used. The partitions to be sandwiched with 8.0mm HDF Board / MR plywood from both the sides & finished with 1.0mm thick approved shades of laminat. finish & match the panelling pattern. The borders/edges to be lained finish. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete. One additional section 50 x 50mm shall be placed at 700 mm level from floor to fix the table. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite.				
2.3	Full Height Laminated Double Skin Plywood Partitions Wth Both Sides Laminations :	10.00	Sqm	0	0
3.1	Wall/Column Panelling - Type I :	82.00	Sqm	0	0
	Providing, making & fixing single skin paneling (type I using 6 mm thick MR plywood) on walls, front facia, boxing for rolling shutter, and/or columns & /or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 mt. ht., as required, made out of 25 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as.				
3.2	Wall/Column Panelling - Type II : single skin panelling	5.00	Sqm	0	0

	Providing and fixing single skin panelling (type-II) on walls , front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises as required with ply frame work for levelling and 18 mm thick MR ply of approved ISI grade, and/or limited use of 6mm Flexible ply for panelling of circular columns etc. including fixing as per pattern and style as directed, with salwood frame of size 38				
3.3	Cabinet for Electric Panel :	1.80	Sqm	0	0
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).				
3.4	ACP Panelling Works :	53.00	Sqm	0	0
	ACP Panelling in ATM room & exteriors and Shutter boxing with trap door : Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, (OR Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/columns/ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, etc. complete. ..contd..				
3.5	12 mm Additional Plywood framing/ Boxing :	2.00	Sqm	0	0
	Providing and fixing additional ply framing/boxing in 12 mm commercial ply (and/or 8mm commercial ply if required) for fixing of softboards/whiteboards etc. on wall surfaces or existing single /double skin partitions or boxing on walls/columns including levelling on walls, and in double thickness for small partitions on tables, etc. The framing shall be finished with 1mm thick plain or Textured Laminates (on one exposed surface) of approved shades including inlay etc if required and as directed along back credenza as required as per fixing pattern to achieve overall flush appearance. The framing shall include the provision of switchboard, lan cabling, telephone wiring etc. The cost shall also include providing and applying polish/paint, etc.				
4	MDF Work:				

4.1	6 mm :Providing and fixing 6 mm Thick Plain MDF sheet in required design/pattern/ shape/size, etc. for application of texture paint/ finishes. MDF shall be fitted over plywood structures, single skin panelling or double skin ply partition and cost shall be calculated for all these application. It shall be provided & fixed in major areas, bands and /or geometrical patterns and edges flat/ bevelled/ rounded off as per requirements upon approval from the Bank's engineer. MDF shall be of reputed makes like Century/ Greenply etc. and cost shall include all recommended adhesives, nailing, screwing, mitring, edge finishing etc. complete, as and in the manner required for proper and seamless fitting.	5.00	Sqm	0	0
4.2	3 mm : same as item no. 4.1 but 3 mm thick for groove depth for BM Cabin. (Groove to be shaded with off-white colour).	36.00	Sqm	0	0
5.2	Partly Glazed Door : (Partly Glazed Door on Floor Spring)	3.00	Sqm	0	0
5.3	Flush Door :	13.00	Sqm	0	0
	Providing and fixing single shutter flush doors of approx size 2.10 m x 0.75 - 0.9 m as instructed, hinged type door openable one side as instructed, made up of superior quality waterproof flush door partially glazed (cost of glass included). The door shall be flush door of approx. 32-38 mm thickness, both sides 1 mm thk laminate as per design. Cost shall be inclusive of beadings, all accessories like SS hinges, medium quality mortise handles/locks, baby latches, stopper, etc. Fittings shall be in SS finish as per approval, the cost shall include p/f of door closers of reputed brand as per approval with all doors.				
5.4	Aluminium Frame Glass Door for UPS / Server Room :	1.00	Sqm	0	0
	Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size 100 x 50 x 2.0mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement ,with SS handles, all necessary fittings, all labour, materials, etc complete. (to be fixed in sever & UPS room)				
5.6	FRP Door Frame & Door for Washrooms :				
5.6.1	FRP Door Frame : Providing and fixing of factory-made Fiberglass Reinforced plastic (FRP) Door Frames of Roofit" brand or equivalent, having three-legged of cross-section 90mm x 45mm having a single rebate of 32mm x 15mm to receive shutter of 25-30 mm thickness (dimensions are approx., to provide as per site requirements). The laminate door frame molded with fire retardant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2 mm thick and shall be filled with a suitable wooden block in all the three legs. The frame shall be covered with fiberglass from all sides. M.S. stay shall be	10	Rmt	0	0
	FRP Door :				

5.6.2,	Providing and fixing single panel FRP door & door frame of reputed make (approx. opening size 2.10 m x 0.75 m) as instructed, hinged type door openable one side as instructed. The door shall be flush door of approx. 25 mm thickness, veneer finish. Cost shall be inclusive of all accessories like hinges, handles, baby latches, stoppers, etc. fittings (on both sides) shall be in SS finish as per approval, etc. complete.	3	Sqm	0	0
5.8.1	CHANNEL GATE REPAIRING WORK	1	Job	0	0
	Repairing of Existing Channle gate with proper Alignment of channel gate, welding,complete with bolts, nuts, lock-ing arrangement, stoppers, handles,and proper rolled on pully at site including all, labour material etc complete.				
6	Sub Total : Part A (Interior Works)				0.00
B	Part B : Furnishing Works :				
7	Furnitures :				
7.2	Tables :				
7.2.1	Providing and supplying Officer's table and other tables as detailed below :				
a	The table shall be of size of 1500 x 750 x 750 mm height, with edges been double thick having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray (<i>measured separately</i>) as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufactures specification.				
7.2.2	Executives Branch Manager Table :	1	Nos.	0	0
	... same as item no. 6.2.1 but providing and supplying Executives Branch Manager of minimum size 2.1 m x 0.90 m x 0.75 m ht.				
7.2.3	Officer / Relationship Manager/ Auditor Tables :	2	Nos.	0	0
	... same as item no. 6.2.1 but providing and supplying Officer / Relationship Manager/ Auditor Tables of minimum size 1.65 -1.50 m x 0.75 m x 0.75 m ht.				
7.2.4	Assistant Tables :	1	Nos.	0	0
	... same as item no. 6.2.1 but providing and supplying Assistant Table of minimum size 1.5-1.35 m x 0.75 m x 0.75 m ht.				
7.2.5	Single Window Operator Counters :	7.80	Rmt	0	0
	The overall size of each Single Window Counter to be 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement.				
7.2.6	Grahak Mitra Table :	1	No.	0	0
	... same as item no. 6.2.1 but providing, making and placing in position arch shape 1650mm long Grahak Mitra Table of approximate size 1650mm x 800mm - 900mm x 750mm with the following specifications				
7.2.8	Wall Mounted Writing desk :	2.00	Sqm	0	0

	Providing & fixing half round / rectangular customer voucher holders writing counter of width 750-1200 mm and depth 300 - 450 mm fixed to be wall or partition or around the column (on two sides), at a height of 1050-1200mm made of 18 mm thk. MR plywood and 12 mm thick toughned glass top, and sides & edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed. The portion below the pigeon hole box to be provided as a cupboard unit, shall be with openable shutter & adjustable shelf all along the full width of the desk. The cost shall be completed with lippings, mouldings, fittings, and accessories etc as per specification. as per the instruction given by the Bank Engineer. (Measurement vertical area = length x height).				
7.3	Storages / Credenza :				
7.3.1	Officer Storage/Side Credenza :	9.00	Sqm	0	0
	Providing, making and placing in position low height storage cabinets as storage & or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and in 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete.				
7.3.2	Back Credenza / Runner :	6.00	Sqm	0	0
	... same as item no. 6.3.1 but providing and supplying Back Credenza/Runner, low height storage cabinets as storage and/or runners, in 18 mm MR grade plywood in verticals at sides, 900 mm c/c so as to form storage units attached together, each of width 900 mm. (Measurement area = Length x Height).				
7.4	Corian Marble Surfaces on Furniture / Partitions :				
7.4.1	Supplying, Fabrication & Installation of Dupont/Corian quartz of 12mm thk. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. To minimis material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed.	15.00	Sqm	0	0
7.4.2	Deduction for lamination work wherever Corian is been used (area same as Corian).	-15	Sqm	0	0
8	Glass Works :				
8.3	12 mm Glass Work :	5.50	Sqm	0	0
	.. Same as item no. 7.5 but of 12 mm thickness. Also providing, making and fixing in position 12mm thick clear float glass on top of tables with tapered, rounded & polished edges, etc. complete.				

8.4	Etching Glass with Film :	8.00	Sqm	0	0
	Providing & Fixing Birla 3M /Lunar make frosted film fixed on the glass after cleaning and wiping glass surfaces free of any dust or foreign bodies and then fixed plain approved pattern / design film on the glass as per detail drawing inclusive of making necessary cutouts, carting away unserviceable materials out of compound, cleaning the site etc. complete as per the site requirements and the instructions of the Architect. (Basic Cost Of Film not less then Rs.800/- Per smt) . (Measurement area = Length X Height).				
8.3	Laquered Glass :	4.00	Sqm	0	0
	Providing and Fixing of Laquered 12mm Thick Extra Clear Float Glass of reputed brands like Modi, Saint Gobain, ASAHI etc. on Table sides/ Panellings/Table Tops etc as instructed. The laquering shall be done on 12mm Thick EXTRA CLEAR Float Glass with best quality Imported Laquer and Hardner as per the manufacturer's specifications so as to achieve even, scratch free finish of colour as specified or as approved. The Glass Shall be edge polished on all sides before laquering and shall be handled carefully to avoid scratches/chips/jagged edges etc. and shall be fitted in place using a layer of NON-TOXIC SILICON adhesive and/or SS Stud head Caps. The rate shall be inclusive of all procurement, labour for laquering, labour for fixing, transportation, edge polishing etc. complete to the satisfaction of the Bank/SBIIMS.				
9	Hardwares :				
9.1	Providing and fixing Doorset / Sterling / Ozone or as approved heavy duty floor spring , upper patch, bottom patch, etc. complete.	1	Nos.	0	0
9.2	Providing and fixing lock keeper plate, euro profile cylinder EPC), etc. complete.	1	Nos.	0	0
9.3	Providing and fixing night latch with three keys at doors, etc.	2	Nos.	0	0
9.4	Providing and fixing two lever mortise lock of Godrej Make with brass handle	2	Nos.	0	0
9.5	Providing and fixing Door closers on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required.	2	Nos.	0	0
9.6	Providing and fixing floor mounting 6 lever lock for main entrance door	1	Nos.	0	0
9.7	Providing and fixing SS AL-drop 300 mm long along with through nut & bolt fittings, etc. complete.	2	Nos.	0	0
10	Misc. Works :				
10.2	Pin-up boards :	2.00	Sqm	0	0
	Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matt/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not be approved.				

10.2.1	NOTICE BOARD :	2	Nos.	0	0
	Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.				
10.3	Vertical Blinds :	8.00	Sqm	0	0
	Providing & installing Vertical Blinds of Trac / Vista or equivalent, 100 mm wide, in two colours, of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes.				
10.8	Drop & Complaint Box :	1	Nos.	0	0
	Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.				
10.9	Wall Paper :	2	Sqm	0	0
	Wall paper -Wallcoverings to be made from vinyl (PVF), coated with plastic; to be colourfast and washable with dust repellent property. Application of wall paper as per approved sample. Rate to include surface preparation abd application as per manufacturers standards. (Basic Rate Rs.90/- sqft)				
11	Sub Total : Part B (Furnishing Works)				0
	Sub Total : Part A (Interior Works)				0.00
	Sub Total : Part B (Furnishing Works)				0.00
	Total : Part (A + B) =				0
RUPEES					
			Seal & Sign of Contractor		