

Client State Bank of India

Project **INTERIOR RENOVATION WORKS FOR STATE BANK OF INDIA AT SIDDHAROUDHANAGAR BRANCH.**

SCHEDULE-I

BILL OF QUANTITY for Interior Renovation Works

Sl. No	Description	Qty	Unit	Rate	Amount
I	INTERIOR WORKS:				
A	FIXED FURNITURE:				
1.00	PARTITIONS				
1.10	FULL HEIGHT PARTITIONS - PARTLY GLAZED	50.00	Sq.M.		
	Providing and fixing metal stud dry wall partition with following specifications:				
	Supporting system comprising of 51mm / 50mm x 35mm / 24mm x 9.5mm metal studs at 600mm c/c and 51mm /				
	12mm Exterior Grade MDF (EG-MDF) Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto 100 mm from FFL to have 1.0mm laminate of dark blue colour				
	From 100mm to 300mm level to have 1mm Laminate (aqua blue color)				
	From 300 mm level to 1070 mm level to have 1mm Laminate (white color)				
	From 1070 mm level to 2135 mm level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.The glass sizes subject to design drawing etc.				
	From 2135mm level to 2235mm level 1mm Laminate (aqua blue color) on both sides as shown in drawing.				
	Partition above 2235mm level to have 1mm Laminate (white color) as shown in drawing.				
	All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
1.20	FULL HEIGHT PARTITIONS - SOLID	21.00	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as full height partition partly glazed above but for Fully Solid Partitions without glass panels and other specifications remaining the same. Glass panel area from 1220mm lvl to 2135mm lvl to be replaced with solid partition with 1mm Laminate (white color)				
1.30	HALF HEIGHT PARTITIONS	23.00	Sq.M.		
	<i>This item includes partitions for SWO counters, officer cubicles etc as per the layout plan. Height of the partitions shall be as mentioned in the drawings.</i>				
	Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following:				
	1mm thick laminate on top, 50mm bands of 1mm thick laminate on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto 100mm from FFL to have 1.0mm laminate of dark blue colour				
	From 100mm to 300mm level to have 1mm Laminate (aqua blue color)				
	From 300mm level to 1070mm level to have 1mm Laminate (white color)				
	From 1070mm level to 1170mm level 1mm Laminate (aqua blue color)				
	From 1170mm level to 1220mm level to have 1mm thick laminate on both sides as shown in drawing.				
1.40	DOORS IN PARTITIONS				
1.41	32MM DOORS IN PARTITIONS - with glass panel:	4.50	Sq.M.		
	Providing and fixing 32mm thick solid core flush shutter with 85mm x 35mm beech wood frame with rebate around the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of 8mm clear float glass fixed with 19 x 19mm beading on both sides and glass pasted with 3M privacy film as per design.				

Sl. No	Description	Qty	Unit	Rate	Amount
	The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.				
1.50	WICKET GATE - for SWO Counters	10.50	Sq.M.		
	<i>Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably</i>				
	Providing wicket gate made of 32mm solid flush door with alround PVC edge banding / BW lipping and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with 85mm x 35mm beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement				
1.70	FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS)	17.00	Sq.M.		
	Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be fixed onto the ply/Exterior Grade MDF base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.				
1.80	12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	7.00	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1830mm x 2135mm - 2440mm in two leaves, and Partition Doors of approximate size 900 - 1065mm x 2135mm - 2440mm . The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1830mm - 1525mm x 2440mm - 2135mm and Single Door approx. Size: 900mm - 1220mm x 2440mm - 2135mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
2.00	WALL PANELLING:				
2.10	WALL PANELLING IN BANKING HALL	140.00	Sq.M.		
	Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise all Exterior Grade MDF (EG-MDF) cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete.				
	Providing 18mm thick Exterior Grade MDF jamb for door and window openings of suitable depth as per site conditions and laminated with 1mm thk laminate to match design as per partitions.				
	All beech wood members to have NO VOC or LOW VOC white duco paint finish.				
2.20	WALL PANELLING WITH <u>MATT FINISH</u> LAMINATE FOR E-LOBBY:	30.00	Sq.M.		
	Same as item for Laminated Panelling above but to be cladded with 1mm MATT FINISH Laminate from one side to a neat finish as per drawings and directions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
2.40	LACQUERED GLASS WORK FOR E-LOBBY: ATM DIVIDERS	7.00	Sq.M.		
	Providing and fixing in position 12mm toughened lacquered glass (colour - same as per laminate for skirting) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1525mm (h) x 830mm (w) subject to site conditions. The rate is for a finished item of work etc., complete as directed.				
2.50	WALLPAPER	18.00	Sq.M.		
	Providing and fixing approved quality wall paper of washable grade including all adhesive, cutting, pasting etc complete.				
	<i>(Basic price Rs 1100 per smt excluding tax, transportation, wastage, loading / unloading, etc.,)</i>				
	<i>Note : Measurement will be taken only for wall paper actually pasted at site.</i>				
2.60	BAND with 12mm Exterior Grade MDF and Lamination				
	Providing and fixing laminated band onto the existing walls with 12mm Exterior grade MDF fixed directly onto the wall surface and finished with 1.0mm laminate sheet. Including all necessary levelling, additional framework/gattas etc if required etc complete. MDF edges finished with PVC edge banding				
2.61	100mm high	5.00	Rmt		
2.62	300mm high	5.00	Rmt		
3.00	FALSE CEILING:				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
3.10	Grid False Ceiling : Mineral Fibre Tile	80.00	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance \geq 87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm , suitable for Green Building application, with Recycled content of 30% - 45% .				
	The tile shall be laid on <u>Microline / Silhouette profile grid system</u> with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.				
	The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using <u>US Boral / Gyproc / Armstrong suspension system</u> (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				
	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				
3.20	PLAIN GYPSUM FALSE CEILING	130.00	Sq.M.		
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:				

Sl. No	Description	Qty	Unit	Rate	Amount
	27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.				
	The ceiling shall be finished with 2 coats of premium emulsion paint over primer putty etc complete				
3.30	VERTICAL FACES IN FALSE CEILING - UPTO 150mm HEIGHT	200.00	Rmt		
	Same as Plain false ceiling above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				
4.00	STORAGE UNITS:				
4.10	LOW HEIGHT STORAGE UNITS	3.00	Sq.M.		
	Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in 18mm EG-MDF to all members except table top and 25mm block board for table top and 8mm EG-MDF for backing sheet . The top and front facia of the storage unit to have 1mm thick laminate. All other exposed faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
	Storage units shall have a internal horizontal shelf of 19mm block board finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished melanine finish				
5.00	TABLES / COUNTERS				
5.10	BRANCH HEAD TABLE: (Laminate Finish)	1.00	Each.		
	Table : 1950 - 2130mm x 900mm x 760mm				
	Side Runner : 1065 - 1220mm x 450mm x 760mm				
	Providing, making and placing in position Executive Table and Side Table with following specifications.				
	Main Table and side Table top and to be made in 25mm block board with 1mm thick laminate . The front side of the table to have a inverted " C " made with 2 x 18mm thick EG-MDF cladded with 1mm thick laminate on the front and the verticals towards the modesty panel. The modesty panel to have 18mm EG-MDF cladded with 6mm thk toughened lacquered glass in blue colour as specified.				
	The " L " shaped table top on the back side to have 50mm edge around and to be cladded with 6mm acrylic solid surface.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm thick laminate as specified.				
	All the edges of 18mm EG-MDF to have PVC edge banding / BW lipping 20mm x 6mm maline polished .				
	One readymade CPU mobile pedestal .				
	One Molded Key Board Tray with channels etc.,				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding / 20mm x 6mm beech wood edge lipping etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG-MDF and 19mm plywood all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC edge banding / 20mm x 6mm beech wood edge lipping etc				
	All the unexposed faces to have 0.8mm Laminate .				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm .				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
5.20	OTHER OFFICER's EXECUTIVE TABLES: (Laminate Finish)	2.00	Each.		
	Table : 1500 - 1650mm x 760mm x 760mm				
	Side Runner : 915 - 1050mm x 450mm x 760mm				
	Providing, making and placing in position Executive Table and Side Table with following specifications.				
	Main Table and side Table top and to be made in 25mm block board with 1mm thick laminate on top. The front side of the table to have a inverted " U " made with 2 x 18mm thick EG-MDF finished with 1.0mm laminate including the verticals towards the modesty panel. The modesty panel to have 18mm EG-MDF cladded with 1mm Laminate as specified.				
	The " L " shaped table top on the back side along with side tabe to have 49mm edge around, which is to be achieved by adding a 75mm piece of 18mm EG-MDF to the table top from bottom.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1.0mm laminate as specified.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood lipping /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have 3 equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1 no internal shelf made with 18mm EG-MDF and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.30	CLERK TABLE	1.00	Each.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as Officer and Executive table above but for Table top size 1375mm x 610mm x 760mm (h) but without side runner and other specifications remaining the same.				
5.50	GRAHAK MITRA / TECH MITRA TABLE:				
5.51	GRAHAK MITRA TABLE: (Laminate Finish)	1.00	Each.		
	Size : 1220-1525mm x 610-760mm x 760mm				
	Providing, making and placing in position Grahak Mitra Table with following specifications.				
	Main Table Top to have 25mm block board with 1mm thick laminate finish. The vertical supports of the table is to be made with two side boxing of 75mm x 700mm x 950 mm made with 18mm EG-MDF and the front side boxing to 100mm x 400mm x 950mm on either sides and central boxing of 150mm x 420mm x 1050mm, all made with 18mm EG-MDF finished with 1.0mm laminate on exposed sides.				
	The front of the table to have a 420mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick colour RAL-5017-Traffic Blue blue colored lacquered glass.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm Laminate as specified to be used.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.,				
	One pedestal of 400mm width having Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.60	SINGLE WINDOW COUNTERS: (Laminate Finish)	5.00	Each.		
	Counter : 1500-1650mm x 900-975mm x 760mm				
	Side Runner : 1050 - 1220mm x 450mm x 760mm.				

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.				
	Table top of main table and side table to be made in 25mm block board with 1mm thick laminate and double thickness at edges around. The laminate to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	All other members to be with 18mm EG-MDF / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm Laminate as specified in the drawing to be used.				
	Front of SWO Counter to have about 100mm high skirting made of 12mm EG-MDF board fixed at floor level and finished with 1.0mm laminate of dark blue colour				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade CPU mobile pedestal .				
	One Molded Key Board Tray with channels etc.,				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	One Side Table with shutters made with 25mm block board top and 18mm EG-MDF for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate .				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.				

Sl. No	Description	Qty	Unit	Rate	Amount
	Each Single Window Counter to have provision for 12mm thick clear float glass in the front and sides as per relevant item measured separately.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
6.00	12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:	5.00	Each.		
	Providing, making and fixing in position 12mm thick toughened clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size 1650mm x 500mm - 100mm in tapered shape . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
7.00	12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):	5.00	Each.		
	Providing, making and fixing in position 12mm thick clear float glass in the front side and shall be in 2 nos of separate sizes . Lower part shall be fixed with a glass panel of size 1500-1650 x 380mm with a central cut out of 200mm x 150mm. Uppper part shall be fixed with a glass panel of size 1500-1650 x 450mm . A gap of 50mm shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.		(incl 2 nos glass)		
8.00	12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS:	4.50	Sq.M.		
	Providing, making and fixing in position 12mm thick toughened clear float glass in sizes as per design with cut out of 200mm x 150mm at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
	Glass size shall be as per length of low height partiton after leaving about 300mm solid portion at both ends				
	Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW lipping /PVC edge banding etc and fixed onto the low partition with all hardware etc complete				
9.00	WRITING DESK:				
9.10	FLOOR MOUNTED WRITING DESK:	1.00	Nos / each		
	Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 760mm with following specifications.				
	A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm EG-MDF cladded with 1mm Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board cladded with 1mm Laminate which will have verticals made with 12mm EG-MDF cladded with 1mm Laminate upto the table top level of 1050mm from floor level.				
	The Writing Desk Circular Top to have 12mm thk toughened clear float glass with 25mm chamfered bull nosing alround.				
	All members to be with 12mm / 18mm EG-MDF and all exposed faces to have 1mm Laminate as specified.				
	All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	All the unexposed faces to have 0.8mm Laminate.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
15.00	BLINDS				
15.10	ROLLER BLINDS	8.00	Sq.M.		
	Providing and fixing in position of Roller Blinds of approved Fabric of Hunter Douglas / Mac / Vista Levalor make or approved equivalent of approved shade etc., as directed.				
17.00	PLASTIC EMULSION PAINTING	50.00	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
19.00	DESIGNER FILM WORK	50.00	Sq.M.		
	Providing and fixing in position Designer Film on all glasses as per drawings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
26.00	SHUTTER BOXING WITH TRAP DOOR				
	Providing & fixing ..shutter boxing in position made of 9mm ply with framing of Aluminium Tube sections of min 50mm x 25.4mm and 20 gauge 600mm C/C both ways.Laminate thickness of 1 mm ,,minimum. Laminate Brand & Shades to be as per bank's approval. Trap door will be 19 mm marine ply finished with Laminate with required accesories & locking arrangement, complete as directed by Engineer	5	Sq.M.		
28.00	CLEARANCE OF DEBRIS	5.00	loads		
	Clearance of Debris and all Waste materials generated during the execution of the work by Vendors of ALL TRADES, including loading, unloading, carrying away, transportation and disposal to suitable location as per site conditions etc complete				
	<i>(Measurement shall be for Number of Loads of tempo / mini truck actually carried away and duly certified by Bank authorities / Security with GATE PASS.)</i>				
TOTAL (EXCLUDING GST)					