



Client State Bank of India

Project **INTERIOR RENOVATION WORKS FOR STATE BANK OF INDIA AT MUNDAGOD BRANCH.**

SCHEDULE-I

**BILL OF QUANTITY for Interior Renovation Works**

Sl. No	Description	Qty	Unit	Rate	Amount
<b>I</b>	<b>INTERIOR WORKS:</b>				
<b>A</b>	<b>FIXED FURNITURE:</b>				
1.00	<b>PARTITIONS</b>				
1.10	<b>FULL HEIGHT PARTITIONS - PARTLY GLAZED</b>	<b>15.00</b>	Sq.M.		
	Providing and fixing metal stud dry wall partition with following specifications:				
	Supporting system comprising of 51mm / 50mm x 35mm / 24mm x 0.5mm metal studs at 600mm c/c and 51mm /				
	<b>12mm Exterior Grade MDF ( EG-MDF)</b> Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto <b>100 mm</b> from FFL to have <b>1.0mm</b> laminate of <b>dark blue colour</b>				
	From <b>100mm to 300mm</b> level to have <b>1mm Laminate</b> (aqua blue color)				
	From <b>300 mm level to 1070 mm</b> level to have 1mm Laminate (white color)				
	From <b>1070 mm level to 2135 mm</b> level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.The glass sizes subject to design drawing etc.				
	From <b>2135mm level to 2235mm</b> level <b>1mm Laminate</b> (aqua blue color) on both sides as shown in drawing.				
	Partition <b>above 2235mm</b> level to have <b>1mm Laminate (white color)</b> as shown in drawing.				
	All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
1.20	<b>FULL HEIGHT PARTITIONS - SOLID</b>	<b>30.00</b>	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as full height partition partly glazed above but for Fully Solid Partitions without glass panels and other specifications remaining the same. Glass panel area from 1220mm lvl to 2135mm lvl to be replaced with solid partition with 1mm Laminate (white color)				
1.30	<b>HALF HEIGHT PARTITIONS</b>	4.00	Sq.M.		
	<i>This item <b>includes partitions for SWO counters, officer cubicles etc as per the layout plan.</b> Height of the partitions shall be as mentioned in the drawings.</i>				
	Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following:				
	<b>1mm thick laminate on top, 50mm bands of 1mm thick laminate</b> on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto <b>100mm</b> from FFL to have <b>1.0mm</b> laminate of <b>dark blue colour</b>				
	From <b>100mm to 300mm</b> level to have <b>1mm Laminate</b> (aqua blue color)				
	From <b>300mm level to 1070mm</b> level to have <b>1mm Laminate</b> (white color)				
	From <b>1070mm level to 1170mm</b> level <b>1mm Laminate</b> (aqua blue color)				
	From <b>1170mm level to 1220mm</b> level to have 1mm thick laminate on both sides as shown in drawing.				
1.40	<b>DOORS IN PARTITIONS</b>				
1.41	<b>32MM DOORS IN PARTITIONS - with glass panel:</b>	8.40	Sq.M.		
	Providing and fixing <b>32mm thick</b> solid core flush shutter with <b>85mm x 35mm</b> beech wood frame with rebate around the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of <b>8mm clear float glass</b> fixed with 19 x 19mm beading on both sides and glass pasted with 3M <b>privacy film</b> as per design.				

Sl. No	Description	Qty	Unit	Rate	Amount
	The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.				
1.42	<b>32MM DOORS IN PARTITIONS : solid</b>	<b>0.00</b>	Sq.M.		
	Same as <u>32mm Door in Partitions - with glass panel</u> as per above but for <b>Solid door without glass panel</b> and other specifications remaining the same				
1.50	<b>WICKET GATE - for SWO Counters</b>	<b>0.00</b>	Sq.M.		
	<i>Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably</i>				
	Providing wicket gate made of <b>32mm solid flush door</b> with around PVC edge banding / BW lipping and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with <b>85mm x 35mm</b> beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have <b>self lock from inside fixed at lower height</b> as per instructions and Bank requirement				
1.60	<b>CEMENT PARTICLE BOARD (BISON BOARD) PARTITIONS - SOLID PARTITION</b>	<b>0.00</b>	Sq.M.		
	Same as full height partition Solid above but for <b>12mm thk bison board</b> on both sides and other specifications remaining same				
1.70	<b>FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS)</b>	<b>20.00</b>	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing, making and fixing in position <b>Fixed 12mm toughened glass</b> as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be <b>fixed onto the ply/Exterior Grade MDF base with patch fittings</b> and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.				
1.80	<b>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</b>	<b>3.00</b>	Sq.M.		
	Providing, making and fixing in position Fixed <b>12mm toughened glass openable shutters work</b> as per specifications given below and for the openings mentioned. <b>Main Entrance Glass Work</b> comprising of Door opening of approximate size <b>1830mm x 2135mm - 2440mm</b> in two leaves, and <b>Partition Doors</b> of approximate size <b>900 - 1065mm x 2135mm - 2440mm</b> . The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1830mm - 1525mm x 2440mm - 2135mm and Single Door approx. Size: 900mm - 1220mm x 2440mm - 2135mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
2.00	<b>WALL PANELLING:</b>				
2.10	<b>WALL PANELLING IN BANKING HALL</b>	<b>50.00</b>	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise all <b>Exterior Grade MDF (EG-MDF)</b> cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete.				
	Providing <b>18mm thick Exterior Grade MDF jamb</b> for door and window openings of suitable depth as per site conditions and laminated with 1mm thk laminate to match design as per partitions.				
	All beech wood members to have NO VOC or LOW VOC white duco paint finish.				
2.20	<b>WALL PANELLING WITH <u>MATT FINISH</u> LAMINATE FOR E-LOBBY:</b>	<b>34.00</b>	Sq.M.		
	Same as item for Laminated Panelling above but to be cladded with 1mm MATT FINISH Laminate from one side to a neat finish as per drawings and directions etc., complete.				
2.30	<b>COLUMN PANELLING</b>	<b>25.00</b>	Sq.M.		
	Same as item 2.1				
2.40	<b>LACQUERED GLASS WORK FOR E-LOBBY: ATM DIVIDERS</b>	<b>7.00</b>	Sq.M.		
	Providing and fixing in position <b>12mm toughened lacquered glass</b> (colour - same as per laminate for skirting) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be <b>1525mm (h) x 830mm (w)</b> subject to site conditions. The rate is for a finished item of work etc., complete as directed.				
2.50	<b>WALLPAPER</b>	<b>10.00</b>	Sq.M.		
	Providing and fixing approved quality <b>wall paper</b> of washable grade including all adhesive, cutting, pasting etc complete.				
	<i>(Basic price Rs 1100 per smt excluding tax, transportation,wastage, loading / unloading, etc.,)</i>				
	<i>Note : Measurement will be taken <b>only for wall paper actually pasted at site.</b></i>				
2.60	<b>BAND with 12mm Exterior Grade MDF and Lamination</b>				

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing and fixing laminated band onto the existing wallls wth 12mm Exterior grade MDF fixed directly onto the wall surface and finished with 1.0mm laminate sheet. Including all necessary levelling, additional framework/gattas etc if required etc complete. MDF edges finished with PVC edge banding				
2.61	<b>100mm high</b>	<b>13.00</b>	Rmt		
2.62	<b>300mm high</b>	<b>10.00</b>	Rmt		
3.00	<b>FALSE CEILING:</b>				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
3.10	<b>Grid False Ceiling : Mineral Fibre Tile</b>	<b>107.00</b>	Sq.M.		
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm , suitable for Green Building application, with Recycled content of 30% - 45% .				
	The tile shall be laid on <b><u>Microline / Silhouette profile grid system</u></b> with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & “birdsmouth” notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.				
	The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using <b><u>US Boral / Gyproc / Armstrong suspension system</u></b> (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				

Sl. No	Description	Qty	Unit	Rate	Amount
	Flush fitting <b>1200mm long cross tees</b> to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				
3.20	<b>PLAIN GYPSUM FALSE CEILING</b>	<b>160.00</b>	Sq.M.		
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:				
	<b>27 x 37 x 1.6mm</b> Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, <b>20 x 28 x 30 x 0.5mm</b> Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.				
	The ceiling shall be finished with <b>2 coats of premium emulsion</b> paint over primer putty etc complete				
3.30	<b>VERTICAL FACES IN FALSE CEILING - UPTO 150mm HEIGHT</b>	<b>110.00</b>	Rmt		
	Same as Plain false ceiling above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				



Sl. No	Description	Qty	Unit	Rate	Amount
3.40	<b>VENEER FALSE CEILING</b>	<b>0.00</b>	Sq.M.		
	Same as Plain false ceiling but for <b>12mm Plywood</b> instead of Gypsum Board / Standard Plasterboard cladded with <b>4mm Veneer</b> with minimum three coats of melamine spray polish to a finished item of work as per drawings and directions etc., complete.				
	<i>Basic rate for Veneer = Rs. 1000/- per smt excluding tax, transportation, wastage, loading / unloading, etc.,</i>				
3.50	<b>PLYWOOD FALSE CEILING</b>	<b>0.00</b>	Sq.M.		
	Providing and making plywood ceiling with Trap Doors in Ceiling of approximate size 1800mm x 760mm made with 50mm x 50mm hard wood frame and shutter with hard wood frame of 35mm x 35mm with <b>19mm marine quality plywood / block board</b> , the exposed surface of the ceiling to be cladded with 1mm thick laminate of approved shade and painted with enamel paint internally with necessary hardware viz., hinges, safety chain, lock, handle etc., complete as per drawings and directions.				
4.00	<b>STORAGE UNITS:</b>				
4.10	<b>LOW HEIGHT STORAGE UNITS</b>	<b>4.00</b>	Sq.M.		
	Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in <b>18mm EG-MDF</b> to all members except table top and <b>25mm block board</b> for table top and <b>8mm EG-MDF</b> for backing sheet . The top and front facia of the storage unit to have 1mm thick laminate. All other exposed faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete.				
	Storage units shall have a internal horizontal shelf of <b>19mm block board</b> finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished melanine finish				
4.20	<b>Full Height Storage</b>	<b>0.00</b>	Sq.M.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as low height storage unit above <b>but for 2.1m height</b> with internal shelves at every 400mm, without Corian sheet on top, and other specifications remaining the same				
<b>B</b>	<b>LOOSE FURNITURE:</b>				
5.00	<b>TABLES / COUNTERS</b>				
5.10	<b>BRANCH HEAD TABLE: (Laminate Finish)</b>	<b>0.00</b>	Each.		
	<b>Table : 1950 - 2130mm x 900mm x 760mm</b>				
	<b>Side Runner : 1065 - 1220mm x 450mm x 760mm</b>				
	Providing, making and placing in position <b>Executive Table and Side Table</b> with following specifications.				
	Main Table and side Table top and to be made in <b>25mm block board with 1mm thick laminate</b> . The front side of the table to have a inverted " C " made with 2 x <b>18mm thick EG-MDF</b> clad with 1mm thick laminate on the front and the verticals towards the modesty panel. The modesty panel to have <b>18mm EG-MDF</b> clad with 6mm thk toughened lacquered glass in blue colour as specified.				
	The " L " shaped table top on the back side to have 50mm edge around and to be clad with 6mm acrylic solid surface.				
	All other members to be with <b>18mm EG-MDF</b> and all exposed faces of the table to have 1mm thick laminate as specified.				
	All the edges of <b>18mm EG-MDF</b> to have PVC edge banding / BW lipping 20mm x 6mm maline polished .				
	One readymade <b>CPU mobile pedestal</b> .				
	One Molded <b>Key Board Tray</b> with channels etc.,				
	One Three Drawer Unit made with <b>18mm EG-MDF and 12mm EG-MDF</b> . The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding / 20mm x 6mm beech wood edge lipping etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with <b>18mm EG-MDF</b> and 19mm plywood all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC edge banding / 20mm x 6mm beech wood edge lipping etc				
	All the unexposed faces to have <b>0.8mm Laminate</b> .				
	Ready Made Modular <b>Foot Rest - 400mm x 350mm x 65mm</b> .				

Sl. No	Description	Qty	Unit	Rate	Amount
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.20	<b>OTHER OFFICER's EXECUTIVE TABLES: (Laminate Finish)</b>	<b>2.00</b>	Each.		
	<b>Table : 1500 - 1650mm x 760mm x 760mm</b>				
	<b>Side Runner : 915 - 1050mm x 450mm x 760mm</b>				
	Providing, making and placing in position <b>Executive Table and Side Table</b> with following specifications.				
	Main Table and side Table top and to be made in <b>25mm block board</b> with 1mm thick laminate on top. The front side of the table to have a inverted " U " made with <b>2 x 18mm thick EG-MDF</b> finished with 1.0mm laminate including the verticals towards the modesty panel. The modesty panel to have <b>18mm EG-MDF</b> clad with 1mm Laminate as specified.				
	The " L " shaped table top on the back side along with side table to have 49mm edge around, which is to be achieved by adding a 75mm piece of <b>18mm EG-MDF</b> to the table top from bottom.				
	All other members to be with <b>18mm EG-MDF</b> and all exposed faces of the table to have 1.0mm laminate as specified.				
	All the edges of <b>18mm EG-MDF</b> to have 20mm x 6mm beech wood lipping /PVC edge banding.				
	One readymade <b>CPU mobile pedestal</b> .				
	One <b>Molded Key Board Tray</b> with channels etc.				
	One Three Drawer Unit made with <b>18mm EG-MDF</b> and <b>12mm EG-MDF</b> . The unit to have 3 equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1 no internal shelf made with 18mm EG-MDF and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular <b>Foot Rest - 400mm x 350mm x 65mm</b> .				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.30	<b>CLERK TABLE</b>	<b>0.00</b>	Each.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Same as Officer and Executive table above but for Table top size 1375mm x 610mm x 760mm (h) <b>but without side runner</b> and other specifications remaining the same.				
5.40	<b>CROSS SELLING COUNTER</b>				
	Same as Officer and Executive table above but for Table top size as given below and with one pedestal unit for every 1050mm length <b>but without side runner</b> and other specifications remaining the same.				
	1050mm x 610mm x 760mm (h)	0.00	Each.		
	2135mm x 610mm x 760mm (h) with centre vertical support of 18mm thk Exterior Grade MDF laminated	0.00	Each.		
	3150mm x 610mm x 760mm (h) with 2 centre vertical support of 18mm thk Exterior Grade MDF laminated	0.00	Each.		
5.50	<b>GRAHAK MITRA / TECH MITRA TABLE:</b>				
5.51	<b>GRAHAK MITRA TABLE: (Laminate Finish)</b>	1.00	Each.		
	<b>Size : 1220-1525mm x 610-760mm x 760mm</b>				
	Providing, making and placing in position Grahak Mitra Table with following specifications.				
	Main Table Top to have <b>25mm block board</b> with 1mm thick laminate finish. The vertical supports of the table is to be made with two side boxing of 75mm x 700mm x 950 mm made with <b>18mm EG-MDF</b> and the front side boxing to 100mm x 400mm x 950mm on either sides and central boxing of 150mm x 420mm x 1050mm, all made with <b>18mm EG-MDF</b> finished with 1.0mm laminate on exposed sides.				
	The front of the table to have a 420mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick colour RAL-5017-Traffic Blue blue colored lacquered glass.				
	All other members to be with <b>18mm EG-MDF</b> and all exposed faces of the table to have 1mm Laminate as specified to be used.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade <b>CPU mobile pedestal.</b>				
	One Molded <b>Key Board Tray</b> with channels etc.,				

Sl. No	Description	Qty	Unit	Rate	Amount
	One pedestal of 400mm width having Three Drawer Unit made with <b>18mm EG-MDF</b> and <b>12mm EG-MDF</b> . The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular <b>Foot Rest - 400mm x 350mm x 65mm.</b>				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.60	<b>SINGLE WINDOW COUNTERS: (Laminate Finish)</b>	<b>0.00</b>	Each.		
	<b>Counter : 1500-1650mm x 900-975mm x 760mm</b>				
	<b>Side Runner : 1050 - 1220mm x 450mm x 760mm.</b>				
	Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.				
	<b>Table top</b> of main table and side table to be made in <b>25mm block board with 1mm thick laminate</b> and double thickness at edges around. The laminate to continue in the <b>front side with curvature</b> from the front table top to the modesty panel in front with cove lighting provision.				
	All other members to be with <b>18mm EG-MDF</b> / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm Laminate as specified in the drawing to be used.				
	Front of SWO Counter <b>to have about 100mm high skirting made of 12mm EG-MDF board</b> fixed at floor level and finished with 1.0mm laminate of <b>dark blue colour</b>				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade <b>CPU mobile pedestal.</b>				
	One Molded <b>Key Board Tray</b> with channels etc.,				

Sl. No	Description	Qty	Unit	Rate	Amount
	One Three Drawer Unit made with <b>18mm EG-MDF and 12mm EG-MDF</b> . The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	One Side Table with shutters made with <b>25mm block board</b> top and 18mm EG-MDF for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the <b>unexposed faces to have 0.8mm Laminate.</b>				
	Ready Made <b>Modular Foot Rest</b> - 400mm x 350mm x 65mm.				
	All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.				
	Each Single Window Counter to have provision for <b>12mm thick clear float glass</b> in the front and sides as per relevant item measured separately.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
6.00	<b>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:</b>	<b>0.00</b>	Each.		
	Providing, making and fixing in position <b>12mm thick toughened</b> clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size <b>1650mm x 500mm - 100mm in tapered shape</b> . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
7.00	<b>12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):</b>	<b>0.00</b>	Each.		

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing, making and fixing in position <b>12mm thick clear float glass</b> in the front side and shall be in <b>2 nos of separate sizes</b> . Lower part shall be fixed with a glass panel of size <b>1500-1650 x 380mm</b> with a central cut out of 200mm x 150mm. Uppper part shall be fixed with a glass panel of size <b>1500-1650 x 450mm</b> . A <b>gap of 50mm</b> shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.			(incl 2 nos glass)	
8.00	<b>12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS:</b>	<b>0.00</b>	Sq.M.		
	Providing, making and fixing in position <b>12mm thick toughened</b> clear float glass in sizes as per design with <b>cut out of 200mm x 150mm</b> at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.				
	Glass size shall be as per length of low height partiton after leaving about 300mm solid portion at both ends				
	Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW lipping /PVC edge banding etc and fixed onto the low partition with all hardware etc complete				
9.00	<b>WRITING DESK:</b>				
9.10	<b>FLOOR MOUNTED WRITING DESK:</b>	<b>1.00</b>	Nos / each		
	Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 760mm with following specifications.				
	A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in <b>12mm EG-MDF</b> claddded with 1mm Laminate. A top to be provided at 900mm level from floor to be made with <b>25mm Block Board</b> claddded with 1mm Laminate which will have verticals made with <b>12mm EG-MDF</b> claddded with 1mm Laminate upto the table top level of 1050mm from floor level.				

Sl. No	Description	Qty	Unit	Rate	Amount
	The Writing Desk Circular Top to have <b>12mm thk toughened</b> clear float glass with 25mm chamfered bull nosing around.				
	All members to be with <b>12mm / 18mm EG-MDF</b> and all exposed faces to have 1mm Laminate as specified.				
	All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	All the unexposed faces to have 0.8mm Laminate.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
9.20	<b>WALL MOUNTED WRITING DESK:</b>	<b>0.00</b>	Nos / each		
	Providing, making and placing in position Wall Mounted Writing Desk 760mm x 300mm x 450mm with following specifications.				
	The entire unit is to be made with <b>18mm EG-MDF</b> clad with 1mm Laminate as per drawing.				
	The Writing Desk to have <b>12mm thick toughened</b> clear float glass with 25mm chamfered bull nosing around at top fixed with SS supports.				
	All members to be with <b>18mm EG-MDF</b> and all exposed faces to have 1mm Laminate as specified.				
	All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	All the unexposed faces to have 0.8mm Laminate OR members of beech wood to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
10.00	<b>SIDE TABLE</b>	<b>0.00</b>	Nos/each		
	<b>610 x 610 x 450mm (H) Laminate</b>				
	Manufacturing and supplying <b>side tables</b> as per the following specifications.				
	Side Table top overall size 610 x 610mm <b>made of 25mm BB and fixed with 8mm thk glass on top.</b>				
	All glass edges shall be machine polished.				
	Support structure with 4 nos legs of B.W 50 x 50mm and horizontal ties around at top and bottom of B.W 37.5 x 37.5.				
	All edge beadings, nails, screws, adhesives etc. All wooden surfaces finished with melamine spray polish.				
11.00	<b>CENTRE TABLE</b>	<b>0.00</b>	Nos/each		



Sl. No	Description	Qty	Unit	Rate	Amount
	<b>450 x 910 x 450mm (H) - Laminate</b>				
	Manufacturing and supplying <b>center tables</b> as per the following specifications.				
	Table top overall size 450 x 910mm <b>made of 25mm BB and fixed with 8mm thk glass on top..</b>				
	Support structure with 4 nos legs of B.W 50 x 50 and horizontal ties around at top and bottom of B.W 37.5 x 37.5				
	All edge beadings, nails, screws, adhesives etc. All wooden surfaces finished with melamine spray polish.				
	Table top shall be provided with <b>6mm thk clear glass and cut to table top shape</b> . All glass edges shall be machine polished.				
12.00	<b>DINING TABLE</b>				
	Providing and fixing Dining / Cash Room Table with Table top of <b>25mm thk BB</b> of size as given below and fixed on the <b>BEECHWOOD supporting frame</b> with screws, bolts etc and PVC edge banding / beading as required				
	Supporting frame made of <b>50mm x 50mm beechwood - 4nos legs</b> joined together <b>around at top/ bottom</b> with 50mmx50mm beechwood members for fixity.				
	<b>All visible surfaces</b> to be finished with <b>1.0mm thk laminate</b> sheet and all <b>internal and underside surfaces</b> to be fixed with <b>0.8mm thick lamination</b> sheet with matching grains & grooves polished with melamine spray.				
	All wooden members to be polished with melamine finish complete.				
	SIZE				
12.10	<b>1220 X 610 X 760</b>	<b>0.00</b>	Nos / each		
12.20	<b>1375 X 610 X 760</b>	<b>0.00</b>	Nos / each		
12.30	<b>1525 X 610 X 760</b>	<b>0.00</b>	Nos / each		
13.00	<b>CASH TABLE</b>				
	Same as above but with additional pencil drawer of <b>width-610mm and depth-100mm, made out of 12mm EG-MDF laminated</b> , and other specifications remaining same				
	SIZE				
13.10	<b>1220 X 610 X 760</b>	<b>0.00</b>	Nos / each		
<b>C</b>	<b>OTHER WORKS:</b>				
14.00	<b>6mm thk SOLID ACRYLIC SHEET (COREAN) ON EXISTING SURFACE</b>				

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing and fixing <b>6mm thk Solid Acrylic Surface sheets (COREAN)</b> onto the existing BB / Exterior Grade MDF / plywood base with all necessary adhesives and including cutting, chamfering, chasing, buffing, polishing etc complete. The finished surface shall be seamless and in perfect line and level complete all as per manufacturers standard for the finished product				
14.10	<b>For more than 150mm</b> wide sheet	<b>0.00</b>	Smt		
14.20	<b>For less than 150mm</b> wide sheet but more than 75mm wide	<b>0.00</b>	Rmt		
14.30	<b>For less than 75mm</b> wide sheet	<b>0.00</b>	Rmt		
15.00	<b>BLINDS</b>				
15.10	<b>ROLLER BLINDS</b>	<b>9.00</b>	Sq.M.		
	Providing and fixing in position of <b>Roller Blinds</b> of approved Fabric of Hunter Douglas / Mac / Vista Levalor make or approved equivalent of approved shade etc., as directed.				
15.20	<b>VERTICAL BLINDS</b>	<b>0.00</b>	Sq.M.		
	Providing and fixing approved fine quality and shade <b>vertical blinds</b> of Hunter Douglas / Mac / Vista Levalor make or approved equivalent make made of special fabric 100mm wide including all channels, tilting mechanism etc., and all standard fittings and fixtures as per manufacturers standard specification.				
16.00	<b>FLOORING</b>				
16.10	<b>WOODEN FLOORING</b>	<b>0.00</b>	Sq.M.		
	Providing and fixing laminated wooden flooring as per and equivalent to the following				
	Providing and fixing laminated wooden flooring with <b>AC-4 GRADE</b> and with plank size apprx 1200 x 200 and having locking arrangement at plank joints. Flooring to be laid on a underlayer of foam with all accessories like end profile, Transition profile, reducer, stair nosing etc complete.				
	<b>INSTALLATION:</b> It is important to ensure the sub floor on which the planks are being laid is smooth, flat & hard & free from moisture, greases, etc. In case of uneven sub floor the same should be leveled by self leveling compound. The tougue & groove joints shall be glued together using reccomended adhesive. The installation shall be undertaken as per the manufacturer's installation instructions.				

Sl. No	Description	Qty	Unit	Rate	Amount
	<i>(Basic price Rs 1000 per smt excluding tax, transportation, wastage, loading / unloading, etc.,)</i>				
17.00	<b>PLASTIC EMULSION PAINTING</b>	<b>50.00</b>	Sq.M.		
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
18.00	<b>TEXTURE PAINTING</b>	<b>0.00</b>	Sq.M.		
	Cleaning the surface of the wall & applying <b>TEXTURE PAINT of Asian Paints - Royale Play (Special Effects) or Berger - Silk Illusions</b> in approved design and shade - <b>with Base coat and Top coat</b> including all primer, putty, necessary materials, labour, tools and plants, etc complete as per manufacturers specifications.				
19.00	<b>DESIGNER FILM WORK</b>	<b>35.00</b>	Sq.M.		
	Providing and fixing in position <b>Designer Film</b> on all glasses as per drawings and heights mentioned. The Designer Film is of <b>Harmony / 3M</b> or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
20.00	<b>POP COVERING</b>	<b>0.00</b>	Sq.M.		
	Providing and spreading POP layer of <b>3mm to 5mm</b> over the existing <b>vitriified flooring</b> and removing the same after completion of the Interior work including cleaning the floor etc., complete as directed.				
21.00	<b>DRESSING MIRROR</b>	<b>0.00</b>	Nos / each		
	Providing and fixing Dressing Mirror with 4mm mirror of approx size <b>760 x 1220mm</b> pasted on 12mm EG-MDF sheet and fastened to wall surface with SS studs including polished /chamfered edges for mirror, PVC edge banding for EG-MDF and all accessories etc complete				
22.00	<b>DRESSING TABLE</b>	<b>0.00</b>	Nos / each		

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing Dressing Table of size <b>380 x 915mm x 450 (H)</b> made of 25mm BB top and 18mm EG-MDF vertical supports including additional 100mm bands at front and back for support and all visible surfaces laminated with 1.0mm laminate sheet including all hardware etc complete				
23.00	<b>DRESSING STOOL</b>	<b>0.00</b>	Nos / each		
	Providing Dressing Stool of size <b>380 x 380mm x 380 (H)</b> made of <b>25mm BB</b> top and side vertical supports including additional cross vertical support at centre and all visible surfaces laminated with 1.0mm laminate sheet including all hardware etc complete				
24.00	<b>ENTRANCE - VINYL SCRAPER MATTING:</b>	<b>0.00</b>	Nos / each		
	Providng, fixing in position 3M™ Nomad™ Scrapper Matting 7150, Gray / Red. <b>Entrance coiled vinyl scrapper matting</b> designed for heavy traffic applications over the existing flooring to a neat finished job as per drawings and directions etc., complete.				
	Size - 1200 x 600				
25.00	<b>ACP CLADDING</b>	<b>0.00</b>	Sq.M.		
	Supplying and fixing aluminium composite cladding with skin material <b>0.5 mm thick aluminium sheet</b> cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work but excluding cost of structural steel fabrication, if any. ACP Cladding - 4 mm thick.				
26.00	<b>ACRYLIC LOGO:</b>	<b>0.00</b>	Nos / each		
	Providing SBI Logo-diameter as indicated below, made with <b>6mm Blue color (as per SBI standard logo colour)</b> acrylic sheet, and fixed onto the existing base ACP / wall / partitions as per site and as per drawings and directions etc., complete.				
	<b>SIZE (apprx) - 600 x 1220 mm</b>				
26.00	<b>SHUTTER BOXING WITH TRAP DOOR</b>				

Sl. No	Description	Qty	Unit	Rate	Amount
	Providing & fixing shutter boxing in position made of 9mm ply with framing of Aluminium Tube sections of min 50mm x 25.4mm and 20 gauge 600mm C/C both ways.Laminate thickness of 1 mm ,,minimum. Laminate Brand & Shades to be as per bank's approval. Trap door will be 19 mm marine ply finished with Laminate with required accesories & locking arrangement, complete as directed by Engineer	20	Sq.M.		
27.00	<b>SHIFTING EXISTING COUNTERS / CABINS</b>				
	Dismantling and shifting existing counters, tables, partitions etc and temporarily re-erecting in alternate location on the same floor, or upper/lower floor as per site, including counters, partitions, glass, doors, wicket gate, loose tables, storage units etc complete and made suitable for Bank's temporary working during the project execution period.				
27.10	<b>for small branch - with upto 3 banking counters + cabins, loose tables etc</b>	0.00	LS		
27.20	<b>for medium branch - with upto 7 banking counters + cabins, loose tables etc</b>	1.00	LS		
27.30	<b>for large branch - with upto 12 banking counters + cabins, loose tables etc</b>	0.00	LS		
28.00	<b>CLEARANCE OF DEBRIS</b>	5.00	loads		
	Clearance of Debris and all Waste materials generated during the execution of the work by Vendors of ALL TRADES, including loading, unloading, carrying away, transportation and disposal to suitable location as per site conditions etc complete				
	<i>(Measurement shall be for Number of Loads of tempo / mini truck actually carried away and duly certified by Bank authorities / Security with GATE PASS.)</i>				
29.00	<b>EMBEDDING OF SAFE</b>				
	Providing and laying in position cement concrete of 1:2:4 including the cost of centering and shuttering for 5 sides all round FBR Defender Safe of 150mm thickness with single layer of 12mm dia re-bar at 150mm c/c bothways at the centre; including cost of materials,labour charges,conveyance,curing and necessary shifting charges of FBR safe etc. complete to satisfaction of Engineer and as per drawing.	.00	L.S		
<b>TOTAL(Excluding GST)</b>					

Client : State Bank of India

Project : **INTERIOR RENOVATION WORKS FOR STATE BANK OF INDIA AT MUNDAGOD BRANCH.**

SCHEDULE-III

**BILL OF QUANTITY for PATCHWORK ITEMS (REPAIR and RENOVATION WORKS)**

Sl. No	Description	Qty	Unit	Rate	Amount
<b>1.00</b>	<b>PARTITIONS</b>				
1.10	<b>EXTENDING EXISTING PARTITIONS</b>	<b>0.00</b>	Sq.M.		
	Providing and fixing SOLID / PARTLYGLAZED partitions <b>onto / in continuation of the existing Partition</b> with GI framework made to suitable size and secured firmly to existing partition with all necessary hardware etc as required				
	<b>12mm Exterior Grade MDF ( EG-MDF)</b> Board fixed on both sides with dry wall screws				
1.20	<b>PARTIALLY DISMANTLING EXISTING PARTITION</b>	<b>0.00</b>	Sq.M.		
	Dismantling existing Partition <b>in PART</b> in order to reduce height or length <b>without damaging</b> the residual portion of partition. The work shall be carried out by cutting existing partitions as				
<b>2.00</b>	<b>LAMINATION ON EXISTING SURFACES</b>				
2.10	<b>PARTITIONS-DOORS-WICKET GATE</b>	<b>60.00</b>	Sq.M.		
	Providing and fixing <b>6mm</b> thk Exterior Grade MDF ( <b>EG-MDF</b> ) onto the existing <b>Partitions, Door Surfaces Etc</b> with necessary screws, hardware and pasting 1.0mm thick laminate sheet as per design with <b>suitable adhesives</b> etc complete(measurement taken for the partitions and doors as in usual case) after removing them from their current location and shifting them to the desired location				
2.20	<b>STORAGE</b>	<b>3.00</b>	Sq.M.		
	Providing and fixing 1.0mm thick laminate sheet onto the existing <b>Storages</b> ( providing 6mm thick exterior grade MDF wherever necessary) including cleaning the surface, sanding the existing laminate sheet <b>with power tools</b> , and pasting 1.0mm the new laminate sheet ( providing 6mm thick exterior grade MDF wherever necessary)as per design with <b>suitable adhesives</b> etc complete. Item includes removing drawers, shutters, glass etc if required and re-fixing the same in position after lamination. The storage units are to be removed from the current location and shifted to desired location.				
<b>3.00</b>	<b>EXTERIOR GRADE MDF + LAMINATION ON EXISTING SURFACES</b>				
3.10	<b>PARTITIONS-PANELLING-DOORS Etc</b>	<b>0.00</b>	Sq.M.		

	Providing and fixing <b>6mm</b> thk Exterior Grade MDF ( <b>EG-MDF</b> ) onto the existing <b>Partitions, Panelling, Door Surfaces Etc</b> with necessary screws, hardware and pasting 1.0mm thick laminate sheet as per design with <b>suitable adhesives</b> etc complete				
3.2	<b>TABLES-COUNTERSEtc</b>				
	Providing and fixing 1.0mm thick laminate sheet onto the existing <b>Tables-Counters Etc</b> including cleaning the surface, sanding the existing laminate sheet <b>with power tools</b> , and pasting 1.0mm the new laminate sheet as per design with <b>suitable adhesives</b> etc complete. Item includes removing drawers, shutters, glass etc if required and re-fixing the same in position after lamination.				
	Single window counters	<b>4.00</b>	Nos		
	Side tables of single window counters	<b>4.00</b>	Nos		
	Branch Manager Table	<b>1.00</b>	Nos		
	Officer table	<b>3.00</b>	Nos		
	side tables of Branch Manager and officers	<b>4.00</b>	Nos		
	Grahak Mitra table	<b>0.00</b>	Nos		
4.00	<b>FALSE CEILING:</b>				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
4.10	<b>REMOVING AND REFIXING GRID CEILING</b>	<b>0.00</b>	Sq.M.		
	<b>Removing</b> existing GRID and MINERAL FIBRE TILES CEILING, in full or in part as directed, including tiles, framework, main runners, cross tees, tiles etc complete, storing the same carefully, and <b>re-fixing</b> in position after completion of works by other agencies. Item includes minor repairs to grid and re-fixing in perfect line and level. <i>(Damaged tiles shall be replaced and measured under separate item elsewhere in this BOQ)</i>				
4.20	<b>PROVIDING NEW MINERAL FIBRE TILES IN EXISTING GRID</b>	<b>0.00</b>	Each.		
	Providing and Fixing NEW MINERAL FIBRE TILES in Existing Grid and of style and design to match existing tiles, including all tools and plants, and matching level to existing ceiling etc complete.				
4.30	<b>CUTTING and RE-DOING GYPSUM FALSE CEILING</b>				
	Cutting existing Gypsum false ceiling including gypsum board, framework etc and <b>re-doing the same</b> as per design to accommodate Int/Elec/AC works, with suitable support including matching of surface level and finishing joints with jointing tape, sanding etc complete				

4.40	Cutting and re-doing Gypsum False Ceiling - <b>upto 1.0 smt</b> (at one location)	<b>0.00</b>	Each.		
4.50	Cutting and re-doing Gypsum False Ceiling - <b>upto 3.0 smt</b> (at one location)	<b>0.00</b>	Each.		
4.60	Cutting and re-doing Gypsum False Ceiling - <b>upto 5.0 smt</b> (at one location)	<b>0.00</b>	Each.		
	Dimension of dismantled / cut ceiling shall be considered for measurement under this item				
	<i>(The ceiling shall be finished with <b>2 coats of premium emulsion paint over primer putty etc complete measured separately under relevant item elsewhere in this BOQ</b>)</i>				
<b>5.00</b>	<b>REPLACING HARDWARE</b>				
	Removing old and damaged hardware from existing furniture, doors, tables, storage etc and replacing with new hardware of matching style and design including removing and re-fixing drawers, shutters, doors etc as required.				
5.10	<b>Handles upto 150mm</b> length	<b>5.00</b>	Each.		
5.20	<b>Handles 150-300mm</b> length	<b>5.00</b>	Each.		
5.30	Storage Unit / Drawer <b>Locks</b>	<b>5.00</b>	Each.		
5.40	Storage Unit / Drawer <b>Self-Locks</b>	<b>5.00</b>	Each.		
5.50	Drawer <b>Sliding Channels</b> (pair)	<b>5.00</b>	Sets		
5.60	Storage Unit <b>Hinges</b>	<b>5.00</b>	Each.		
5.70	Door <b>Dead Lock</b>	<b>5.00</b>	Each.		
5.80	Door <b>Mortice</b> Lock with handle	<b>3.00</b>	Each.		
5.90	Keyboard Tray	<b>5.00</b>	Each.		
6.00	CPU Trolley	<b>3.00</b>	Each.		
6.10	Door Closure	<b>3.00</b>	Each.		
6.20	Floor Spring	<b>1.00</b>	Each.		
6.30	Door Stopper-SS	<b>4.00</b>	Each.		
6.40	Door <b>Hinges</b>	<b>3.00</b>	Each.		
<b>6.00</b>	<b>PLASTIC EMULSION PAINTING to GYPSUM CEILING</b>	<b>0.00</b>	Sq.M.		
	Cleaning the surface, applying jointing tape to cracks, applying primer, putty and <b>2 coats</b> of Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
<b>7.00</b>	<b>RE-POLISHING WOODWORK</b>				
	Cleaning, sanding the surface, and Re-polishing with matching shade including melamine finish complete				
7.10	Beadings upto <b>25 x 25 mm</b>	<b>0.00</b>	Rmt		
7.20	Beadings upto <b>25 x 50 mm</b>	<b>0.00</b>	Rmt		
7.30	Door Frames upto <b>75 x 150 mm</b>	<b>0.00</b>	Rmt		
7.40	Cover Beadings (on low partitions) upto <b>18 x 125 mm</b>	<b>0.00</b>	Rmt		
7.50	Veneers Surfaces	<b>0.00</b>	Sq.M.		
<b>8.00</b>	<b>REPLACING FLOOR TILES</b>	<b>0.00</b>	Sq.M.		



	Chipping and Carefully removing existing Vitrified Floor Tiles and Re-placing the same with new tile of matching size and colour including adhesive etc complete				
<b>9.00</b>	<b>GROUTING TO TILE JOINTS</b>	<b>0.00</b>	Rmt		
	Providing <b>grouting in the existing flooring tile joints</b> with matching colour grout including scraping away the old grout, cleaning the joints and applying new grout etc complete.				
	<b>TOTAL(Excluding GST)</b>				

Client : State Bank of India  
Project : INTERIOR RENOVATION WORKS FOR STATE BANK OF INDIA AT MUNDAGOD BRANCH.

SCHEDULE-IV

**BILL OF QUANTITY : REBATE for material dismantled and carried away by the contractor**

Sl. No	Description	Qty	Rate	Unit	Amount
	<b>SALVAGE VALUE</b> (rebate to be offered by contractor) for dismantling the following items and carrying away to the contractors own premises.				
	<i>(The Amount quoted shall be paid to the bank for carrying away the materials under this item. Hence rate to be with a MINUS SIGN and <b>deducted from the total amount</b>)</i>				
1.00	Partitions	0.00		Smt	
2.00	Panelling including framework	75.00		Smt	
3.00	Vertical blinds	10.00		Smt	
4.00	<b>Storage units</b>				
4.10	Low height storage	0.00		Smt	
4.20	Full height storage	0.00		Smt	
5.00	False ceiling	99.00		Smt	
6.00	Tables of different sizes - (up to 1.80 mtr long)	0.00		Nos	
7.00	Tables of different sizes - (beyond1.8mtr long)	1.00		Nos	
8.00	Side runners of different sizes	0.00		Nos	
9.00	Counters	0.00		Rmt	
10.00	Chairs	0.00		Nos	
	<b>Total (EXCLUDING GST)</b>				