

	BILL OF QUANTITIES FOR INTERIOR FURNISHING WORKS AT STATE BANK OF INDIA, SUKHPURA CHOWK BRANCH, ROHTAK. HARYANA.				
	Item of Work	Qty	Unit	Rate	Total Amount
1	Wooden Partitions with Laminate				
	<p>Low/Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate of APPROVED make in specified pattern as per interiors details on both sides .</p>				
	<p>Also 2 1/2"X5/8" teak wood section shall be provided with 12mm thk. glass with etching work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood. Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</p>	32.00	Sq.mt		
2	Single Level SWO Counters	6.15	Rmt		
	<p>Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF</p>				
	<p>beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer block board and</p>				
	<p>finished with 6mm thk. flexi ply as base for acrylic sheet as/design with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.</p>				
	<p>Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finsihed</p>				

	Item of Work	Qty	Unit	Rate	Total Amount
	with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.				
3	Providing and fixing (12mm thick) white acrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including buffing and wastage. (Make: Du-Pont.,_Glaciar White_)	9.30	Sq.mt		
4	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides. Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.	5.50	Sq.mt		
5	Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.	6.00	No.s		
6	Fixed Toughned Glass Partitions Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors as per manufacturers guidelines of (Godrej/Dorma/Ozone/Stanley) make,rested on 12 mm x 25 mm 'U' channel grouted with in floor surface,fixed in position, as per interior details & recessed in ceiling fixed as per the instruction of the Achitect/Engineer in charge.	5.00	Sq.mt		
7	Wall Connecting Profile Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass.,make: DORMA/OZONE	8.00	Rmt		
8	Toughned Glass Doors Providing & Fixing Openable 12mm thk. Toughned Glass Door,holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make,fixed in position as per manufacturers guidelines. The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.	7.80	Sq.mt		
9	Wall Paneling Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be				

	Item of Work	Qty	Unit	Rate	Total Amount
	clad with 12.0 mm thick commercial ply/12mm thk. water proof MDF as per detail and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape.				
	The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc.				
i.	Panelling with laminate	60.00	Sq.mt		
ii	Panelling with 12mmMDF with Spray Paint/Texture	18.00	Sq.mt		
10	Officer's & Staff Tables Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); with 35mm thk. Post forming top, as per drawing and thickness made by joining two boards.. The front of the table top shall be projected as per drawing. The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The PVC Edge binding tape will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and PVC Edge binding tape on two visible sides. three lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 0.8mm thk. laminate of white/off white shade.				
a	Size 5'0" X 2'6" X 2'6"	3.00	Nos		
b	Size 6'0" X 3'0" X 2'6"	1.00	Nos		
C	Size 9'0" X 2'0" X 2'6"/3'-0" split lvl for sales	1.00	Nos		
11	8.0 MM thk glass on top of officers tables. All the edges of the glass shall be grinded polished including Hole for cable manager.	5.50	Sq.mt		

	Item of Work	Qty	Unit	Rate	Total Amount
12	Side Credenza Providing & fixing Side credenza (15" to 18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make.				
	The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
a	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	4.50	Rmt		
13	Back credenza / Storage Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 30"/36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have draweres 4"high, horizontally	14.00	Sq.mt		
	running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be				
	provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment				
	MISCELLANEOUS				
14	Softboard Providing and fixing in position soft baord (12mm) including fabric cover wooden beading of size 25mmx 19mm on all sides finished with polish of approved shade(Basic rate Rs. 175/- per mtr.)	10.00	Sq.mt		
15	Frosted Film Providing and fixing 3 M make decorative film on glass of approved shade as per architect's instruction with grooves etc. all completed. Note Actual area of film installed will be measured and paid . No wastage will be considered	18.00	Sq.mt		
16	MDF JALI Making and fixing in position (as per approved sample) Laser Cut Jaali partition to be made out of MDF board of 8mm. thickness and make. All exposed surfaces to be finish with clear gloss Verinlengo paint as per approved shade . All complete as/ design to the entire satisfaction ofArchitect/ Engineer in charge (Elevation area to measure).	12.00	Sq.mt		
17	ALUMINUM SHUTTERS FOR ELECTRICAL PANEL with LOUVERS Providing and fixing aluminum shutters over Aluminum frame with frame of section size of 115mm x 45mm in 16	7.00	Sq.mt		

	Item of Work	Qty	Unit	Rate	Total Amount
	gauge with Aluminum louvers of 77.6mm x 27.6mm of weight 0.483/m including powder coating of selected shade and all desired hardware of approved make fixed at site complete in all respects to the satisfaction of Architect., Engg. in Charge				
18	Lacquered Glass panels on SS studs : Providing and fixing 6mm thick Lacquered glass fixed with SS studs and Dow Corning make Neutral Silicone sealant 896 over the frame of 12mm thk. Comm.ply fixed against the wall as panelling as per the drawing to complete satisfaction of the Architect/Bank Engg. in charge. (Make: Saint gobain/AIS)	5.20	Sq.mt		
19	Door Closer - Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	9.00	Nos		
20	Mortice Lock -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.	5.00	Nos		
21	Gypsum Board False Ceiling				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level.The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MFS) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MFS of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at				
	1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.				
	The gypsum board layers are screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. AIC ducting etc.				
	The work includes painting with 2 coats of plastic emulsion to give an even & finished surface. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge. NOTE: NO EXTRA CHARGES WILL BE PAID FOR COVE OR DESIGN.	150.00	Sq.mt		
22	False Ceiling - (Mineral Fibre) Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by aners at 600 mm c/c to form 1200 mm X 600 mm modules.	54.00	Sq.mt		

	Item of Work	Qty	Unit	Rate	Total Amount
	approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runCut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				
23	Teak Ply Ceiling (Teak Veneer @ 75/- sq.ft)				
	Providing and fixing 4mm thk. teak veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes espirit polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	18.00	Sq.mt		
24	Roller Blinds of Vista Make	8.50	Sq.mt		
	Providing & Fixing SHEER SERIES BLINDS Vista Make Delux Collection Composition : 100% Polyester ., Finished Width : 300 CM., Weight : 200 GSM., Thickness : 0.35 Mm,Colour Fastness to light: 4-5 Grade with supporting framework etc. of Bshade & colour complete in working order as per manufacturers specifications & drawings & directions of the Architect.				
25	Plastic Emulsion Paint				
	Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more				
	coats of plstic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Architect/Engineer-In-Charge).	60	Sq.mt		
	Make:- Asian paints/ICI Dulux/Nerolac.				
26	TEXTURE WORK on walls				
	Providing and applying texture work of Asian/Okinis make Royale Play/ metallic/pearl/, ready mixed material with synthetic binders, applied manually with spatula uniformly on to the wall surfaces, complete as per instructions of the architect / Bank's Engineer.	70	Sq.mt		
27	Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box	1.00	Nos		
	Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings				
	made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.				

	Item of Work	Qty	Unit	Rate	Total Amount
28	Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. (Kutty flush doors & furniture co. Pvt Ltd.paonta sahib, distt.	1.95	Sq.mt		
a	Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).				
b)	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge,				
	with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).				
c	Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.)				
29	Panelling With Aluminium Composite Panels (With Aluminium Frames) Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scafoulding, labour, material, complete.	54.00	Sq.mt		
30	P/F and fixing of Golden Steel letters as per approval. The work includes fixing od the same at site with stencil marking as required., complete in all respects to the satisfaction of Engg. In charge/Architect. The size shall be measured in running inches per letter and of the longer side.The work includes removal of existing letters and re- alignment if same as per approval.	120	R.inch		

	Item of Work	Qty	Unit	Rate	Total Amount
31	P/F and fixing of Planter Boxes : made of 19mm thk. Commercial ply, cladded with teak veneer from outside, including teak wood margin/gola as per detail and all inside surface to be finished with aluminium sheet, as per instructions of the architect / Bank's Engineer.	3.25	Sq.mt		
	TOTAL				