

**Schedule of Quantities for Interior Furnishing Works for Renovation
of Treasury Branch, Kakinada, East Godavari District.**

S.No	Description of Item	Unit	Qty	Rate(₹)	Amount(₹)
1	<p>Single Window Counters with Side Unit: Providing, fixing in position 1500mm to 1600mm(w) x 900mm -975mm(d) x 750mm (h) Single Window Counters along with side unit of size 1050mmx 450mmx 750mm made up of 18mm thick EXTERIOR GRADE MDF board with specifications as mentioned below:</p> <p>Counter and side unit top to have 25mm Block Board to have extra edge thickening with 18mm x 50mm (horizontal) MDF Exterior Grade Board and vertical to have 12mm x 49mm MDF Exterior Grade Board lipping clad with 6mm thick acrylic solid surface for the entire counter top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision (As shown in drawing).</p> <p>Front facia of the counter should be provided with and 1mm thick blue glossy laminate</p> <p>All other members to be with 18mm MDF Exterior Grade Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface as specified in the drawing to be used.</p> <p>One Three Drawer Unit made with 18mm</p>	Nos	5		

	<p>MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>One Side Table with shutters made with 25mm block board top and 18mm MDF Exterior Grade Board for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 18mm x 12mm beech wood edge lipping etc.,</p> <p>All edges of 18mm thick external grade MDF board to have 18mm x 12mm MDF exterior grade edge lipping.</p> <p>Fixing in position 2 Nos. 12mm thick toughened glass in the front side (perpendicular to each other along width of counter in horizontal and vertical directions) of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm (in vertical glass) . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets.</p> <p>The counter should be provided with Readymade modular foot rest (400mmx350mmx65mm), molded keyboard tray with channels, mobile CPU Stand, wire manger etc All wooden members to have minimum two coats of NO VOC or LOW VOC duco paint finish. All the unexposed faces to have 0.8mm Laminate</p> <p>The cost to include the "L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.</p>				
--	---	--	--	--	--

2	<p>Branch Manger's Table with Side Unit: Providing, making and placing in position Executive Table and Side Table of approximate size 2400mm - 2100mm x 900mm x 750mm + 1200mm - 1050mm x 450mm x 750mm with following specifications.</p> <p>Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a " C " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm thick designer laminate of basic cost (₹700/ Sq.Mt)</p> <p>The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used. All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping. One readymade CPU mobile pedestal. One Molded Key Board Tray with channels Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. etc.,</p> <p>One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to</p>	Nos	1		
---	--	-----	---	--	--

	<p>have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>One Side Table with shutter unit of 600mm with 2 drawers and two openable shutters made with 18mm MDF Exterior Grade Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>All the unexposed faces to have 0.8mm Laminate.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
3.0	<p>Officer Table with Side Unit: Providing & fixing in position 1500mm to 1650mm (L) x 750mm (H)x750mm (W) + 1050mm x 450mm x 750mm with the following specifications:</p> <p>Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " U " made with 2 x 18mm thick MDF Exterior Grade Board clad with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board clad with 1mm Glossy Laminate and 1mm Laminate as specified.</p> <p>The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical fascia to have 12mm x 43mm MDF Exterior Grade Board lipping clad with 6mm thick acrylic solid surface for the entire table top and the front fascia and</p>	Nos	6		

	<p>remaining all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used.</p> <p>All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p> <p>One readymade CPU mobile pedestal, One Molded Key Board Tray with channels , Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. etc.,</p> <p>One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>One Side Table with shutter unit of 600mm, with 2 drawers and two openable shutters made with 18mm MDF Exterior Grade Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>All the unexposed faces to have 0.8mm Laminate</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
--	--	--	--	--	--

4.0	<p>FULL HEIGHT PARTLY GLAZED PARTITIONS: Providing & fixing in position metal stud dry wall partition with the following specifications:</p> <p>A) Supporting system comprising of 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings.</p> <p>B) 12 mm Exterior grade MDF plywood fixed on both sides with 25 mm dry wall screws.</p> <p>C) 1 mm thick designer laminate of basic cost ₹600/Sq.M of given color(s) n shade(s) on both sides up to false ceiling level.</p> <p>D) 8mm thick clear float glass with 85mm x 18mm al-round MDF exterior grade jamb and 12mm x 2mm MDF exterior grade button beading on both sides of glass to a neat finishing for heights between 900mm and 2100mm. The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.</p> <p>E) All the MDF jamb and button beading should be finished with duco paint finish.</p>	Sq.m	22.0		
5.0	<p>FULL HEIGHT PARTLY GLAZED PARTITIONS: (Premium Laminate) Same as that of Specifications of full height partly glazed partitions as above but the finishing with premium laminte of basic cost 700/Sq.M</p>	Sq.M	22.0		

6.0	Full height solid partitions: Same as the specification for Full height partly glazed partition but the entire height of partition is to be provided with 12mm thick exterior grade MDF board finished with laminate of 1mm thick glossy laminate of given color(s) and design on one side and 12mm thick Cement Fibre board with putty, primer and two coats of paint in given pattern.	Sq.m t	38.0		
7.0	Full height solid partitions: Same as the specification for Full height partly glazed partition but the entire height of partition is to be provided with 12mm thick Cement Fibre board on both sides with putty, primer and two coats of paint in given pattern.	Sq.M t	40.0		
8.0	Low Height Partition: Providing & fixing metal stud low height Partitions with following specifications. a) Supporting system comprising of 51 X 35 mm metal studs (of approved make) at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should include necessary strengthening with studs/tracks or channels at openings. b) 12 mm exterior grade MDF BOARD with 1mm glossy laminate on both sides. c) 85x18 mm exterior grade wooden jamb on all-round partition finished with duco paint the partition will have 12 mm clear float glass fixed with SS "D" brackets, from 900mm level to 1200mm level. The glass to be finished with designer film with ellipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.	Sq.m t	45.0		
9.0	FULL HEIGHT FULLY GLAZED PARTITIONS: Providing & fixing in position 12MM TOUGHENED GLASS with approved brand patch fittings including fixing in position as directed by Engineer-in-	Sq.m t	20.0		

	<p>charge. Glass should be up to false or roof height (single piece) fixed using Patch Fittings. No wooden or plywood cantles runners to be used for fixing the glass up to false ceiling height. Suitable supporting structure if required may be build with best quality wooden members above false ceiling level. (The rate quoted should be inclusive of this supporting system)</p> <p>The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.</p>				
10	<p>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:</p> <p>Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1150mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with "D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.</p> <p>The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.</p>	Nos	4.0		
11.0	<p>12MM TOUGHENED GLASS MAIN DOOR:</p> <p>Providing, fixing in position 12mm thick toughned glass door with patch fitting of approved make. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and</p>	Sq.M t	9.0		

	fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete. The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.				
12.0	Wall Mounted Writing Desk: Providing, making and placing in position Wall Mounted Writing Desk 750mm x 300mm x 450mm with following specifications. The entire unit is to be made with 18mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate as per drawing. All members to be with 18mm MDF Exterior Grade Board and all exposed faces to have 1mm Glossy Laminate as specified. The Writing Desk to have 12mm thick toughened clear float glass with 25mm chamfered bull nosing alround at top fixed with SS supports. All the edges of 12mm / 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping. All the unexposed faces to have 0.8mm Laminate. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.	Nos	4		
13.0	Wall/Column paneling(LAMINATE): Providing & fixing metal stud wall paneling with the following specification: a) Supporting system comprising 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 12 mm exterior grade MDF board fixed on one side with 25 mm dry wall screws for the entire height of paneling. c) 1 mm glossy laminate and 1mm thick texture laminate as shown in drawing. (Length X height up to false ceiling will be measured for payment.) The rate quoted should include making niches in paneling	Sq.m t	50.0		

14.0	Wall paneling(Premium Laminate): Same as specification of Wall paneling but Premium laminate of basic cost ₹600/Sq.M	Sq.m t	20.0		
15.0	<u>GRID FALSE CEILING:</u> Providing and fixing in true horizontal level false ceiling grid system of approved brand. The suspension system shall be Microline/ Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier miro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed.	Sq.m t	280.0		
16.0	Roller blinds: Providing and fixing in position of block out roller blinds roller blinds of make Vista/Mac/ Hunter Douglas (Basic cost of fabric is Rs1200/- per Sq.Mt)	Sq.m t	15.0		
17.0	Doors in Partitions: Providing and fixing 35mm thick solid core flush shutter with 85mm x 18mm MDF Exterior Grade jamb al-round and 12mm x 12mm MDF Exterior Grade button beading fixed 1mm Laminate as specified on both sides and	Sq.m t	28.0		

	8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 18mm MDF Exterior Grade jamb around the glass opening and 12mm x 12mm MDF Exterior Grade beading for fixing of glass on both sides. The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, 4 Nos. SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC duco paint finish for all exposed surfaces of MDF Exterior Grade members, etc., complete as directed.				
18.0	Storage Units (Laminate): Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm MDF Exterior Grade Board to all members except table top and 25mm block board for table top. The Table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. All other exposed faces of the unit to have 1mm Glossy Laminate as specified and all unexposed faces to have 0.8mm thick laminate and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and MDF Exterior Grade beading 36mm x 36mm at top and MDF Exterior Grade edge lipping 18mm x 12mm etc., as per drawings and directions etc., complete.	Sq.mt	18.00		
19	Storage Units (Premium Laminate): Same as above with specifications Storage units but premium laminate of basic cost ₹600/Sq.m is to be used	Sq.mt	5.0		

	instead of glossy laminate				
20	Plastic Emulsion Painting with Putty: Cleaning the surface of the wall & then applying Two coat of Wallcare putty one coat of primer to give smooth finish exactly in line and level & then finally applying one coat primer and two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling	Sq.mt	300.0		
21	Suggestion Box: Providing and fixing suggestion Box of size 450mm (H)x450mm (w) x 150mm (D) (Inner Dimensions) with 12mm thick external MDF board laminated with 1mm thick glossy laminate on one side and 0.8mm thick backer laminate inside. The Box should have locking facility. Front Side of Box should have 6mm thick clear glass vision panel of size 150mmx 150mm fixed with necessary beadings.	Nos	2.0		
22	Vitrified Tile Flooring: Providing & laying flooring with Full Body Vitrified Tiles (DOUBLE CHARGE) of B15 or approved equivalent make, shade and color of 800mm x 800mm size of 10 / 12mm thickness laid over laid over the existing flooring using tile adhesive (Laticrete-290 or equivalent) and filling the joints with epoxy grout of approved make and colour to match the shade of tiles including cost of base coat, cement slurry, jointing material and conveyance of all materials viz., cement, sand, water, ceramic tiles, white or colored cement etc., to site, cost of seigniorage charges on materials, labour charges for all operations etc., complete as directed, curing etc., complete for finished item of work.(Basic cost of tile : Rs .600/Sq.m)	Sq.mt	290		
23	ACP CLADDING: Supplying and fixing aluminum composite cladding with skin material 0.5 mm thick aluminum sheet cover material natural	Sq.Mt	70.0		

	polyethylene aluminum cladding panel fixed with extruded aluminum basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.				
24	<p>Tech Mitra and Grahak Mitra Table: Providing, making and placing in position Tech Mitra/ Grahak Mitra Table of approximate size 2600mm x 800mm - 900mm x 1150mm (Height) with following specifications.(Refer Drawing)</p> <p>(a) Main Table Top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The vertical supports of the table is to be made with two side boxing of 75mm x 800mm x 750mm made with 18mm MDF Exterior Grade Board and the front side boxing to 200mm x 450mm x 750mm on either sides and central boxing of 250mm x 600mm x 750mm, all made with 18mm MDF Exterior Grade Board cladded with 6mm acrylic solid surface on all the exposed sides and top. The front of the table to have a 600mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be cladded with 6mm thick blue colored lacqured glass.</p> <p>(b) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have</p>	Nos	1		

	<p>6mm acrylic solid surface and the drawer unit to have 1mm Glossy Laminate as specified to be used..</p> <p>(c) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p> <p>(d) 2No.s readymade CPU mobile pedestal.</p> <p>(e) (f) Two Molded Key Board Tray with channels etc.,</p> <p>(f) (g) 2 No.s Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12m MDF Exterior Grade edge lipping etc.,</p> <p>(g) (i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p> <p>(j) 2 No.s Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
25	<p><u>GYPSUM CEILING:</u></p> <p>Providing and fixing suspended ceiling system of 12.5mm La Gyp / Boral Plaster Boards fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be</p>	Sq.m	100		

	made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. The rate quoted should include finishing the surface with putty, one coat of primer and minimum two coats of royal emulsion paint.				
26	Enamel painting: Providing 2 or more coats of enamel painting existing iron grills after scrapping the existing paint. Rate quoted should be inclusive of one coat of primer. Surface area of painted portion will be taken for measurement	Sq.m	50		
27	Plastic Emulsion Painting without Putty: Cleaning the surface of the wall with emry paper , filling the dent with putty & one coat of primer to give smooth finish exactly in line and level & then finally applying one coat primer and two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling	Sq.m	200		
28	Wood work in Door Frame : Providing wood work in frames of doors framed and fixed in position including painting the portion in contact with masonry/RCC with two or more coats of Anti-termite treatment paint and fixing the frames with suitable MS holdfast duly embedded in PCC 1:3:6 or with dash fasteners in column surfaces wherever required including a coat of wood filler as per directions of Engineer-in-Charge. Using well seasoned teak wood with two or more coats of melamine polishing on one side and Duco paint on the other side to give an even shade complete as per site condition/requirement	Cum	0.12		

	and approval of Engineer-in-Charge. The rate quoted should be for complete work and nothing extra will be paid for any minor variation required to complete the work.				
29	Brick Work with plastering(115mm thick): Providing and laying 115 mm thick brick masonry in walls with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels in proper plumb, line and level, including scaffolding, curing, racking of joints etc. including providing 3 nos.8 mm dia bars after every fourth course complete as per instructions at site. Rate quoted should include providing openings . Rate quoted should include plastering the surface with two coats of Cement plastering using 1:4 Cement mortar.	Sq.m	42		
30	Brick Work with plastering(230mm thick): Same as above but with 230mm thick	Sq.m	60		
31	<u>FPVC Doors with Door Frame :</u> Providing of Factory made prelaminated FPVC (Foamed Polyvinyl Chloride). Door frame of the size 105x40mm with a wall thickness of 10mm made out of extruded rigid FPVC profile mitre joined with 6 Nos. of 50mm long screw. The door frame shall be fixed to the wall by using 80mm long screws through the frame with the help of PVC fasteners of 3 no's to be provided for each vertical member, GI stiffeners of ("U" channel of size 29x9x1mm, 150mm long) -3 no's at hinge point, Frame reinforcement of("U" GI channel of size 46x22x.06mm),Bottom tie rod of ("U" GI channel size of 15x15x1mm) etc. complete as per manufacturers specification for finished item of work. Maximum door frame size : 980 x 2070 including providing of 35mm thick Factory made Prelaminated ABS (Acrolonitrile Butadyne	Nos	3		

	<p>Styrene) Door shutter moulded in different designs, consisting of all round Frame made out of water proof solid foam PVC bar of size 20x32mm, reinforced by 32x32mm - 2 nos. for vertical made out of LVL (Laminated Veneer Lumber), core material of 32 mm thick high density craft paper honey comb board, sandwiched on both sides with prelaminated ABS sheet thickness of 1.5mm . PVC edge banding of size 0.45mm on the vertical sides. Hardware made out of steel coated butterfly hinges - 3 Nos. for each shutter and ISI make S.S round lock completes for finished item of work. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item as directed by the Engineer in charge. Make: NCL, WINTEC</p>				
32	<p>Floor Tiles: Providing and laying of anti skid vitrified floor tiles of approved colour and design 10 mm thick floor tiles of approved make and 2" x 2" size fixed over 20 mm thick cement base mortar 1:6. The scope work is inclusive of providing proper slopes for better drainage of water to the traps, filling the joints with neat cement and matching pigment etc complete in all respects as directed by Bank. The basic cost of the tile is Rs 450.00 per Sq.Mt. The above basic cost does not include tax, transportation etc at site should be assumed to arrive the tender rate. No extra claim towards wastage Make: Johnson, Somany, Kajaria or Equivalent</p>	Sqm	12		
33	<p>Wall Tiles: Providing and fixing of wall tiles of 300x600size or approved size of approved colour, design and make over a base plaster of 15mm thick on the brick work and 12 mm thick cement plaster 1:4 leveling course and filling / grouting the joints with white cement slurry mixed with approved matching colour with tiles at all</p>	Sqm	50		

	levels with all required tools, plants, materials and labour required to complete the work in all respects as directed by Bank. The scope work is also inclusive of disposal of debris out of Bank campus on weekly basis, failing which Bank will make arrangements for the disposal at the risk & cost of the contractor. The Basic cost of the tile is Rs.500.00 per Sq.Mt the above basic cost does not include tax, transportation etc at site should be assumed to arrive the tender rate. No extra claim towards wastage. Make: Johnson, Somany, Kajaria or Equivalent all complete as directed by Bank				
34	<u>Collapsible gate:</u> Providing and Fixing in position collapsible steel shutters with vertical channels 20x10x2 mm braced with vertical Channles 20x5 mm size with top & bottom rails of T-Iron 40x40x6 mm with 38 mm dia steel pulleys complete with bolt, nuts, loking arrangement, stoppers handles including applying a priming coat of red lead paint.	Sqmt	5.0		
35	<u>Long Body 2 in 1 bib Cock</u> :Supplying and Fixing of Long Body 2 in 1 Bib Cock of approved make (Quarter turn) series, Chrome finish with 7 years warranty with necessary fittings etc., complete including cost and conveyance of all materials, labour charges for finished item of work.	Nos	3		
36	<u>Angel Valve:</u> Supplying and Fixing of Angle valve with necessary fittings etc., complete including cost and conveyance of all materials, labour charges for finished item of work.	Nos	6		
37	<u>Health Faucet</u> :Supplying and Fixing of Health faucet with necessary fittings etc., complete including cost and conveyance of all materials, labour charges for finished item of work	Nos	3		
38	<u>Pillar Cock:</u> Supplying and fixing of pillar cock of approved make	Nos	3		
39	<u>Towel Ring</u> :Supplying and Fixing of Towel ring , complete, including cost and conveyance of all materials, labour	Nos	2		

	charges for finished item				
40	<u>Soap Dispenser:</u> Supplying and Fixing of Soap Dispenser complete, including cost and conveyance of all materials, labour charges for finished item	Nos	3		
41	<u>EWC:</u> Supplying and fixing of floor mounted EWC of approved make with basic cost ₹6000 including flush tank with complete accessories.	Nos	3		
42	<u>Wash Basin:</u> Supplying and fixing of Wash Basin with Bottle trap of approved make with basic cost ₹6000 including flush tank with complete accessories.	Nos	3		
43	<u>Urinal :</u> Supplying and fixing of Flat Back Urinal of approved make with basic cost ₹4000 including flush tank with complete accessories.	Nos	2		
44	<u>Nahni Traps:</u> Providing fixing nahni trap of 100mm dia with SS jolly		3		
45	<u>Mirrors:</u> Providing and fixing of 5 mm thick of size 600mmx450mm beveled edge mirrors of approved make and quality, frame less fixed with SS studs etc inclusive of all materials, labours, tools, tackles, consumables etc all complete as directed by the Bank. Make-Modi guard/saint-gobain or Equivalent.	Nos	3		
46	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes of 20 mm dia of approved quality and make, having thermal stability for hot and cold-water supply, including providing and fixing CPVC plain & brass threaded specials of same make, fixing the pipes with clamps at 1 mtr. spacing for concealed work including cutting chases in the wall to the required depth, connecting to the existing duct line, jointing of the pipes and fittings with one stop CPVC solvent cement of approved quality and make, making good the damages, etc. complete. The rate shall include for pressure testing of joints/ pipelines for leakage etc., all complete as directed by the Bank's Engineer.	Mts	50		
47	Same as above but 25mm dia pipe	Mts	10		
48	<u>Granite Platform:</u> Supply and laying of	Sq.mt	2		

	18-25mm thick Black galaxy granite slabs with double edge moldings and granite strip attached under the granite over hung to make it look thick all material,labour, installation, transportation, lead, lift, consumables, tools, tackles, instruments, machines, etc all complete as directed by the Engineer-in-charge. Rate quoted should be inclusive of cutting of granite for fixing SS Sink				
49	SS Sink : Supplying and fixing stainless steel sink of overall size 610 x 458 mm with bowl size 22" x 16" x 9" conforming to SS 304 grade/1mm thick of approved make, the joints with granite slab shall be sealed thoroughly with epoxy/ silicon sealant, including all necessary fittings and fixtures, CP waste coupling, PVC flexible waste pipe etc. all complete as directed by the Bank's Engineer. Rate quoted should be inclusive of swan neck cock.	Nos	1		
50	Dismantling Brick Work: Carefully dismantling existing brick and carting away debries from work site to a disposal site approved by local municipal corporation. Stacking of debries is not allowed.	Sq.mt	150		
51	Dismantling: Dismantling of rear wall and floor tiles, EWC's, IWC's, old GI & CI lines, walls, wooden partitions, counters cash room, wall tiles, floor tiles, Storage units, brick work, false ceiling , trap doors, record room and disposal of debris to dump yard approved by local municipal corporation. (Bidder should visit site before quoting the rate for this work)	Ls	1		
52	Buy back of Old Furniture in the branch premises like counters, tables etc	LS	-1		
	Total				
	DISCOUNT IF ANY				
	NET TOTAL				

Signature of Agency with Seal.