

BETHELHEM BRANCH
BOQ for Supply, Installation and Annual Maintenance Contract for of Air-conditioners

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.0 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej (FOR ATM ROOM)	No.	2		
2	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej (FOR BM CABIN)	No.	1		
3	Supply of 2.0 TR Cassette type split air conditioners with Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Carrier/Daikin /LG	No.	2		
4	Installation charges of the 1.0 /1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	3		
5	Installation charges of the 2.0 TR Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	2		
6	For 2.0 TR Copper Cassette type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	30		
7	For 1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	12		
8	Supply and Installation of 4 KVA Stabilizer for 1.0 TR Split Acs	Nos.	3		
9	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	2		
10	Supply for Digital Timer of 32 A out put rating to be used in ATM room with all necessary wiring and installation	Nos.	1		
10	Comprehensive Annual Maintenance Contract of above mentioned 2 No. of 1.0 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation. Rate will be quoted for one year only. The rate quoted will be valid for 5 years of AMC and no further increase in AMC amount will be allowed.	Nos.	1		

11	Comprehensive Annual Maintenance Contract of above mentioned 1 No. of 1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation. Rate will be quoted for one year only. The rate quoted will be valid for 5 years of AMC and no further increase in AMC amount will be allowed.	Nos.	1		
12	Comprehensive Annual Maintenance Contract of above mentioned 2 Nos. of 2.0 TR Copper Cassette type split air conditioners after expiry of defect liability period of 1 year from the date of installation. Rate will be quoted for one year only. The rate quoted will be valid for 5 years of AMC and no further increase in AMC amount will be allowed.	Nos.	1		
GST will be extra as applicable.		Grand Total(In Rupees)			

1tr 2600

1 2600

#REF!

2.0C 6400

2 12800