

**BILLLS OF QUANTITIES FOR FURNISHING WORK OF STATE BANK OF INDIA FOR GOVT. BUSINESS DEPARTMENT AT  
MAIN BRANCH, BHADRA, LAL DARWAJA, AHMEDABAD**

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
---------	-------------	----------	------	------------------	------------------	--------

**Note :** Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

**[A] FURNISHING WORK**

**1 SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White corian & blue lacquered glass finishing**      15      RMT

Supplying, fixing and keeping in position single window counter complete as per design and drawing made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.

The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.

[a] size :

Description:	L	B	Ht.
Writing Top	5'-0"	2'-9"	2'-6"

4 Drawers with pigeon hole	2'-0"	1'-3"	2'-0"
----------------------------	-------	-------	-------

Computer key Board with mouse pad

Supplying and fixing metal key Board of approved make in counter as per design and instructions.

[b] Working table top and edges shall be finished with 6 mm thick white corian of DUPONT or equivalent approved make as per drawing and direction with all labour and material.

[c] Front Apron : 2 nos 6 mm thick flexy ply wood in round shape with 6 mm thick white corian shall be provided at front as per design. All edges should be finished with corian of DUPONT make.

[d] Front pannel shall be finished with 6 mm thick 18" high blue back painted glass of approved make and fixed on 18 mm thick commercial ply wood with Natural Silicon gum as per manufacturer's specification and to be completed as per drawing

[e] Table shall have ready made CPU trolley with castors and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners

[f] All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.

[g] All fittings like S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.

[h] Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.

[i] All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete

[j] Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.

**FINISHING DETAILS IN NUTSHELL:**

1) Table Top : 6 mm thick white corian

2) **Front Apron:** Round corian and 6 mm thick backpainted blue glass fixed with Natural Silicon

3) **Facing of Drawers:** 1.00 mm thick laminate finish

4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
2	<p><b>Providing and fixing 12 mm thick Toughened Glass partition on counter top, front side as follows.</b>  Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary S.S Brush finish brackets &amp; support on wooden partition as directed with necessary cut out in glass.All edges of glass shall have Diamond cut polished edges as directed.</p>	11.5	SQMT			
3	<p><b>Providing and fixing 12 mm thick Toughened float Glass partition between Single Window counters as follows.</b>  12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and T.W beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. Wooden partition will be paid seperately. Maximum length and height will be measured for payment purpose.</p>	4	SQMT			
4	<p><b>TABLES</b>  <b>TABLE SIZE: 6'-0" X 3'-0" X2'-6" HT. with Laminate finish on Table Top, sides and all other visible surfaces etc complete as follows</b>  Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawer of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make, grouplock, S.S. Handle. Computer Key board tray with moused of metal of approved make shall be provided. All internal surface will have 0.60 mm thick balacing laminate.</p> <p><b>Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing</b>  <b>Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.</b>  Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood &amp; Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.</p> <p>Table shall have ready made CPU trolley with castors and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges &amp; corners  Exposed edges of Table Top, <b>Ready made Foot Rest &amp; drawers</b> shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.  <b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.</b>  All the surface without laminate / balancing laminate shall be lacquered polished of approved shade  <b>As per drawing and instruction of Architect/Bank work to be Completed</b>  <b>FINISHING DETAILS IN NUTSHELL:</b>  1) <b>Table Top</b> : 1.0 mm thick Dark laminate &amp; Burma Teak beading on Edges with polished  2) <b>Front Apron &amp; Sides:</b> 1.0 mm thick Dark Laminate</p>	1	NO			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
	3) Facing of Drawers: 1.0 mm thick Dark Laminate 4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate					
5	Same as above Item-no-4 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR MANAGER & ADVANCE]	9	NO			
6	<b>SIDE CREDENZA (SIDE TABLE)</b> <b>Side Credenza Size 3'-3" x 1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. (For Manager &amp; Officers) Rate for length Less than 3'-3"</b> Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balancing laminate  Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate  <b>FINISHING DETAILS IN NUTSHELL:</b> 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides: Frosty White Laminate	8	SQ.MT			
7	<b>SIDE CREDENZA (SIDE TABLE) with partly Drawers Same as above Item No 7 all external surfaces to be finished with 1.0 mm thick Laminate (approved shades). Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with Partly drawers &amp; Partly openable shutters as directed</b>  <b>FINISHING DETAILS IN NUTSHELL:</b> 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides : Frosty White Laminate	0	SQ.MT			
8	<b>SIDE CREDENZA (SIDE TABLE) For S.W Countwer Same as above item No-7 but Side Table Top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with 1.00 mm thk laminate. Size shall be 3'-0" x 1'-4"x2'-6" ht. With openable shutter as directed</b>	8	SQMT			
9	<b>LOW/FULL HEIGHT STORAGE CABINET with Top &amp; Front laminate finished. Storage of any height</b> Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades) <b>FINISHING DETAILS IN NUTSHELL:</b> 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions	19	SQMT			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
7[d]	<b>P/F ELECTRIC CUB BOARD</b> Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50 x 25 x 1.20 mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.	3	SQMT			
10	<b>P/F PANTRY PLATFORM CUB BOARD SHUTTER</b> Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface	0	SQMT			
11	<b>LOW HEIGHT PARTITION WORK</b>  <b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR BACK SIDE AND IN BETWEEN S.W COUNTER AND CASH CABIN WITH TOUGHENED GLASS</b>  Providing and fixing low height partition using 50mm x 25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides, fixing 12 mm thick transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed. Laminate to be provided only on visible surface. <b>For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.</b>	29	SQMT			
12	<b>PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE</b> Same as item no 10 but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers, doorstop etc complete as directed.	1.5	SQMT			
13	<b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS</b> Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.	23	SQMT			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
14	<p><b>FULL HEIGHT PARTITION WORK</b></p> <p><b>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR</b></p> <p>Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.</p> <p>For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.</p>	33	SQMT			
15	<p><b>Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.</b></p> <p>Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing &amp; instructions.</p>	2	SQMT			
	<p><b>PANELLING WORK</b></p>					
16	<p><b>P/F Wall panelling with laminate finishing for wall and Pillar etc</b></p> <p>Providing and laying panelling on walls &amp; pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall &amp; pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .</p>	20	SQMT			
	<p><b>FALSE CEILING WORK</b></p>					
17	<p><b>Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid.</b></p> <p>Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. he rates include removal of existing false ceiling</p> <p>After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications</p>	424	SQMT			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
18	<b>P &amp; F ACP FALSE CEILING</b> P & F 3 mm thk ACP False ceiling with wood finish and necessary aluminium frame work as directed complete. Rate includes making necessary cutouts for fixing light fixtures complete as directed. Only finished surface area shall be measured for payment. The rates include removal of existing false ceiling	385	SQMT			
19	<b>SOFT BOARD</b> Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.	1	SQMT			
20	<b>Removing, refixing and realignment of existing Furnitures</b> Removing, Refixing and re-alignment of Tables, Side Tables, cup board, Misc. other furnitures to be used from existing premises including polishing and minor repairs.  (i) Shifting and re-laying table, side table, cup board as per new lay out. Rate also includes removal of electric/ data/telephone connection as per site requirements. (ii) Necessary cutting, modification and repairing if required. (iii) Repairing of drawers and shutter and painting /polishing complete as directed.					
21	S.W Counter with necessary cutting and modification includes painting/polishing etc. Complete. Rate also includes providing and fixing Transaction Top : 2 nos 6 mm thick flexy ply wood round shape at front as per design,	2	RMT			
22	<b>REPAIRING WORK</b> Repairing of existing cash cabin/SW counter drawers and shutter with necessary modifications, replacing of members if required, painting/polishing etc. complete as directed	1	NO			
23	Charges for Temporary shifting of Branch Furniture at convenient location on GF/FF as per the instruction of Architect/Bank. Rate includes fixing / erecting counters, cash cabin arrangement of furniture to the entire satisfaction of Branch Manager / Bank. Rate includes dismantling existing furniture and storing/ stacking the same at a location as directed by bank	1	JOB			
24	Removing Existing Single Window with partition and door, Full/Low Height wooden partitions, Tables, Side Table, Storage, Panelling etc. including stacking debris and reusable material as directed including carting away debris all levels.	1	JOB			

**TOTAL COST "A"**

**Note:**

- [a] In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this
- [b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balancing laminate of approved make & shade in the all S.W Counters/Tables/ Credenza, Storage Cup Board etc.
- [c] Rate includes dismantling existing furniture and storing/ standing the same at a location as directed by bank Nothing extra shall be paid for then.
- [d] Temporary shifting of Branch Furniture at convenient location as per the instruction of Architect/Bank. Rate includes creating/erecting counters, cash cabin arrangement of furniture to the entire satisfaction of Branch Manager complete as directed by bank Nothing extra shall be paid for then.

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Amount)	Amount
[B]	<b>BUY BACK OF OLD FURNITURE</b> Dismantling of entire furniture and fixtures from existing premises and buy back of furniture which is not required by Bank, as follows					
1	CASH / S.W COUNTER	3	RMT			
2	12 mm thick glass partition on S.W Counter	1	SQMT			
4	Wooden partition for S.W Counter	25	SQMT			
5	Wooden Partition for Server Room/ Manager Cabin & other partition	190	SQMT			
	<b>TOTAL COST OF BUY BACK "B"</b>					_____
	<b>SUMMARY</b>					_____
[A]	<b>FURNISHING WORK</b>					_____
[B]	<b>BUY BACK OF OLD FURNITURE</b>				(-)	_____
	<b>NET TOTAL COST [A - B]</b>					_____