

**PRICE BID FOR CIVIL WORKS AT SBI KUMBALAM BRANCH (NEW PREMISES) UNDER RBO-2,  
ERNAKULAM, AS PER UNIFORM LAYOUT**

SI.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	Dismantle brick masonry of 23 cm/ 15 cm and finishing the exposed surface with cement mortar 1:4 and disposal of all debris clear off the premises. The work includes making good the exposed surface of the walls after dismantling.	30	Sq.M		
2	Dismantling the existing floor/ wall tiles and plastering in the proposed strong room/ brick wall area without damaging the surrounding tiled portions and disposal of the debris away from site at no risk and cost to the bank.	1	LS		
3	Block work in CM 1:6 with CC blocks of 40/30x20x15 cm for superstructure	18	CuM		
4	Cement Concrete 1:2:4 for lintel including shuttering, curing, cost of reinforcement etc complete as directed	2	CuM		
5	Providing and fixing steel door of size 90 x210 cms for ups and record rooms with necessary frame work and all other fixtures	6	Sq.M		
6	Provide/fix kitchen counter with 18 mm thick jet black granite (with polished / rounded edges) over a box of marine plywood of 19 mm thick with 1mm thick laminate with openable shutters, handles, box hinges etc complete	2	Sq.M		
7	Providing and fixing stainless steel sink with drain board of size about 36" x 18" including all connection/ fittings.	1	No.		
8	Reinforced Cement Concrete M20 for floor and walls including shuttering, curing etc complete but excluding reinforcement	32	Cu.M		
9	Providing steel reinforcement of 12 mm dia for RCC works including bending, tying and placing in position [for strong room walls and floors, 12mm dia bars shall be placed vertically and horizontally at 15cm centre to centre in two rows, staggered centrally and placed along both faces of the walls with a clear cover of 40mm on either side of the walls/ floor].	2880	Kg		
10	Providing 20 mm steel rods @ 7.5 cm c/c both ways for roof including the cost of welding the joints and finally fixing and welding to 60 x 60 x 5mm angle to be fixed on all the perimeter walls. The angles shall be supported/ welded to the steel bars embedded/ provided on the RCC walls during casting of walls. (Cost of angles will be paid separately)	2100	Kg		

11	Providing and fixing angle of size 60 x 60 x 5 mm supporting/ welding to the steel bars embedded/ provided on the RCC walls during casting of walls.	135	Kg		
12	Plastering including patch plastering with cement mortar 1:5 (1cement 5 sand) 12mm thick, one coat floated hard and travelled smooth for the wall surfaces including all staging works, watering ,curing etc. complete.	404	Sq.M		
13	Fixing strong room doors (2nos of approx size 110x220cms) and Strong Room Ventilators (2nos of approx size 45x45cms) in the strong room walls by welding the reinforcement to the holdfast/ other areas of the door/ ventilator and making good the walls/ floors etc complete. (Doors/ ventilators will be supplied by the Bank). The cost of concreting for filling the gap between the wall and door/ ventilator will be paid vide item for M20 concrete above.	1	LS		
14	Collapsible grill - Twin units/ double leafed, meeting at the centre of the span. The collapsible door is fabricated from vertical pieces of rolled steel channels, 16 to 20 mm wide, joined together with the hollows of the channels on the inside; leaving a gap between them of 12 to 20 mm. Both are offered to the roller on its top and bottom sides. The vertical channel is spaced at 10 cm center to center, and is joined to one another by means of hoop iron cross pieces or flats 16 mm to 20 mm wide and 4-5mm thick, allowing the door to open or unfold. The rollers shall be run over steel channels fixed at top and bottom. The bottom channel shall be embedded within the floor tile level to provide smooth transit of the men, wheel chairs atc. Both the grills (leaves) shall have Steel handles, Locking arrangements etc and are to be fixed firmly to the walls/ pillars, floor and ceiling as required.	12	Sq.M		
15	Providing and fixing 60 x 60 cm/ 80 x 80 cm vitrified ceramic tiles of approved make/ shade/ color by using tile oin tile adhesive/ cm 1:3 as the case may be, on to existing flooring and skirting. Basic price of tiles to be taken as Rs.60 per square foot.	70	Sq.M		
16	<b>TOTAL (Excluding GST)</b>				

GST at applicable rates will be extra