

**INTERIOR & FURNISHING WORKS OF SBI RAJINDER NAGAR, GHAZIABAD BRANCH**

**INDICATIVE PRICE BID**

<b>S.No</b>	<b>Particulars</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
<b>1.0</b>	<b>PARTITIONS &amp; DOORS</b>				
	<p>Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rate to include provision of extra frame work as necessary for skirting, <b>niches</b> and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings &amp; directions. All wood framework to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti termite treatment properties.</p> <p><b>(Measurement shall be taken of the plan area only nothing extra for designing and provision of niches and vertical sections)</b></p>				
<b>a</b>	<p>Providing and fixing in position <b>Full Height Partition</b> having overall thickness of 64 mm made out of aluminum hollow section of 44mm x 44mm size 1.20 thick of JINDAL / INDAL as internal frame structure placed horizontally &amp; vertically in 600mm x 600mm center to center with fixing 8 mm thick commercial ply on both sides with 1.0 mm thick laminate in approved shade with groove pattern. Item includes provision of 4 mm grooving in desired pattern, finishing of grooves with polishing in desired shade with TW scantling etc. complete including necessary melamine polish in approved shade. Rates to include providing and fixing of 30 mm thick flush doors covered with 1.00 mm thick laminate on both sides, 4 nos. SS butt hinges (heavy) on each door, 6 levers Godrej make mortise lock with decorative handles, door stopper, 5 mm. thick etched glass (for door) in 2nd class teak wood frame work (chaukhat) of size 75 X 40 mm complete along with melamine polish in desired shade including providing and applying fire retardant VIPER paint over wooden frame work etc. complete. Note: The cost of doors with necessary hardware locks etc. complete to be included in rates of this item.</p>	12	Sq.Mt.		0.00
<b>b</b>	<p>Providing &amp; fixing 12mm thick toughend <b>Fixed Glass Partition</b> in front of cabins for Manager and also Branch Front Entrance, glass fixed with S.S. clamps on sides and top &amp; S.S. u-channel in the ground as per detail drgs. and complete to the satisfaction of Architect/ Bank's Engineer.</p>	24	Sq.Mt.		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
c	Providing and fixing front <b>Frameless Patch Fitting Door</b> with 12mm thick toughened glass with frame less glass fittings joining 2 glass & double action floor springs (Hettich/Dorma/Godrej) as per design. The item includes providing and fixing S.S. handle not less than 600mm long on both side of glass, locks and fittings (Haffle/ Hettich/ Ozone) as per the manufacturer's specifications etc. complete to the satisfaction of Bank's Engineer.	8	Sq.Mt.		0.00
d	Providing and fixing in position <b>Low Height Partition</b> with 10 mm thick acid wash glass having overall thickness of 64 mm made out of aluminum hollow section of 44mm x 44mm size 1.20 thick of JINDAL/INDAL as internal frame structure placed horizontally & vertically at max distance of 600mm approximate c /c both ways with fixing 8 mm thick commercial ply on both sides finished with 1.0mm thick laminate of approved shade as per Bank's Engineer instructions. 10 mm thick acid wash glass is to be fixed with SS clamp at the exposed edges of the partition. Item includes teakwood moulding of size 75 X 25 mm. All exposed woodwork to be high gloss melamine polished.	15	Sq.Mt.		0.00
e	Providing & fixing <b>Glazed Door</b> (35 mm thick flush door with vision panel of size 150 mm X 1500 mm having 6 mm toughened glass) with 10 mm thick teakwood lipping on all sides finished in 1.0mm thick decorative texture laminate fixed on both sides as per design. The item includes providing and fixing chaukhat made from 100mmx50mm sal wood members. The door is to be complete with mortice door lock & SS handle , S.S stopper, 125mm S.S. hinges etc. All wood surfaces to be malamine polished complete to the satisfaction of Bank's Engineer.	2	Sq.Mt.		0.00
f	Providing & fixing <b>Door Closers</b> (Hettich/ Haffle/ Dorma/ Godrej) including fixing and all associated hardware etc. complete to the satisfaction of Bank's Engineer.	2	Nos		0.00
g	Relamination of <b>existing Doors and Chaukhats</b> , existing door to be removed and refixed after providing it with 1.0mm thk. decorative texture laminate over 4mm thk. commercial ply after removing existing finish, providing vision pannel/ glazing of required size complete with all new hardware fittings such as SS handles, SS hinges, mortice lock, door stopper, silencer etc. complete, Item also includes polish on all wooden surfaces etc, complete to the satisfaction of Bank's Engineer. <b>(Measurement of only one side shall be taken)</b>	4	Sq.Mt		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
h	Providing and fixing <b>Louvered Shutter Cabinet</b> for main panel fabricated out of 19 mm thick commercial board and finished with 1 mm thick laminate of approved make, shade and texture, louvers fabricated out of steam beech wood duly polished with melamine spray and all other specifications as per item no. 1 complete.	5	Sq.Mt.		0.00
<b>SUB TOTAL : I : PARTITIONS AND DOORS</b>					<b>0.00</b>
<b>2.0</b>	<b>PANELLING</b>				
a	Providing & fixing <b>Panelling (Laminate)</b> with frame work with aluminum hollow section of 44mm x 44mm size 1.20 thick of JINDAL/INDAL of JINDAL @ 600 mm c/c in both directions, finished with 8 mm thk. commercial ply. The ply to be covered with 1.0mm thk. decorative texture laminate in two or more colour. Paneling to have 3 Nos. of 50 mm high metallic decorative texture laminate band. Paneling to have 50x35mm teak wood moulding on edges. Panelling to have provision of extra frame work as necessary for skirting, <b>coves</b> and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Bank's Engineer.	140	Sq.Mt.		0.00
b	Providing & fixing <b>Panelling (Wall Paper)</b> with frame work with aluminum hollow section of 44mm x 44mm size 1.20 thick of JINDAL/INDAL @ 600 mm c/c in both directions, finished with 8mm thk. commercial ply. The ply to be covered with Wall Paper (Elemento/ Marshel). Paneling to have 50x35mm teak wood moulding on edges. Panelling to have provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Bank's Engineer. (Base Price of wall paper to be used to be Rs. 100/ sq.ft.).	2	Sq.Mt.		0.00
c	Providing & fixing <b>Panelling (Customized Digital Print Lacquer Glass)</b> with frame work with aluminum hollow section of 44mm x 44mm size 1.20 thick of JINDAL/INDAL of JINDAL @ 600 mm c/c in both directions, finished with 8mm thk. commercial ply. The ply to be covered with 6.0 mm thick colored glass in two or more colour, as per drawings & directions etc. complete to the satisfaction of the Bank's Engineer. (Base Price of lacquered glass to be used to be Rs. 200/ sq.ft. (without tax).	3	Sq.Mt.		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
d	Providing & fixing in position <b>Aluminium Composite Paneling (ACP)</b> with framing of aluminium tube sections of 38mmX25mm and 20 gauge at a spacing of 2' center to center both ways. ACP to be of shade as approved by Bank in 2' width panels or distributed equally. ACP sheets to be fixed to the frame 3 M make adhesive along with mirror screws . Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminium foil thickness to be min. 0.25 mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the higher position.	46	Sq.Mt.		0.00
	<b>SUB TOTAL : II : PANELLING</b>				<b>0.00</b>
<b>3.0</b>	<b>FALSE CEILING</b>				
	Item includes providing False Ceiling in plane, curve shape and design. Suspending system and frame work shall match layout of A.C. ducts / grills, electrical / fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work, necessary scaffolding needed due to layout of other utilities refered above and fixtures etc. <b>(Measurement shall be taken of the plan area only nothing extra for cove design and verticle sections)</b>				
a	Providing and fixing <b>Gypsum Board False Ceiling (Plastic Emulsion Paint)</b> with INDIA GYPSUM ULTRA main ceiling sections at 1200 c/c and cross members at 450 c/c of INDIAN GYPSUM. The grid work to be suspended from ceiling with hangers at every 1200 c/c in both directions. The Frame work to be as per manufacturer's specifications. 12.5 mm thk. GYPBOARD to be screwerd to the frame. The board to be finished with filling the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling to be finished with a top coat (plastic emulsion paint with 'Velvet Touch' of approved brand and manufacture to give an even shade: Two or more coats on new work with rollers/ spray) as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Bank's Engineer.	140	Sq.Mt.		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
b	Providing and fixing <b>False Ceiling with Mineral Fibre Acoustic Ceiling Tiles</b> of Armstrong/ USG/ Boral with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 15mm wide <b>Silhouette</b> type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Ceiling tiles of <b>Dune Premier</b> of size 600 x 600 x 15 mm (thk.) to be placed in the grid. Rate to include making necessary cut-outs or openings for light fixtures, air conditioners and other utilities etc. complete to the satisfaction of Bank's Engineer.	33	Sq.Mt.		0.00
c	Providing and fixing plain non perforated metal sheet <b>GI tiles Grid False Ceiling</b> of size 600mm x 600mm having ceiling sections at 600 mm center to center both ways duly fixed with screws. The grid work to be suspended from ceiling with hangers at every 600 mm center to center in both directions. The framework to be as per manufacturer's specifications. Item includes providing extra support for fixing light fixture etc. complete.	6	Sq.Mt.		0.00
	<b>SUB TOTAL : III : FALSE CEILING</b>				<b>0.00</b>
<b>4.0</b>	<b>COUNTER/ TABLES/ WORKSTATIONS</b>				
	All Tables/ Counters/Work stations/Reception Counter to have 19mm thk. commercial ply top and sides and 1.0 mm thk. laminate (Decorative/Texture/Metallic) finish on exposed surfaces along with 0.8 mm thk. white laminate on inside surface, drawer units to be made from 12 mm thk. BWR ply with 19mm thk. commercial ply FASCIA with 1.0 mm thk. decorative texture laminate finish (as per individual item).The drawers to run on telescopic drawer channels. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement (Godrej). Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. handles, cable manager (Hettich/ Dorma/Hafele) etc. complete. The item also includes a tray for keyboard runing on telescopic channel, finshed with decorative texture laminate on top and rounded front of size 560x450mm, readymade CPU trolley with castors etc. complete to the satisfaction of Bank's Engineer.				

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
a	Providing and placing <b>BM Table</b> made of 19mm thk. commercial ply finished with approved 1.0mm thk. high gloss/ textured decorative laminate and sides made with 19mm thk. commercial ply finished with 1.0mm thk. high gloss decorative laminate. Front modesty panel to be made of 19mm thk. commercial ply finished with 1.0mm thk decorative texture high gloss laminate in shade as per SBI standards. Table top edges to be approx. 75mm thk. finished with laminate as per design & details. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. 8 mm thick clear toughened glass with bevelled edges to be provided on top. The table size shall be 1800x900x750(H)mm.	1	Nos.		0.00
b	Providing and placing in position <b>Officer Tables</b> made of 19mm thk. commercial ply top and sides finished with 1.0mm thk. decorative texture/high gloss laminate. Front modesty panel to be made of 19mm thk. commercial ply finished with 1.0mm thk decorative texture high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. 8 mm thick clear toughened glass with bevelled edges to be provided on top. The table size shall be 1350-1500x750x750 (H)mm.	2	Nos.		0.00
c	Providing and placing in position <b>Asstt. Tables</b> made of 19mm thk. commercial board top and sides finished with 1.0mm thk. decorative texture/high gloss laminate. Front modesty panel to be made of 19mm thk. commercial board finished with 1.0mm thk decorative texture high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. 8 mm thick clear toughened glass with bevelled edges to be provided on top. The table size shall be 900 - 1200x600x750 (H)mm.	1	Nos.		0.00
d	Providing and fixing double top <b>Reception / CVE counter</b> in semi circular/linear shape with 19mm commercial Board and 1 mm thick laminate of approved make in two or more shades and one drawer unit. The Customer top to be at 300 mm higher than working top as per design & Details to the satisfaction of Bank's Engineer. The table size to be 1800x750x1050	1	Nos.		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
e	Providing and fixing <b>Side Table of Branch Manager</b> finished with decorative texture laminate same as that of main table. The side table to have 2 drawers on top with shuttered storage below. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Haffele) and locks (Godrej) etc. complete as per design/drawing. 8 mm thick clear toughened glass with bevelled edges to be provided on top. The side table size shall be 1050x450x750(H)mm.	1	Nos.		0.00
f	Providing and fixing <b>Side Table of Officers</b> finished with decorative texture laminate same as that of main table. The side table to have 2 drawers on top with shuttered storage below. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Haffele) and locks (Godrej) etc. complete as per design/drawing. 8 mm thick clear toughened glass with bevelled edges to be provided on top. The side table size shall be 900x450x750(H)mm.	2	Nos.		0.00
g	Providing and placing in position <b>Banking Counters</b> in straight/curved shapes 750 mm high made of 19 mm thk. commercial ply duly rounded with flexi ply covering in 750mm wide working top, finished with 12 mm thk. high density acrylic (Dupont) in curved shape upto top 1.25' portion of the front and bottom 1.25' portion of the front with 6.0 mm thick colored glass and rest of the structure made from 19mm thk. commercial ply finished with 1.0 mm thk. decorative textured high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above but with divisions for currency as per Bank's instructions. The drawer units shall be provided with autolocking system (Godrej) for drawers etc. complete as per design/ drawing.	7	R.Mt.		0.00
h	Providing and fixing 12mm thk. <b>Toughened Float Glass</b> in front portion of single window counters with metal clamps including cutouts for passing currency and communication as per details. The edges of the glass to be polished etc. complete to the satisfaction of Bank's Engineer.	8	Sq.Mt.		0.00

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
i	Providing and fixing <b>Side Storage Tables for Banking Counters</b> made of 19 mm thk. commercial ply having 450mm wide top provided with 12 mm thk. high density acrylic (Dupont) and sides finished with 1mm thk. decorative laminate. The side table to have 2 drawers on top with shuttered storage below. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Haffele) and locks (Godrej) etc. complete as per design/drawing. The side table size shall be 900x450x750(H)mm.	5	Nos.		0.00
j	Providing and fixing modular type <b>Voucher Tray</b> 900x300x1050 mm deep made out of 19 mm thick commercial board finished with 1 mm thick laminate of approved make, shade and texture with writing top of 12 mm glass and racks for keeping vouchers and cheque drop box with slit for dropping of cheque, glass for viewing and cup board locking arrangement as per Engineer-in-Charge. All exposed edges to be finished with edge binding tape.	1	Nos.		0.00
k	Providing and fixing in position 2'6"X1'6"x6' <b>Dressing Unit</b> in locker room fabricated out of 19 mm thick commercial board finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces including top, front of drawers, sides including provision of drawers. The rate shall include providing and fixing 0.8 mm thick laminate on all internal surfaces of drawers and inner side of back ply, providing the sides and both sides of vertical, horizontal members with teak wood moulding, necessary hardware such as locks, telescopic sliding channels, handles etc as per approved sample. The unit will have one settee with castors with upholstered (Basic rate Rs. 240/- per meter) rubber seat of size: 1'-4"x1'-4"x1'-4" .	1	Nos.		0.00
	<b>SUB TOTAL : IV : COUNTER/TABLES/WORKSTATIONS</b>				<b>0.00</b>
<b>5.0</b>	<b>STORAGE CUPBOARDS</b>				



S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
a	<p>Providing &amp; fixing <b>Full Height Box Storage Cupboard</b> 450mm deep with frame, all sides, shelves to be made with 19 mm thk. BWR ply and 6mm thk. BWR ply fixed at the back. The shutters to be made with 19mm thk. BWR ply. Shutters, top and sides finished with 1.0 mm thk. decorative texture laminate on all exposed surfaces. All edges to have 2mm thk. edge binding tapes as per details, all shutters to to be made overlapping the frame and edges of shutters to have 2mm thk. edge binding tapes as per details including S.S. long handles, magnetic catchers, self closing hinges, locks (Godrej/Hettich/Haffele) etc. The item includes polishing the wood surfaces with melamine polish and inside surfaces to have 0.8 mm thk white laminate finish etc. complete to the satisfaction of Architect / Bank's Engineer.</p> <p><b>(Only front elevation will be considered for area calculation)</b></p>	2	Sq.Mt.		0.00
b	<p>Providing &amp; fixing <b>Low Height Storage Cupboard</b> with same specificatin as mentioned in item 5a above for box storage cupboard but height of 750-900mm etc. complete to the satisfaction of Architect/Bank's Engineer.</p> <p><b>(Only front elevation to be considered for area calculation)</b></p>	13	Sq.Mt.		0.00
c	<b>Pantry Storage (Shutters under Platform)</b>				
	<p>Providing and fixing Storage under Platform made of 18mm thk. FIRESAFE IS: 5509 plywood sheet finish with 1mm thick high glossed laminate sheet on outer face and 1mm thick white laminate sheets on inner face of the shutter; edge to be covered with aluminum profile section as per selection, shutters to have soft close hinges (Hettich/ Dorma/Haffele) with teak wood frame below platform. Item to be inclusive of 19mm thick interal horizontal laminated shelves, joining cleats, accessories, ss hardware, soft close drawer with ss basket, aluminum profile handles etc. complete. In side of storage to be finished with 1mm thick laminate etc. complete to the satisfaction of Bank's Engineer.</p> <p>(Measurement will be counted from front shutter's height &amp;</p>	1	Sq.Mt.		0.00
d	<b>Pantry Storage (Overhead Unit)</b>				
	<p>Providing and fixing Over Head Storage made of FIRESAFE IS: 5509 plywood sheet inside laminate finish with required 19mm thick aluminium profile shutters with back painted glass, required soft closing hinges (Hettich/ Haffle/ Dorma) &amp; glass shelves. Item to be inclusive of all accessories, storage shelves, lift up sutters, design grooves, moulded edges, aluminum profile, soft close hinges etc. complete. Inner side of the storage to have 1mm thick laminate finish etc. complete to the satisfaction of Bank's Engineer.</p>	1	Sq.Mt.		0.00
<b>SUB TOTAL : V : STORAGE CUPBOARDS</b>					<b>0.00</b>

S.No	Particulars	Qty	Unit	Rate (Rs.)	Amount (Rs.)
<b>6.0</b>	<b>MISCELLANEOUS</b>				
<b>a</b>	Providing and fixing <b>Digital Glass Frosting Film (3M)</b> for frosting as per design in all shapes including curve shapes etc. complete to the satisfaction of Bank's Engineer.	16	Sq.Mt.		0.00
<b>b</b>	Providing and placing in position <b>Center Table</b> of size 1200x600x450 mm with 40mm teakwood legs 62.5x35 mm teakwood frame at top as detailed. 10mm bevelled brown glass fixed in SS spacers on top. The table to be finished in melamine polish complete.	2	Each		0.00
	<b>SUB TOTAL : VI : MISCELLANEOUS</b>				<b>0.00</b>
	<b>GRAND TOTAL (Excluding GST)</b>				<b>0.00</b>