.No.	Description of Item	Qty	Unit	Rate	Amount
Α	Part A : Electrical Works :				
	ELECTRICAL WIRING WORK				
	Note: Use of Flexible conduits & Elbows in Circuit wiring is not allowed except in				
	exceptional site conditions with the approval of Bank's Engineer / Architect and All				
	wiring laying in the MS/PVC conduit strickle follow IE(Indian Electricity) rules, IS				
	code, follow in all items of project/ work execution. Proper ferrules, lux, thimble, gland termination to be done in all cabling & wiring from both load/source end.				
	Conduit carrying submain will not carry circuit/point wiring. Similarly conduit				
	carrying circuit wiring will not carry submain/point wiring. Conduit carrying point				
	wiring will not carry submain/circuit wiring. All Electrical works				
	(Cabling/wiring/panel etc) to be carried out as per layout/General Arrangement				
	(GA)Drawing attached only.				
1	ELECTRICAL WIRING				
	Providing, fixing, testing and commissioning of POINT WIRING of any length for				
	light point/Wall fan point/Exhaust fan point/ Call bell point/ including call bell/				
	including fan box(if required), 'S' type fan hook etc with 3 X 1.5 Sq.mm(P/N/E)				
	PVC 650V/1100V Grade FR insulated copper conductor single core multi				
	strended wire in 16 SWG(Medium Gauge) stove enamelled rigid steel conduit				
	20mm/25mm with conduit accessories like bend, junction box etc in concealed/surface manner as per site requirment with suitable Modular				
	Switches/Sockets with plate and Metal/PVC box,Scaddle, angle bracket (if				
	required), 3 plate ceiling rose/bulb holder etc. The floor/roof/wall junction box				
	shuold be of MS(heavy duty) box of suitable size and covered with Steel finish				
	Steel cover sheet by screw tight and gasket to avoid water/dust insertion. The item				
	includes Circuit wiring from DB to the switch board with 3x2.5 Sq.MM. The above				
	wiring carried out surface or recess in wall/floor/roof should be cutting by				
	cutter/chiesling, replastering, curing, painting with uniform and smooth finish by				
	specilised workman ship and making the surface neat afterwards complete in all respect as per direction of Bank Engg. (EACH Circuit to take NOT MORE than 7-8				
	points) The conduit/ Flexible conduit/junction box/metal modular box etc must be				
	ioined by gland and check nut at both ends. (each circuit to be controlled by one				
	Phase- Red, Neutral- Black, Earth-Green				
	Make of Material for items of BOQ:-				
	(i) Modular Type Switch/socket/step electronic fan regulator, plate, box,				
	TV/telephone, bulb holder/3 pin ceiling rose with all accessories:- Lergand/ Anchor(Roma)/MK/ Crabtree				
	(ii) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision				
	(iii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/				
	Havells				
0	Providing and fixing of point wiring with above specifications. One light point	60	Nos.		
а	controlled by one switch.	00	1105.		
b	Providing and fixing of point wiring with same above specifications. Two light points to be controlled by one switch.	30	Nos		
	Providing and fixing of ceiling fan point controlled as under				
С	(i) one 6 amp switch	16	Nos.		
	(ii) one no stepped electronic regulator of two module type.				
d	providing and fixing 6 Amps Plug Points with same specs as above and install along with same light switchboard	15	Nos		
	Master switch of 16 Amps(Only Grey/Golden/Wooden colour other than white				
е	colour) to install alongwith same light switch board to control all light as a master	15	Nos	1	

2	6 AMP. POINTS ON SEPARATE BOARD :			
	Supply,fixing,testing and commissioning of 1 No 6 A Multi Socket with 1No. 6 A switch (Modular type) with cover plate, sheet steel box / PVC modular box etc on surface / concealed manner l/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. (Minimum two and Maximum three points are loop with one circuit as mentioned	15	Nos	
	beolw)			
3	Power Wring (6 / 16 AMP. POWER POINTS)			
	Supply, fixing, testing and commissioning of 1 No 16 A switch & 1 No.six pin 6/16 Amp. Multi Socket (Modular Type) with cover plate, sheet steel box etc on surface / concealed manner I/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed.	18	Nos	
	(Maximum two points are loop with one circuit as mentioned below)			
4	SPECIAL POINTS : (For Computers)			
	Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate, PVC modular box on Surface / sheet steel box in concealed manner I/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed.	12	Nos	
	2 Nos. 6 A Switch + 3 Nos. 6 A, 3 pin Socket			
	(Minimum two and Maximum three points are loop with one circuit as mentioned beolw)			
5	AC/Geyser Point (Single Phase)			┨─────┤
5	Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. / GEYSER power point with the followings :			
	Metra Plug and Socket DBs with one Nos 20 Amp SP MCB, 20 Amp plug and socket with complete Enclosur plate and box 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as required as per site requirement and as directed by Bank	10	Nos	
	Engineer. OR Modular 32A DP 1 way switch with plate & box 1 set. + 25A & 10A twin socket			
	(Only one point is connected with one circuit as mentioned below)			
6	AC Point (Three Phase)			
	Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. Cassette power point with the followings :			
	Metal enclose Four way with one Nos 32 Amp FP MCB with complete Enclosur plate and box 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete as required as per site requirement and as directed. (Only one point is connected with one circuit as mentioned below)	6	Nos	
7	<i>CIRCUIT WIRING :</i> Supplying, providing circuit wiring for Power/UPS with following PVC insulated copper conductor single core multi strended wire (HRFR) in mentioned conduit i/c electrical connections in suitable size MS / PVC modular boxes and it laying, fixing, testing and commissioning in suitable size 20/25 mm dia,16 SWG (Medium Gauge) thickness rigid MS conduit with conduit accessories like bend/junction box/ fan box etcwith cover plate, sheet steel box/ PVC modular box etc on surface/ concealed manner i/c electrical connections and making goods all the damages,replastering, painting, cleaning the site etc complete as required as per site condition. The floor/roof/wall junction box should be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion. The length of circuit upto 30 meter length or loss approximate.			
	(i) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision (ii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/ Havells			
а	3 X 2.5 sqmm (For UPS Circuit/6 amp Separate Board) in suitable size of 16 SWG (MMS) steel conduit as per IS code.	15	Nos	
b	3 X 4.0 sqmm (For AC/Power Circuit) in suitable size of 16 SWG (MMS) steel conduit as per IS code.	12	Nos	

с	5 x 4.0 sqmm (for three phase AC Indoor Circuit) in suitable size of 16 SWG(MMS) steel conduit as per IS code.	6	Nos		
8	UPS OUTGOING & OTHER WIRING, As Per Requirment.				
	3 x 10 Sqmm copper multistreand wire in 25 mm 16 SGW (MMS) steel conduit.	_			
(a)	UPS INPUT DB TO UPS)	5	R.Mtr		
	3 X 1.5 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	45	D N #		
(b)	conduit.	15	R.Mtr		
(0)	3 X 2.5 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	25	D M+r		
(c)	conduit.	35	R.Mtr		
(d)	3 X 4 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	40	R.Mtr		
(4)	conduit.	-10	T.IVIG		
(e)	5 X 4 Sqmm. Copper multistrend wire in suitable size of 16 SWG (MMS) steel	60	R.Mtr		
.,	conduit (For Cassettee AC)				
(f)	3 X 6 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	40	R.Mtr		
	conduit.				
9	DISTRIBUTION BOARDS				
9	All MCB to be "C" series				
	Supply, installation, Testing and commissioning of the surface/recess mounting				
	following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar,				
	earth bar, din bar detachable gland plate, interconnection and making good all the				
	damages, painting, cleaning the site etc complete as required as per site				
	requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has				
	breaking capacity has 10 KA. Make of Materials				
	Panel- As per IS Standards/CPRI Tested.				
	DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only				
	(Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority,				
	otherwise it will not considered)				
	Supplying, installation, testing and commissioning of indoor type, sectionalised,				
	compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet				
	of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with				
	stiffers where required, having vibration free structure chemically treated with				
	seven tank process before painting for surface treatment and powder coated, with				
	aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50				
	Hz AC supply i/c providing and fixing the following switchgear mounted thereon				
	complete with gaskets and interconnections, connection as per specification complete as required.				
	complete as required.				
	(The board shall be dust & vermin proof with suitable degree of IP protection)				
	NOTE : All switchgears Ics shall be equal to 100% Icu.				
	Sheet 14 swg : panel sides,upper,lower,and Ft.doors				
	Sheet 16 swg : back side and compartments.				
~	Glande plates : 3 mm thick.	4	Noc		
а	Cable entry : Provision at bottom and upper sides.	1	Nos		
	The above panel belongs following as under:				
	A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored				
	Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports				
	with Antitracking barriers.				
	B.INCOMING SWITCHGEARS :(RYB LED Indicators for Both Main/DG)				
	(i) 1 No. FP.160 A , 25 KA MCCB with thermal magnetic trip unit with digital				
	voltmeter & ammeter with suitable size of CTs, selector switch etc.				
	C. OUTGOING SWITCHGEARS:				
	 (i) 2 Nos- 125Amp TP MCCB for main with 200amp bus bar with indicator. (ii) 160 amp onload changeover with 1 Nos 125 amp 25 KA, TP MCCB for DG 				
	supply with 200 amp bus bar with indicator				
	(iii) 200 amp bus bar for parallel connection with DG changeover output				
	(In) 200 amp bus bar for parallel connection with DG changeover output (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority,				
	otherwise it will not considered)				
				1	i i i i i i i i i i i i i i i i i i i

			1	
b	Supply & Installation of SDP(Surge Protector Devicve) for general protection of main Distribution Board Legrad Make Cat No. 412247 (3P+N), 40 KA, T2- Imax 40KA/pole with complete wiring.	1	Nos	
С	Providing and fixing 6 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN , controlling 18 Nos. 10/16/32 Amps SPMCBs. & Complete.	1	Nos	
d	Providing and fixing 4 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN , controlling 12 Nos. 16/32 Amps SPMCBs. & Complete.	2	Nos	
е	Providing & fixing 4 way vertical load line double door D.B for AC with 125 Amp. TP MCCB incomer and outgoing to be 2 Nos 32 amp TP MCB, 6 Nos 32 amp SP MCB	1	Nos.	
f	Providing and fixing (12) way SPDB double door type For UPS points with 1x32 Amps DP, controlling 10 Nos, 16 AMP SPMCB	2	Nos.	
g	Providing and fixing (8) way SPDB double door type For Light DB only for Emergency Lights like glow sign with timer etc alongwith 1x32 Amps DP, controlling 6 NO.10 A./16 AMP SPMCB.	1	Nos.	
h	Providing and fixing (4) way TPN double door type For UPS INPUT with 1x63 Amps TPNand 63 amp DP MCB- 3 Nos & 3 Nos, 32 amp SP MCB complete (E- lobby/UPS Output)	1	Nos.	
i	Providing and fixing of Kit Kat Rewirable Porcelian fuse carrier & base with wooden frame of 200 amp/415 Volt near meter box	1	Set	
10	CABLES			
	Supplying, unloading, storage, laying, testing and commissioning of PVC/XLPE insulated (Heavy Duty) Al/Cu conductor armoured cable suitable for working voltage upto and including 1100 V grade, laid and tied on existing overhead cable trays, or laid and tied over MS supports in masonry trenches with copper/al cable lugs, single compression brass cable glands, tapping, crimping etc. as required and all cables run with double run(2 No.) of GI wire of 8 SWG size. The size of cables are as under:-			
	Make of Material:- (i) PVC/XLPC Armoured cable:- Finolex, Havells, RR cable, CCI(Cable Corp. of India)			
	(ii) Cable Termination:- Dowells, Comet 3.5 X 70 Sq.mm XLPE. Al. armoured Cable(AC VTPN & BUS BARS)/Main cable	50		
а		50	Mtr	
b	3.5 X 50 Sq.mm XLPE. AI. armoured Cable(AC VTPN & BUS BARS)/Main cable	30	Mtr	
С	3.5 X35 Sq.mm XLPE.Al.armoured Cable (POWER)	35	Mtr	
d	4X 25 Sq.mm XLPE.AI.armoured Cable (POWER/LIGHT/UPS)	30	Mtr	
е	4X 16 Sq.mm XLPE.AI.armoured Cable (LIGHT/UPS)	60	Mtr	
11	EARTHING			
	COPPER PLATE EARTH STATION: Preparation of the Plate Earth Station:(As per IS:3043) (a) Excavation of hard rocky earth, soft murrum, hard murrum etc and back filling with black cotton soil for the earth station, the earth pit size is 1000 mm X 1000 mm X 2500 mm. (b) Supply and fixing of Copper Plate of Size 600 mm X 600 mm X 3.0 mm thick. (c) Eixing of 50 mm X 6 mm 2 Mtra copper string from Copper Plate to earth			
(i)	 (c) Fixing of 50 mm X 6 mm, 3 Mtrs copper strips from Copper Plate to earth terminal including brazing/welding at plate etc. (d) Supply and laying in position 19 mm, 2 Mtrs G.I "B" Class pipe for watering with reducer/funnel with mesh. (e) Supply and Fixing of the following in the earth station. (i) 75 Kg. Charcoal. (ii) 15 Kg. Original Salt. 	2	Nos	

((iii) Black Cotton soil of adequate amount. (f) Construction of earth pit chamber including necessary brick work concrete, plastering, S/F of C.I Cover of size 12" X 12" complete as per site requirment. 			

		-	-		
	G.I.PLATE EARTH STATION :				
	Preparation of the Plate Earth Station: (as per IS:3043)				
	(a) Excavation of rocky earth, soft murrum, hard murrum etc and back filling with				
	black cotton soil for the earth station, the earth pit size is 1000 mm x 1000 mm x				
	2500 mm deep.				
	(b) S/F of G.I. plate of size 600 x 600 x 6.0 mm thick.				
	(c) S/F fixing 50 mm x 6 mm, 3 mtrs G.I, strips from G.I.plate to earth terminal				
	including brazing / welding at plate etc.				
(ii)	(d) Supplying and laying in position 19 mm, 2 mtrs G.I. `B' class pipe for	2	Nos		
	watering.with reducer/funnel with mesh.				
	(e) S/F of the following in the earth station.				
	75 Kg. Charcoal, 15 Kg. Original Salt. and Black Cotton soil of adequate amount.				
	(f) Construction of earth pit chamber including necessary brick work concrete,				
	plastering, S/F of C.I. Cover of size 12" x 12" complete as per site req.and marking				
	its value and identification etc.				
	Providing and fixing Copper/GI strip as per specification compete including				
(;;;)					
(iii)	connection to earth electrode revetting/sweating/soldering, burying 15 cms below				
	in all types of soil/rocks etc complete as requiued.	10	N 4+r		
<u> </u>	(a) Copper Strip 25 X 5 mm	10	Mtr.		
	(b) G.I.Strip 25 X 5 mm	10	Mtr		
	(b) 6.1.5uip 25 X 3 mm	10	IVILI		
	Supply and laying of 10 Sq.mm 650V/1100 V PVC grade insulated copper wire in				
(iv)	15 mm G.I. Pipe ISI grade including all accessories complete as	30	Mtr.		
(10)		50	iviti .		
	required.(Dedicated Earthing for UPS output DB only)				
12	OCCUPANCY SENSORS:-				
12					
	Supply, installation, testing and commissioning of occupancy sensor				
	surface/recess mounted as per site condition complete with all	4	Nos		
	wiring/conduit/Switch etc complete in all respect as per site condition as required				
	Honeywell Make K5015/16, Siemens/Johnson Control				
	OR Equivalent as per Bank's approved.				
13	TELEPHONE POINT				
10	Supplying, Installation, testing and commissioning of the telephone point with the				
	followings				
	Two pair, 0.61 mm dla. telephone cable tinned copper conductor, P.V.C. insulated				
	and sheathed, fire retarding, anti termite, colour coded twisted pairs and rip cord,				
	Double outlet The length of telephone cable upto 35 meter length or less as per				
	site condition with shutter modular type Telephone Outlets ($RJ - 11$) wth				
	suitable size MS / PVC modular boxes and it laying, fixing, testing and				
	commissioning in suitable size 20/25 mm dia,16 SWG (Medium Gauge) thickness				
(i)	rigid PVC conduit with conduit accessories like bend/junction box/cover plate/sheet	2	Nos		
	steel/PVC box on surface/ concealed manner i/c electrical connections and				
	making goods all the damages, replastering, painting, cleaning the site etc				
	complete as required as per site condition. The floor/roof/wall junction box shuold				
	be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover				
	sheet by screw tight and gasket to avoid water/dust insertion.				
	Make of Material:- Delton/Finolex/RR cable				
	Complying and fiving of logge talenhang to a black or suffered as a second se				
	Supplying and fixing of krone telephone tag block on surface/ recess mounted with				
	its accessories suitable for the multi core telephone cable and shall accommodate				
	tin-plated phosphor bronze connectors, the connectors shall splice unskinned				
(ii)	cables up to 0.61 mm dia and shall be terminate both incoming and out going	1	Nos		
	lines, the tag blocks shall be mounted inside, water proof box and locking				
	arrangement and shall be fully accessible.				
	(A) 20 Doir tog block				
	(A) 20 Pair tag block				
	Supply installation toating and commissioning of the following size is the filler				
(;;;)	Supply, installation, testing and commissioning of the following size jelly filled	20	Mtr		
(iii)	armoured tehephone cable.	20	IVILI		
	20 pair				
1		1	1	1	

14	DATA CABLING FOR LAN			
а	Providing, fixing, testing and commissioning of all nodes of four pair UTP CAT 6 LAN cables length upto 30 meter length or less as per site conditionin suitable size 20/25 mm dia, 16 SWG wall thickness rigid PVC conduit with conduit accessories like bend/junction box/ fan box etc on surface/recessed manner and making good all the damages, painting, cleaning the site etc complete as required as per site condition and as directed as required. Junction box shuld be covered with Stainless steel plate with screw with gasket for protection of water/dust. Providing, fixing, testing and commissioning of modular type Information Outlets with suitable size of MS/PVC modular boxes complete, all accessories with insulation displacement connectors etc suitable for CAT 6 UTP cabling with RJ-45 socket with testing and commissioning of STP cabling with scanner for all the nodes/switches/jack panel complete (Each point/circuit/cable from both load and source end to be marked with ferrules.)	16	Nos	
	Make of Material:- (i) Data Cable, Cat 6 cable, Switch, Jack panel, Rack, Patch cords & Other accessories:- D-Link, Legrand			
b	Providing and fixing Patch Panels 24 port (100 base TX) CAT 6 patch/jack panel with connector, out lets and necessary connectivity complete as required & (D-Link make)	1	Nos	
с	Providing, assembling, fixing, testing and commissioning Floor/Wall mounted RACKS for gig switches, patch panels etc including cooling DUAL fan trays, a 10 Point PDU, Fixed Trays as necessarycomplete. 9 U wall mounted RACK	1	Nos	
d	Providing and fixing of flowing factory fabricated Patch cords. (UTP/CAT 6 complte			
i)	with connector on both side.) for 1 Mt. long	16	Nos.	
i) ii)	for 2 Mt. long	16	Nos.	
		10	1100	
е	Providing, fixing,testing and commissioning of four pair CAT 6 LAN cable in suitable size of 20/25mm PVC medium gauge 16SWG conduit including all accessories to interconnect the switches from different location.	20	Mtr	
f	Poviding, fixing, testing and commissoining of Jack Panel of reputated brand.	1	Nos	
15	TV POINT:-Supply, installation, testing and commissionig of TV point(Modular) with RG-6 cable in the Medimum Gauge 1.6 mm PVC Conduit with all accessories complete in all respect	2	Nos	
16	Supply and installation of Vinyl sticker for on Electrical DBs like, " Switch Off at Night", Switch Off For Safety, Specifications of DB's etc	10	Nos	
17	Making & Providing of 3 sets of Asbuilt Drawing with coloured print for entier Electrical work (Power/UPS/Light/Data/Telephone/AC etc.) as advised by the Bank's Authority.	1	Lum sum	
	Description of light /fan fixture			
	Supply and Installation, Testing and commissioning of the following fittings / equipments in surface/recess mounted as directed etc down rods of size upto 300 mm where ever required with ball sockets, anchor fastner etc complete as per site conditions. All fittings should be hang with suitable size of GI wire to four corner of fittings to the RCC rooftop with suitable size of anchor fastner/heavy gauge screw. The necessary arrangement is made by the contractor to install fittings in false ceiling especially 2'X2' and 4'X1' etc. as per instruction of Bank Engg.			
18	LED LUMINARES:- 2' x2' (FULL GLOW TYPE) LED light fittings (600 X600mm) dimension suitable for grid/gypsum ceiling complete with its electrionic driver as required per instruction of Bank's Model No are as under:- PHILIPS:- RC380B G2 LED 35S-6500 PSU OD WH LED (FULLGLOW)	28	Nos	
	WIPRO:- CRCO1ORO 38 HP57 HAVELLS:- LHECDIL7IL1W036 (Edge- Lit) CG:- LCTAR3-40-CDL			

	LED DOWNLIGHTER: 15 Watt, recessed mounted circular down lighter , 6" dimension with complete its											
19	electronic driver are as under:-											
	PHILIPS:- GREENLED-DN193B LED-12S-6500 PSU	50	Nos									
	WIPRO:- IRIS LED LD 71-121-XXX-50-XX											
	HAVELLS:- LHEBJNP ZPZ 1W 015(ENDURA LOW DEPTH) CG:- LC DD-15-CDL,											
	00 L0 DD-13-0DL,											
20	LED Spot Light, 3 Watt, 2/3"(Inches) size as per site requirment.	4	Nos									
	PHILIPS, WIPRO, HAVELLS, CG											
	LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- Supply,											
	installation, testing and commissioning of bright LED strip light with its electronic											
21	driver complete as required.	100	Mtr									
	PHILIPS, WIPRO, HAVELLS, CG											
22	BOX TYPE LUMINAIRES: LED TUBE FITTINGS, 1200mm, 18/20 Watt PHILIPS/WIPRO/HAVELLS/CG	20	Nos									
	PHILIPS/WIPRO/HAVELLS/CG											
	CEILING FAN:											
	Single phase heavy duty grease filled double ball bearing, aerodynamically											
23	designed heavy gauge aluminium blades, copper wounded and impregnated	16	Nos									
	silicon stamping motors etc 1200 mm sweep, brilliant white											
	CG/USHA/ ORIENT/HAVELLS											
	EXHAUST FAN:-											
	Single phase, 300mm sweep, 900 rpm, metallic exhaust fan of the following single											
	phase Exhaust fan continuously rated, capacitor start and run type, totally enclosed and ruggedly built, pre lubricated double ball bearing, copper wounded,											
24	A & E class insulation, dynamically balanced, below 40 db sound level etc, front	9	Nos									
	cover with grill/gravity louver for protection purpose with 12 mm plywood complete											
	in all respect make as under: CG/USHA/	1										
	ORIENT/HAVELLS/ALMONARD/ALSTOM											
	WALL FAN:-(Only Metallic Body)											
25	Oscillating wall fan with regulator i/c coonections etc complete as required as per	E	Noc									
25	approved make, Sweep 400/450 mm , RPM 1300 make are as under:	5	D NOS	5	5 NOS	5 NOS	5	5 1105	5	Nos		
	CROMPTON/USHA/ ORIENT/HAVELLS											
	Out Tatal - David A (Elastrical Mariles)											
	Sub Total : Part A (Electrical Works)											
в	Part B : AIR CONDITIONING WORKS :											
	AIR CONDITIONING WORK			1								
	Supply, installation, testing and commissioning of following AIR CONDIRIONERS											
	as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid											
	additionally by the Bank as applicable subject to GST Number. and system has											
	complete one year warranty & If any additinal warranty provided by											
	company/vendor in any specific part like compressor etc that is acceptable, please mentioned it. Rates include prime quality copper pipe if required extra on site											
	as per site condition.											
	Rates also includes Stablizer of approved make and KVA to be installed with											
	AC.											
	The rates inclusive of all repairs of civil and carpentry work The cost											
	includes original fill and additional top up of refrigerant gas as per site											
	condition. The rate inclusive of all chisel work, plastering, finishing, painting											
	& all civil related work pertaing to mentioned work. Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only											
<u> </u>												

26	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF BEE AIR CONDITIONERS 1.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display.	2	Nos	
	Note:- The rate should be inclusive of Tie rod and clamp support for copper wire Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only			
27	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF BEE AIR CONDITIONERS 1.5 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. Note:- The rate should be inclusive of Tie rod and clamp support for copper wire Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only	3	Nos	
28	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF BEE AIR CONDITIONERS 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. Note:- The rate should be inclusive of Tie rod and clamp support for copper wire and cables till outdoor.	1	Nos	

29	Supply, installation, testing and commissioning of Higher Efficient models of CASSETTE TYPE AIR CONDITIONERS(Three) BEE Certified rating 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 415 Volts + 10 %, three Phase, 50 Hz AC supply with Scroll compressor, Refrigerant (R-32) and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti dust , anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. Note:- The rate should be inclusive of Tie rod and clamp support for copper wire and cables till outdoor .	3	Nos	
30	Supply and installation of hard & prime quality of min. 22 G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex . Make of cable:Finolex/RR	80	Mtr	
31	Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installation. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:-SuperIon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells	40	Mtr	
32	Drain Pipe (If Required additional) Applicale to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:- Kasta/supreme	100	Mtr	
33	Electronic Timer for auto swith on/off to AC of server/ATM/E-lobby for 4Hr/8Hr.	1	Nos	
34	Make:- Legrand, L&T, and other Eq. ISI make Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make:-Microtek, V-Gards (Voltage Range 150- 280 Volts)	6	Nos	
35	Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 2Tn Split AC & 2 Tn Cassette AC) Make:- Microtek, V-Gards. (Voltage Range 150- 280 Volts)	4	Nos	
	Sub Total : Part B (AIR CONDITIONING WORKS)			

TOTAL WORK (A+B)