

**BILLS OF QUANTITIES FOR FURNISHING WORK OF STATE BANK OF INDIA FOR SCAB DEPARTMENT AT MAIN BRANCH, BHADRA,
LAL DARWAJA, AHMEDABAD**

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Words)	Amount
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills					
A	FURNISHING WORK					
1	<p>TABLES MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawer of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board tray with moused of metal of approved make shall be provided. All internal surface will have 0.60 mm thick balacing laminate.</p> <p>Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces. Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer nlished etc complete as directed Table shall have ready made CPU trolley with castors and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners</p> <p>Exposed edges of Table Top, Ready made Foot Rest & drawers shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete. All the surface without laminate / balancing laminate shall be lacquered polished of approved shade As per drawing and instruction of Architect/Bank work to be Completed.</p> <p>FINISHING DETAILS IN NUTSHELL: 1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished 2) Front Apron & Sides: 1.0 mm thick Dark Laminate 3) Facing of Drawers: 1.0 mm thick Dark Laminate 4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</p>	0	NO			
2	<p>Same as above Item-no-1 but Size: 5'-6"/5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. [FOR CM & OFFICERS] existing table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Locks and sliding channels, key boards including polishina beadina pattis etc complete.</p>	15	NO			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Words)	Amount
3	<p>SIDE CREDENZA (SIDE TABLE) Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Existing table to be used with renovation, changing of lamination, repairing of shutters, Drawers, Locks and sliding channels, key boards including polishing beading pattis etc complete.</p> <p>FINISHING DETAILS IN NUTSHELL: 1) Top : Dark Laminate & Burma Teak beading on Edges with pillshade 2) Front Apron & Sides: Frosty White Laminate</p>	11	SQ.MT			
4	<p>LOW/FULL HEIGHT STORAGE CABINET with Top & Front laminate finished. Storage of any height Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)</p> <p>FINISHING DETAILS IN NUTSHELL: 1) Top : Dark Laminate & Burma Teak beading on Edges with pillshade 2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions</p>	15	SQMT			
6	<p>LOW HEIGHT PARTITION WORK</p> <p>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed</p>	14	SQMT			
7	<p>FULL HEIGHT PARTITION WORK</p> <p>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR Providing and fixing both sides laminate full height partly glazed partition using 50mm x 50mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing minimum 8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 8 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstep shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed. <i>Height of the partition will be upto 18 feet</i> For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.</p>	226	SQMT			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Words)	Amount
8	<p>Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.</p> <p>Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing & instructions.</p>	2	SQMT			
9	<p>GLASS DOORS AND PARTITIONS</p> <p>P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch</p> <p>Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for null & nish</p> <p>The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.</p>	4	SQMT			
10	<p>PANELLING WORK</p> <p>P/F Wall panelling with laminate finishing for wall and Pillar etc</p> <p>Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect.</p>	40	SQMT			
11	<p>ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH OUT SIDE</p> <p>Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or equivalent</p>	20	SQMT			
12	<p>SOFT BOARD</p> <p>Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.</p>	1	SQMT			
13	<p>Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure.</p>	1	NO			

Sr. No.	Description	Quantity	Unit	Rate (In Figure)	Rate (In Words)	Amount
14	Charges for Temporary shifting of Branch Furniture at convenient location on GF/FF as per the instruction of Architect/Bank. Rate includes fixing / erecting counters, cash cabin arrangement of furniture to the entire satisfaction of Branch Manager / Bank. Rate includes dismantling existing furniture and storing/ stacking the same at a location as directed by bank	1	JOB			
15	Reconditioning of existing partitions and refixing of the same upto 8 feet height at designated place requires changing of laminate, modifying glass, door position, and polishing of beading pattis with necessary hardware etc. complete	140	SQMT			
TOTAL COST "A"						

Note:

[a] In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this

[b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balancing laminate of approved make & shade in the all S.W Counters/Tables/ Credenza, Storage Cup Board etc.

[B] BUY BACK OF OLD FURNITURE

Dismantling & Removing Existing Full/Low Height wooden partitions, Tables, SideTable, Storage, Panelling, Sofa etc including stacking debris and reusable material as directed including carting away debris all levels from existing premises and buy back of furniture which is not required by Bank. as follows

1	CASH / S.W COUNTER	4.5	RMT			
2	12 mm thick glass partition on S.W Counter	1	SQMT			
3	Wooden Partition for Cash Cabin with Aluminium grills	4	SQMT			
4	Wooden partition for S.W Counter	7	SQMT			
5	Wooden Partition for Record Room/ Manager Cabin & other partition	50	SQMT			
6	Wooden Panelling	20	SQMT			

TOTAL COST OF BUY BACK "B"

SUMMARY

[A] FURNISHING WORK

[B] LESS BUY BACK OF OLD FURNITURE

(-)

[C] TOTAL COST OF FURNISHING WORK "C" [A - B]

The above tentative estimate includes using existing furniture, partition, flooring and false ceiling