

Ref No. DIC/58SBI/2k23/Waring Khera/Tender

TENDER FOR INTERIOR FURNISHING, WORK FOR STATE BANK OF INDIA AT WARING KHERA (51328)		
Sno.	Description	DETAIL
	INTERIOR & FURNISHING WORK	
1.0	WALL PANELING WORK	
2.0	PARTITIONS WORK	
3.0	DOORS	
4.0	FALSE CEILING WORK	
5.0	FURNITURE WORK	
6.0	MISCELLANEOUS WORK	
a	VALUE OF THE WORK	

Signature and seal of Contractor's

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
1	PANELING/PARTITON				
	Note: (i) For the works of paneling, full height partitons and low height partitons measurement shall be done only for plain visible surface, no extra cost for extrusions or extra frame work required will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.				
	(ii) All ply to be sprayed with anti terminate and anti borer spray.				
1	WALL PANELING				
1.1	Providing and fixing of paneling on column/wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mm x25 mm x1.5 mm wall thickness (Make Jindal/ Hindalco/ Indal) with maximum spacing @ 600mm c/c both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm HDF Ply (Moisture content- <8 %, Water Absorption 5% after 2 Hours Soaking)(Make. GREENPLY/ Century / Duro) and finished with 1.0 mm thk. laminate(Make- Sunmica/ Green lam/ Century/ Merino) of desired shade design and gloss of approved makes. Wooden molding, lipping etc. shall be provided wherever required as per drawing in desired shade. . The work shall also include the cost of making cutouts for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc.	772.00	Sq.ft		
1.2	ACP SHEETS WALL PANELING				
a	Providing and fixing Aluminum Composite Panel (Makes- Alstrong/ Alucbond/ Euro bond/ flexi bond) as per the approved makes wall cladding with the 3mm thick PVDF coated aluminum composite panel (ACP) (0.25 mm coil thick) with frame of aluminum channels (25 x 50 x 1.5 mm), (Make Jindal/ Hindalco/ Indal)cleat angle (8 x 18 x 2mm) necessary hardware, backup material and weather sealant to make the joints leak proof. The spacing for the channel along the length and spacing of cleat on the perpendicular shall not be more than 600mm.	625.00	Sq.ft		
Total of Wall Paneling work					
2	PARTITIONS WORK				
2.1	FULL HEIGHT PARTITIONS:				
	Providing and fixing wooden full height partition with following specifications:	169.00	Sq.ft		
	(a) Supporting system comprising of Aluminum Frame Work of 50mm x 50mm x 1.5 mm wall thickness,(Make Jindal/ Hindalco/ Indal) square section max. 600mm c/c both horizontally and vertically. The bottom member shall be aluminum extruded section of size 50mm X 50mm X 1.5 mm wall thickness. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				
	(b) Fixing 8mm thick HDF ply (Moisture content- <8 %, Water Absorption 5% after 2 Hours Soaking)(Make. GREENPLY/ Century / Duro) on both sides finished both side with 1.0 mm thk. laminate(Make- Sunmica/ Green lam/ Century/ Merino) (premium range) of approved shade with groove pattern as per architect instructions. Grooves to be 3mm deep and 12 wide finished with mica. 12 mm thick clear float toughened glass fixed with Teak wood beading of finished size 37mm x 25mm all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. Joint shall be located strictly as shown in the drawing. All exposed woodwork to be melamine polished (paid separately). All complete as per approval of the Architect/ engineer-in-charge.				
2.2	LOW HEIGHT PARTITONS:				
	Providing and fixing low height partition with following specifications:	54.00	Sq.ft		
	(a) Supporting system comprising of Aluminum Frame Work of 50mm x 50mm (16 Gauge) square section max. 600 mm c/c both horizontally and vertically. The bottom member shall be aluminum extruded section of size 65mmX50mmX16 Guage frame shall be fixed rigidly at floor level and ceiling level with rawal plugs/steel lugs wherever possible. The rate should also include necessary strengthening with additional members at door and other openings.				
	(b) The partition shall have 8mm thick HDF ply fixed on both sides with screws for the entire height of the partition and finished with approved 1.0 mm Thk. Laminate of desired shade, design and gloss on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with 1.00 mm laminate of desired shade, design and gloss. All teak ply/wood to be treated with wood preservative of approved ISI quality. All teak ply/wood shall be finished with high gloss spirit polish of approved shade.				

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
	(c) The low height partition shall have 12 mm thick Toughened glass as per design fixed with stainless steel wall cladding profile (WCP) at bottom and sides. All the edges of the 12mm thick Toughened glass shall be duly grinded/bevelled and exposed wooden surfaces melamine polished.				
2.3	12MM THICK TOUGHENED GLASS PARTITIONS				
	Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughened the same.	164.00	Sq.ft		
	The cost to include all hardware (PATCH FITTINGS etc) required of approved equivalent make viz. single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed.				
	The cost to include the cost of beveling and smoothing of the exposed edges of the glass.				
2.4	12MM TOUGHENED GLASS FOR FRONT AND SIDE OF COUNTERS				
	Providing and fixing 12 mm thick, clear plain toughened glass of approved pattern fixed in vertical position at counter front/ side of low height partition as per drawing, fixed on wooden partitions with superior quality stainless steel patch fittings of ebco/godrej/ozone. An opening as per the drawing at the bottom for transaction shall be provided in case of glass in front of the transaction counter. All the edges of the glass shall be grinded/bevelled and polished. The glass shall also be etched as per the design. Glass area with maximum height shall be measured for the purpose of payment. The work shall be carried out as per drawings.	25.00	Sq.ft		
Total of Partitions Work					
3	DOORS				
3.1	Wooden Door Frame of 50 x 75 mm of MP teak wood to be provided in wall / partition wherever door is required to be provided finished with melamine polish and fixed with fastener of approved make.	32.25	R.ft		
3.2	Providing and fixing ISI marked flush door 30 mm thick shutters (Make-Duro/ Century/ Archid/ Green) conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched 3 ply veneering with vertical grains or cross bands and finished with 1mm thick Laminate (Make- Sunmica/ Green lam/ Century/ Merino) of approved shade with groove pattern as per instructions of architect / engineer -in- charge. on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws. All edges of shutter sealed with CP teak wood edging slip of finished section 34mm x 6mm approx. on all sides. Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) with screws. The item inclusive mortise handle & lock, door stopper, (Makes- Godrej/ Dorset/ Dorma) All complete as per approval and instructions of the Engineer incharge/Architect.	50.75	Sq.ft		
3.3	Flap Door/ wicket door				
	Providing and fixing ISI marked Wicket door 30 mm thick shutters (Make-Duro/ Century/ Archid / Green) conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched 3 ply veneering with vertical grains or cross bands and finished with 1mm thick Laminate (Make- Sunmica/ Green lam/ Century/ Merino) of approved shade with groove pattern as per instructions of architect /. C.P. teak wood beading on all edges, all teak wood lipping to be melamine polished. The flap door shall have double action door hinges and a tower bolt at suitable location.	11.25	Sq.ft		
3.4	12MM THICK TOUGHENED GLASS DOORS :				
	Providing and fixing in position 12mm clear float toughened glass (Makes-Modi / Asahi / Saint Gobin) for door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required approved make its accessories, top pivot, center lock, 300mm glass door handles (Make Godrej/ SXL C series (Dorma)/ OPF series (Ozone) etc. as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work etc., complete as directed.	89.25	Sq.ft		
3.5	Floor spring (Make Everite/ Dorma/ Godrej) heavy duty of approved make.	4	Nos		
3.6	HYDRAULIC DOOR CLOSER: (Make-Doorking/ everite/ Dorma/ Ebco)				

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
	Providing and fixing silver color (or matching with color scheme as per site) of approved make hydraulic door closer to doors complete in all respects.	6.00	Nos.		
3.7	NIGHT LATCH LOCK:				
	Providing and fixing night latch lock (make Doorking/ everite/ Dorma/ Ebco) in wooden doors,complete in all respects.	1	Nos.		
3.8	FIRE DOOR: Supplying & fixing				
	P/F KFD 40mm thick STEEL -MATE powder coated,120 minutes fire rated (for Stability & integrity) GI steel or Galvanized (Zinc Coated)steel Door and frame by KFD confirming to IS 3614 part 2& BS 476 part 22.the Door shutter made of with 0.8 mm thick steel pressed formed to provide a 46 mm thick fully flush double skin door shell with lock seam joint at stile edges. the internal construction of the door to be phenolic .resin impregnated specially designed honeycomb craft paper with suitable internal reinforcement. Suitable reinforcement is to be providing in the door shutter to receive the hardware and hardware to be fixed on the door with no visible screw other then in the glass beading The doors with double shutters are to be provided with astragals on both sides and astragals to be fitted to the door without any screw. The shutter to be fixed with SS Hinges (Size 100X75X3mm), handle, locking etc with complete fittings.				
	The door frame (Section size 100X50) made from 1.2mm thick GI steel/GP steel pressed to single rebate profile for better structural strength. Frames are to be fixed to the wall with fasteners The gap between the frame & the shutter should not exceed 3mm on all sides except at the bottom where the gap can go upto max. of 5/7mm. The entire assembly to be pre-finished, factory-finished heat ovened, powder coated.	21	Sq.ft		
3.9	Supplying and fixing of Dorma or Dline or equivalent make 2 hrs fire rated door closer with 10 yrs warranty tested to BS-476 Part 22 to the entire satisfaction of Engineer-in-charge.	1	Nos		
Total of Doors Works					
4	FALSE CEILING				
4.1	GYPSON BOARD FALSE CEILING WITH STEPS:				
	Providing and fixing suspended false ceiling including steps and provision of cove lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board (Makes-Gyproc (saint gobain)/ India Gypsum) to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel(MF6a of dimension 20mmX27mmX37X3.5m) fixed round the perimeter to receive and of the ceiling section (MF5) and outer edge to gyp-board. The intermediate channel (MF7 of dimension 15mmX45mmX0.9mmX3.5M) at 1200mm c/c in the one direction and the ceiling section (MF5 of dimension 80mmX26mmX0.5mX3.5M) at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger(MF8) of dimension 25mmX9.5mm at 1200mm c/c on both ways from the structural soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleat and for joining ends of channel section together.	486.00	Sq.ft		
	The Gypsum Board (Makes-Gyproc (saint gobain)/ India Gypsum) layers to be screwed to the M/F ceiling sections with gyp-board dry wall screws. Jointing and screw spotting are then carried out as per manufacture's standard recommendation. Perimeter Channels (MF7) to be used around the cuts outs for light fittings. A/C ducting etc. The work should be complete as per instruction of architect or engineer in charge including 2-3 coats of oil bound distemper,over a coat of primer.The rate should be inclusive of making opening with frame etc. For electrical/air conditioning, A.C grill & trap door etc .if required and finishing of ceiling in all respect.payment shall be made only for exposed surfave & actual measurement at site.The work includes cost and conveyance of material and labour charges including all operational charges,tools lift and all height etc.				
4.2	GRID FALSE CEILING:MINERAL FIBRE (Make Armstrong/ Saint Gobin)				
	Providing and fixing in true horizontal level False ceiling grid system as per the apprved makes. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions.	560.00	Sq.ft		

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
	Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched at every 1200mm c/c maximum and 1200mm cross tee at every 600mm c/c maximum and 600mm cross tee at every 1200mm c/c maximum and wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm prestraightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of premier mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as per manufacturer's specifications.				
Total of Ceiling Work					
5	FURNITURE Work				
5.1	TABLES WITHOUT SIDE CREDENZA (Finishing with 1.0mm thick Laminate)				
	(a) Providing and fixing at site, Officer's tables made of 19mm th. commercial ply (Makes-Century/Green ply/Archid) with 1.0mm thick Laminate (Make- Sunmica/ Green lam/ Century/ Merino) of desired shade , design on outer visible surfaces; single color on horizontal & vertical surfaces. The front of the table top shall be projected and curved as per drawing. Provision for 3" dia cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. CP TEAK wood lipping will be provided on all the edges of the table, including melamine Polish and bottom touching the floor and the drawers				
	(b) The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 19mm commercial ply fixed with sliding telescopic channels (Makes-Hettich / Haffele/ Godrej/Ozone) of approved make.				
	(c) There shall be provision of one storage cabinet 1'-3" wide.The frame shall be made with 19mm thick commercial ply. The cabinet shall have Three lockable drawer running on side mounting drawer slides (channels) (Makes-Hettich / Haffele/ Godrej/Ozone) of approved make & one cupboard with shutter beneath the drawer, made of 19mm thick commercial ply finished with 1.0mm thick Laminate (Make- Sunmica/ Green lam/ Century/ Merino) of desired shade & design. All fitting / accessory shall be of approved make. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick Commercial ply front of 19mm thick Commercial Ply (Makes-Century/Green ply/Archid)				
	(d)The work shall also include provision of foot rest made with Sal wooden member of section 3" x 1.5" across the leg space.				
	(f) All other surfaces i.e. inside / legsapce of table, inside of drawer /cupboard shall be provided with 0.8mm thick laminate (Make- Sunmica/ Green lam/ Century/ Merino) of desired shade/design and gloss, and wood lipping / beading Excluding Melamine polished. The table shall have a CPU ledge made of 19mm thick Commercial Ply on one side, complete as per drawing.				
a	Branch Manager (6'-0"x3'-0"x2'-6")	1	Nos		
b	Investment Desk (5'-0'X2'-6"X2'-6")	1	Nos		
c	Officer Table (4'-6"x2'-6"x2'-6")	2	Nos		
5.2	Side credenza made of 19mm thick commercial ply (Makes-Century/Green ply/Archid) frame and 6mm thick commercial ply on back side & 1.0mm thick Laminate (Make-Sunmica/ Green lam/ Century/ Merino) on top horizontal surface , one vertical visible side only, with C.P teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 1'-6" wide outer to outer, containing Two drawers Horizontal running on side mounting drawer slides(channels) (Makes-Hettich / Haffele/ Godrej/Ozone)of approved make. The sides of the drawer shall be made of 12mm thick Commercial Ply (Makes-Century/Green ply/Archid) (bottom of 6mm thick plywood & front of 19mm thick Commercial Ply (Makes-Century/Green ply/Archid). The remaining part of the credenza will have open cupboard with shutters and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica(Make- Sunmica/ Green lam/ Century/ Merino) of desired shade, design, gloss and Including the exposed wood shall be malamine polished in desired shade.				
a	SIDE CREDENZA Size (3'-6"x1'-6"x2'-6")	1	Nos		
5.3	SWO COUNTERS: (AS PER NEW DESIGN AND SPECIFICATIONS)				
	Providing and fixing at site, SWO Counter made of 19mm th. commercial ply (Makes-Century/Green ply/Archid)	5	R.ft		
	Providing and fixing 3 no,s drawers as per drawing made from 19mm thick Commercial ply on front side and 12mm thick on sides and 6mm thick ply wood on bottom. Drawer slide on telescope channels ,handle, lock of approved make & fixing 1.00 mm thick laminate of approved make on front side etc complete in all respect as mention below:-				

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
	(a) Supplying and fixing metal keyBoard of Ebco Earl Bihari make or its equivalent in counter as per design and instructions.				
	(b) Working table top and edges shall be finished with 6 mm thick white corian of approved make (Merino/ LG/ Aludecor / Dupont), as per drawing and direction with all labour and materials all edges should be finished with corian.				
	(c) Transaction top: 3x6 mm thick flexy ply wood round shape with 6 mm thick white corian shall be provided at in front as per design & all edges should be finished with corian as well.				
	(d) Front pannel (Front Apron) shall be finished with 1mm thick 1'-6" high blue Glossy Laminate of approved make (Make- Sunmica/ Green lam/ Century/ Merino) and fixed on 19mm thick commercial ply wood (Makes-Century/Green ply/Archid) along with the provision of back LED light as per manufacturers specification of approved make all complete as per drawing.				
	(e) Foot rest of 3" x 1.5" in sal wood. and CPU stand 16" x 24"				
	(f) All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
	(g) All fittings like S.S.handle make (Godrej/ Dorset/ Dorma) or equivelent make. Auto Lock to each drawer and cabinet doors, piano hinges, ball catcher stopper, metal cable manager etc. heavy duty full extension channel in drawers.				
	(h) Heavy duty telescope full extension slidding channel of (Makes-Hettich / Hafele/ Godrej/Ozone) make shall be used in all drawers				
	(i) All inside & back surfaces to be finished with 0.8 mm laminate (Make- Sunmica/ Green lam/ Century/ Merino) of approved make & choice. However apart from that any other surfaces without laminate shall be painted as/approved shade.				
	(j) Counter shall be made independent in Length of 5'-0" and properly placed between two partition. Counter for measurement between two partition shall be measured and paid (Drawing as enclosed herewith)				
	(k) Finishing detail in nutshell : (For S.W Counter & Cash Counter)				
	(k-1) Table Top : 6 mm thick white corian (Make Merino/ LG/ Aludecor / Dupont)				
	(k-2) Front Apron: Round corian and Bottom 1 mm thick blue laminate (Make- Sunmica/ Green lam/ Century/ Merino)				
	(k-3) Facing of Drawers: 1.00 mm thick laminate Finish (Make- Sunmica/ Green lam/ Century/ Merino)				
	Note: The contractor to get the sample of the counter approved from the Architect/Bank Engineer before covering it with laminate without any extra cost.				
5.4	SHUTTERS BELOW GRANITE COUNTERS				

TENDER FOR INTERIOR FURNISHING WORK OF STATE BANK OF INDIA, WARING KHERA.(51328)					
Sl. No	Description of Item	Qty.	Unit	Rates	Amount
A	INTERIOR WORKS				
	(a) Providing and fixing Low Height storage cabinets of size 2'-6"(High)x 1'-6"(Deep) along the walls/partitions, as per interior drawings,using 19mm Commercial Ply (Makes-Century/Green ply/Archid) for shutters, vertical and horizontal partitions, 6mm ply for the back.1.0 mm thick laminate (Make- Sunmica/ Green lam/ Century/ Merino) of approved shade on top, vertical and horizontal visible surfaces. The shutters shall be overlapping on the carcass and shall be provided with suitable hinges with autoclose & soft close. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the ply shall be provided with wooden lipping 19mm x 3mm,duly Including melamine polished in desired shade.The inner surface shall be provided with 0.8mm thick laminate (Make- Sunmica/ Green lam/ Century/ Merino) of desired shade, design and gloss. The cabinet shall be complete with handles, knobs, locks and magnet catchers (Makes- Godrej/ Dorset/ Dorma) etc.to the satisfaction of the Architect/Engineer	18	Sq.ft		
5.5	Low Height Storage (2'-6" height)				
	(a) Providing and fixing Low Height storage cabinets of size 2'-6"(High)x 1'-6"(Deep) along the walls/partitions, as per interior drawings,using 19mm Commercial Ply (Makes-Century/Green ply/Archid) for shutters, vertical and horizontal partitions, 6mm ply for the back.1.0 mm thick laminate (Make- Sunmica/ Green lam/ Century/ Merino) of approved shade on top, vertical and horizontal visible surfaces. The shutters shall be overlapping on the carcass and shall be provided with suitable hinges with autoclose & soft close. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the ply shall be provided with wooden lipping 19mm x 3mm,duly Including melamine polished in desired shade.The inner surface shall be provided with 0.8mm thick laminate(Make- Sunmica/ Green lam/ Century/ Merino) of desired shade, design and gloss. The cabinet shall be complete with handles, knobs, locks and magnet catchers (Makes- Godrej/ Dorset/ Dorma) etc.to the satisfaction of the Architect/Engineer.	58.75	Sq.ft		
5.6	WOODEN BOXING FOR THE ELECTRICAL PANEL				
	Providing and fixing at site wooden boxing for the electrical panel as per the design and drawing. The carcass shall be made of 19mm thick commercial Ply (Makes-Century/Green ply/Archid) finishing with 1mm thick Laminate of desired shade, design and gloss on the outer surface. The carcass shall have intermediate band and skirting of 1mm thick Laminate (of desired shade, design and gloss. The shutter shall be mounted on the SS Piano hinges and provided with magnetic catcher, lock and tower bolts as required etc. All the visible edges of ply shall be provided with teak wood lipping, With Melamine Polish. All interior surfaces and back of shutters shall be provided with 0.8mm thick mica. the cabinet shall be complete with all necessary hardwares like locks,handles, catchers, towerbolts etc. Measurement will be done for front surface area.	49.5	Sq.ft		
Total of Furniture Work					
6	MISCELLANEOUS WORK				
6.1	Providing and fixing Zabra blinds (Makes-Vista levior/ MAC/ Deck) of approved shade and make having dust resistant fabric and all complete as per manufacturers specification .	98	Sq.ft		
6.2	Glass top				
a	providing and supplying 8 mm thick glass with its edges duly bevelled & grinded on all sides	18	Sq.ft		
6.3	Pin Up Board				
	providing and fixing 12 mm thick soft board over 12 mm thick commercial ply (Makes-Century/Green ply/Archid) fixed in wooden frame made out of commercial champ wood out of size 2.5 " x 1.5" (duly polished). The work shall be completed by covering the soft board with fabric/tapestry of approved	11	Sq.ft		
6.4	WRITING DESK/CUSTOMER VOUCHER STAND including pass book cheque drop & suggestion box				
	Providing & fixing forms stand of size 4'-0"X1'-6"X3'-9" with 3 nos storage units of forms with 12mm glass top fixed with 3" S.S spacetr.spacer for housing voucher of size 1'-6"X1'-0"X0'-9" is also provide on the top and side(L-shape wall hung) as per drawing made of 19mm thick commercial ply with 1.0mm thik. laminate to be fixed and 3/4" X1/4" teak wood lipping on two visible sidea on it all exposed teak wood edge/ teak wood lipping/beading shall be sprit polished with matching pigment etc. To be fixed on the wall cost of spacer etc. All inclusive complete.	1	Each		
MISCELLANEOUS WORK					