BOQ FOR INTERIOR FURNITURE AND ALLIED CIVIL WORK AT SBI, Diphupar BRANCH NAGALAND						
SI.No	Description of items	Unit	Qnty	Rate(Rs.)	Amount(Rs.)	
1	SWO COUNTER: Supply and installing new SWO Counters of overall size 1680 mm X 1830 mm X 750 mm, including cost of side credenza (1200mm x 450 mm x 750 mm) made up of 19 mm thick Block board of approved brand all around and finished with laminate of not less than 0.8 mm thick of approve colour, brand and shade. The cost to include three drawers of 375 mm wide made up of 6mm/12mm ply of approved brand on right hand side of the table on telescopic slider with partitions for keeping of notes of different denominations, a keyboard tray 250 mm wide, CPU stand, foot rest as designe and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood bidding/lipping stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type auto lock. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature on front with flexi ply. Counter & Credenza top to be provided with 8mm thick glass duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/Kitply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam/Merinolam or equivalent.	Each	4			
2	Providing & fixing counter Front 12 mm thick float glass with polished edges,fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Rate shall includes fixing of frost film as per design & directed, cost of studs, making cut-outs for transaction and voice hole.	SQM	5			
3	Providing & Fixing 12 mm thick float glass of size 320mm (width) x 1100mm (height) & tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout & elevation policy, fixed with silicon and T.W beading support on wooden partition as directed, on either sides of SWO as per design. Rate shall includes etching of glass as directed by bank. All edges of glass shall be duly beveled & polished as directed complete. Make: Saintgobin/ Modiguard or equivalent.	SQM	1.5			
4	Supply and installing of size- 2130 mm x 930 mm x 750 mm including cost of side credenza (1080mm x 600mm x 750 mm) for Branch Manager made up of 19mm thick Block board all around, finshed with not less than 0.8 mm thick laminate of colour, shade & brand as approved. The table cost to include (pedestal), three drawers of 450 mm wide made with 6mm/12mm ply on right hand side on telescopic slider and a keyboard tray 250mm wide, CPU stand, foot rest as per design and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/ bidding of requierd size stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	Each	1			
5	Supplying and installing Tables of Overall size - 1680 mm X 1830 mm x 750 mm including cost of side credenza (1230 mm x 450 mm x 750 mm) made up of 19mm thick block board of approved brand all around and finished with not less than 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	Each	3			

				1
6	Providing and fixing floor mounted writing desk of size 1200mm x 300mm x 900mm(H) made of 19 mm/ 12 mm ply finish with not less than 0.8 mm thick laminate and with 12 mm thick float glass on top and voucher pigeon holes as per design & direction of bank, with laminated boards support.	Each	2	
7	Fabricating and installing Grahak Mitra table of overall size - 1520mm x 600mm x 750 mm in straight or curved profile made up of 19mm thick block board of approved brand all around and finished with not less than 0.8 mm thick laminate of brand, colour and shade as approved by the Bank. The table cost to include three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide, foot rest & CPU stand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type. All exposed edges to have wooden lipping/bidding of requierd size, stained to match the desk and melamine finished. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on table and necessary cut-out to accommodate wires, edges to be m/c polished, with m.s. powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	Each	1	
8	Low ht storage unit: Providing and fixing storage units of size 450 mm x 750 mm, made up of 19 mm thick block board of approved brand on top & vertical support and finished with not less than 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of requierd size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brancd. The works to include all hardwares such as: castors, brass hinges, ball catchers, ,locks , handles etc. of Godrej or approved make. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	RM	10	
9	Fabricating and fixing column/wall paneling with 12 mm thick ply finshied with not less than 0.8 mm thick laminate of approved shade & brand over 25 mm x 35 mm (thickness notless than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface. Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy. Rate inclueds removal of existing furniture. Center columns, BM Chamber wall, Back of SWO wall. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	75	
10	Fabricating and fixing full height semi glazed/solid partition , made of 6 mm ply of approved brand in both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middile portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall inclueds etching of glass as requierd by bank. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	33	
11	Providing and fixing low height semi glazed wooden partitions made of 6 mm ply of approved brand in both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Top portion from 900 mm to 1500 mm height shall have 12 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished as per designe and direction by bank. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Rate shall includes making provision for fixing of counter top 12 mm glass on its edges with neccessary fixing arrangment as directed. Rate shall inclueds etching of glass as requierd by bank. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	29	

Providing and furning Samily glassad/Solid doors shutter made up of 36 mm thick block band of approved brand, croisul and shutter Dots in the Similar Solid Mine To 200 mm to 20						
made up of 38 mm thick binds board of approved brand and finished with not less than 0.0 mm thick binds of approved proteing and direction of bank. The Goor shall includes all hardware such as: as hippe with counteraint is a server, handle, door coloser, door includes all hardware such as: as hippe with counteraint is a server, handle, door coloser, door polishing programs and server. Phylibook Board Makes MR Grade of Centruly Creen/Archighy or equivalent. Phylibook Board Makes MR Grade of Centruly Creen/Archighy or equivalent. Phylibook Board Makes MR Grade of Centruly Creen/Archighy or equivalent. All caminate Make: Greeniam/Contrulystam/Melinotan/Archidam or equivalent. MAIN GATE: Providing and fixing glazed door made of 12 mm thick bat glass with frostate drift finished in the between top 8 bottom rail and side stell of plywood farmwavsk of size 125 mm x 50 mm. The farmworks to be finished with not less than 0.8 mm thick liaminate on both side. Class to have add ethed design pattern with logo as directed. Doors to be mounted on heavy duty for appropriation of central patterns with logo as directed. Doors to be mounted on heavy duty. Providing & fixing in position Aluminium Composite Panel (ACP) / Shutter boxing Panelling with flaming in 800 mm CCC bath ways. Maintain 3 mm titles. ACP to be fixed over the sequence of the sequence of the sequence of the panel of the sequence of t	12	approved brand and quality, finshed both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Middile portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall inclueds etching of glass as requierd by bank. Rate inclueds removal of existing furniture. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent.	SQM	4		
film fixed in between top & bottom mail and side attile of phywood framework of size 125 mm x.50 mm. The framework to be inhished with not less sham 0.8 mm thick laminate no both side. Glass to have acid actived design pattern with logo as directed. Doors to be mounted on heavy duty floor spring/door obser. Reta shall includes a hardware such as: Two nos S. S. finish handle, lock, door stoper, hinge, tower bott etc. of approved make. Rate includes removal of existing furniture. Providing & fining in position Aluminium Composite Panel (ACP) / Shutter boxing Paneling with framing in 600 mm CC both ways. Minimum 3 mm thick ACP to be fixed over the framwork with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Akobond or equivalent ISO certified or approved brands to be used. False ceiling: Providing and fixing suspended false ceiling with 600x600 mm size & 12mm with thick mineral liber ceiling lites of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lightsein-conditioning gills as per design direction by batik. Rate includes removal of existing lightsein-conditioning gills as per design direction by batik. Rate includes removal of existing furniture. Gypsum board false ceiling: Providing and fixing suspended 12mm thick Gypsum board false ceiling with Cl framework of shanderd gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fillings, cove light etc. complete as per design direction by bank. Rate included removal of existing furniture. Providing & fixing highest per formation of the complete as per design direction by bank. Pate included removal of existing furniture. 19 Supplying, providing and fixing Godriej Cyfindrical	13	made up of 38 mm thick block board of approved brand and finshed with not less than 0.8 mm thick laminate of approved shade and brand as per design and direction of bank. The door shall includes all hardware such as: so hinge with countersunk so screw, handle, door coloser, door stoper etc. of approved make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent.		7		
with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the fearmwork with 3M or equivalent adhesive and mirror screen in 600 with panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. False celling: Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as premauricaturer's specifications. The item to include cost of making necessary culcusts of the including furniture. Gypsum board false ceiling: Providing and fixing suspended 12mm thick Gypsum board false ceiling with Gif framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include panting with lustre paint and making necessary design, pattern & cut out for light filtings, covel light etc. complete as per design direction by bank. Rate includes removal of existing furniture. Providing & fixing in place 100 mm. Vertical bilinds with scotch guard of approved make, quality and colour shade & pattern. Rate shall include necessary filtings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate. SQM 40 PART: B: ALLIED CIVIL WORK Dirck work in Cement mortar 1:4 (1 cement: 4 coarse sand) with 1st class bricks including 1 racking out joinis and cuting complete as directed in all levels. 12 min thick cement plaster in single coat on fair/rough side of brick/concrete walls for Interioriexterior plastering in all levels finshed even and smooth including curing complete as GOM 58 Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer fail	14	film fixed in between top & bottom rail and side stile of plywood framework of size 125 mm x 50 mm. The framework to be finished with not less than 0.8 mm thick laminate on both side. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring/door closer. Rate shall inclueds all hardwears such as: Two nos S.S. finish handle, lock, door stoper, hinge, tower bolt etc. of approved make. Rate inclueds removal of existing	SQM	7		
be used. False celling: Providing and fixing suspended false celling with 600x600 mm size & 12mm thick mineral fiber celling lites of Armstrong dune or approved make. Suspender, frame work from the fiber celling lites of Armstrong dune or approved make. Suspender, frame work got a manufacturer's specifications. The tient to include cost of making necessary cul-outs for lights/air-conditioning grills as per design direction by bank. Rate inclueds removal of existing furniture. Gypsum board false celling: Providing and fixing suspended 12mm thick Gypsum board false celling with Cl framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate inclueds removal of existing furniture. Providing & fixing in place 100 mm. Vortical blinds with scotch guard of approved make, and a cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate includes removal of existing furniture. Providing & fixing in place 100 mm. Vortical blinds with scotch guard of approved make, and a cut on the complete as deceded removal of existing furniture. SQM 40 Supplying, providing and fixing Godrej Cylindrical night latch lock at cash enclosure doors Fix ALLIED CIVIL WORK Brick work in Cement mortar 1.4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. 12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interfore-fixerior plastering in all levels firshed even and smooth including curing complete as directed: 12 incernent mortar 1.4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer of approved brand. Applying & Finishing walls with 2 or m	15	with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamwork with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20	SQM	11		
False celling: Providing and fixing suspended false celling with 600x600 mm size & 12mm thick mineral fiber celling tiles of Amstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lightsiair-conditioning grills as per design direction by bank. Rate includes removal of existing furniture. Sypsum board false celling: Providing and fixing suspended 12mm thick Gypsum board false celling with Gi framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design,pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate included removal of existing furniture. Providing & fixing in place 100 mm. Vertical bilinds with scotch guard of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate. PART: B: ALLIED CIVIL WORK Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. Half brick wall (112 mm). 12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer of substrace. Rate including cost of primer coat. Make: Asian paint, Deutux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pre waste pipe of standard pattern including painting of fittings and brackets, outling and making the walls wherever required. White vircues China wash basin 550 X 4						
Gypsum board false ceiling: Providing and fixing suspended 12mm thick Gypsum board false ceiling with Gl framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with buste paint and making necessary design, pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate includes removal of existing furniture. Providing & fixing in place 100 mm. Vertical blinds with scotch guard of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate. 19 Supplying, providing and fixing Godrej Cylindrical night latch lock at cash enclosure doors Each TOTAL (PART A) PART: B: ALLIED CIVIL WORK Brick work in Cement mortar 1.4 (1 cement : 4 coarse sand) with 1st class bricks including 1 racking out joints and curing complete as directed in all levels. 10 are thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: 10 Incement mortar 1.4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Applying & Finishing walls with 2 or more coats of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with C1 bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6	16	False ceiling: Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank. Rate inclueds removal of existing	SQM	112		
quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate. 19 Supplying, providing and fixing Godrej Cylindrical night latch lock at cash enclosure doors 10 TOTAL (PART A) PART: B: ALLIED CIVIL WORK 11 Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. 10 Half brick wall (112 mm). 11 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: 10 nement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, withing and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass screws and washers complete as now the complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as now the complete with Chromium Plated bras	17	Gypsum board false ceiling: Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design,pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate	SQM	70		
PART: B: ALLIED CIVIL WORK Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. Half brick wall (112 mm). 12 mm thick coment plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Make: Asian paint, Deulux	18	quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment	SQM	40		
PART: B: ALLIED CIVIL WORK Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. 12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer of approved brand. Make: Asian paint, Deulux Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. Withe vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass screws complete as Nos 3	19	Supplying, providing and fixing Godrej Cylindrical night latch lock at cash enclosure doors	Each	4		
Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. Half brick wall (112 mm). 12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Make: Asian paint, Deulux Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as not provided and screws and washers screws, complete as not provided and screws and washers complete.				тс	TAL (PART A)	
1 racking out joints and curing complete as directed in all levels. Half brick wall (112 mm). 12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer of approved brand. Make: Asian paint, Deulux Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as	PART: B:					
interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Make: Asian paint, Deulux Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos	1	racking out joints and curing complete as directed in all levels. Half brick wall (112 mm).	SQM	29		
surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand. Make: Asian paint, Deulux Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos 3	2	interior/exterior plastering in all levels finshed even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand)	SQM	58		
Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos 3	3	surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer ofapproved brand.	SQM	335		
Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos 3	4	Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and	SQM	125		
6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers Nos 3 complete. Supply & Fixing standard sized Chromium Plated brass towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos 3	5	Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense.	Each	3		
7 Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as Nos 3	6	Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers	Nos	3		
	7	Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as	Nos	3		

	Description and finite O.D. have a complex star and the	l N	_	I	1		
9	Providing and fixing C.P. brass angular stop cock. Providing and fixing uplasticised PVC connection pipe with brass unions:	Nos	6 3				
10	Urinal: Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350, including drain pipes, painting of fittings and brackets, cutting and making good the walls and floors etc. wherever required: (make:Cera/Parryware).	Nos Each	1				
11	Water Closet: (European type W.C.) Providing and fixing white vitreous china water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required. W.C. pan with ISI marked white solid plastic seat and lid. (WC make:Cera/Parryware/Hindware).	Each	3				
12	Providing and fixing cp toilet paper holder of approved brand	Nos	3				
13	Providing and fixing 2 in 1 Bib cock of approved quality conforming to IS:8931	Nos	3				
14	Supplying, Fitting & fixing of health faucet of Prayag / Jaguare / or equivalent make with one metre long Tube, Hook & all fixtures.	Nos	3				
15	Providing and fixing UPVC/HPVC pipes complete with fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia/15 mm dia	RM	20				
16	Providing and fixing PVC (6kg) darinage pipes complete with fittings and clamps, bends etc complete as per direction of engineer in charge. 75 mm dia	RM	15				
17	Ceramic glazed wall tiles: Providing and fixing 300 x 300 mm size 8 mm thick Ist quality ceramic glazed wall tiles conforming to IS: 15622 of approved make, in all colours, shades approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) or 5 to 8 mm thick Balendura / Latticrate adhesive as advised and jointing with matching shade cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including dismantling of existing tiles if any Make: Kajaria / Jhonshon/marbito	SQM	45				
18	Non skid Bathroom floor tiles: Providing and laying Ceramic non skid bathroom floor tiles of size 300 x 300 mm 8 mm thick of approved make and shade, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), or 5 to 8 mm thick Balendura / Latticrate adhesive, as advised including pointing the joints with white cement and matching pigments etc. complete including dismantling of existing tiles if any. Make: Kajaria / Jhonshon/Marbito	SQM	15				
19	Providing, fittings and fixing 29 mm thick polymer reinforced moulded PVC door shutter fixed to the chowkhat with necessary hinges. Screw, bolts etc. as specified and directed at all levels, including cost of all necessary fixtures and fittings such as handle, locking arrangment etc. all complete. rate shall inclued provide chowkhat.	Nos	3				
20	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters including Providing and fixing ball bearing for rolling shutters. Rates shall includes applying priming coat.	SQM	10				
	80x0.90 mm M.S. laths with 0.90 mm thick top cover			TAL (DART D)			
	TOTAL (PART B) GRAND TOTAL (PART A + PART B)						
			` `		1		
	NOTE :The estimated cost is exclusive of statutory taxes (GST)on work contract						