

**PRICE BID FOR CIVIL CONSTRUCTION WORK OF DOCUMENT ROOM  
OF RASECC under AO MUZAFFARPUR**

S.NO.	ITEM	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
1	<b>PLASTIC EMULSION PAINT</b>	Providing two or more coats of Plastic emulsion paint, 1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved brand with a water thinnable priming coat with cement primer having VOC content less than 50gm/litre, to give an even shade over newly plaster surface of finished walls & ceilings as per direction of BANK/eic.	200	Sq.m		
2	<b>BRICK SOLING</b>	Brick soling with common burnt clay machine moulded bricks of class designation 12.5 conforming to IS : 2690 (Part I) in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand) (if required). Laying of brick in 5" ht after levelling with mortar/sand to be done. Price is inclusive of all work.	13	CUM		
3	<b>RCC IN FLOOR</b>	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	13	CUM		
4	<b>RCC in WALL</b>	Reinforced cement concrete work in walls (any thickness), including attached plasters (of specifications mentioned in S.No. 5), buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, including cost of centering, shuttering, finishing and reinforcement : 5.2.2 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	27	CUM		
5	<b>CEMENT PLASTER</b>	P/F/F 6-10mm cement plaster of mix (1cement:3fine sand) finished with a floating coat of neat cement and thick coat of lime wash on top of walls when dry for bearing of RCC slabs and beams etc Wall beam/column joints to be finished using chicken mesh.	45	Sq.m		
6	<b>REINFORCEMENT</b>	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1800	KG		
7	<b>DEMOLITION</b>	Demolition work in brick work of 10" thickness.	1	LS		
<b>AMOUNT IN WORDS</b>			<b>TOTAL (in INR)</b>			

**NOTE:-**

- \* PRICE INCLUDES TRANSPORTATION, LIFTING, FIXING CHARGES AND OTHER TAXES AS PER GOVERNMENT RULES
- \* ALL OTHER TERMS AND CONDITIONS AS PER INDIAN STANDARDS/SPECIFICATIONS
- \* ABOVE PRICE IS EXCLUDING GST & GST WILL BE PAID EXTRA BY THE BANK AS PER RULE.
- \* 3&4 DOESNOT INCLUDE REINFORCEMENT MENTIONED IN S.N. 5

(SIGNATURE)  
**AUTHORIZED SIGNATORY**