



STATE BANK OF INDIA
LOCAL HEAD OFFICE PATNA

ADMINISTRATIVE OFFICE MUZAFFARPUR

Name of the work:- INTERIOR DECORATION & FURNISHING WORK OF SME BETTIAH BRANCH AT ITS NEW PREMISE UNDER RBO BETTIAH.

PRICEBID

Sl.No.	Description	Unit	QTY	Rate (RS)	Amount
1	COUNTER FOR CASHIERS (length UPTO 7'0" wide x7'6"depth as per site design)	Nos	1		
	Providing and fixing low height Single Window counters / Case Manager's table with a maximum width of 900 mm in required shape as per typical design. The main structure of the counter is to be made of 19mm thick BWP Phenol Formaldehyde block board (of approved or equivalent make). The width of the counter should have 1500mm (with disc credenza / cabinet of 400mm wide and maximum 1050mm length / depth (including width of counter). The vertical supporting members of counter are to be made of 19 mm thick BWP Phenol Formaldehyde block board (of approved or equivalent make). D-Tel box shall be fitted properly in right hand side. The key board pullout tray to be provided in addition to drawer with lock and key make arrangement of standard make. The left hand side should have cabinet made of 19 mm thick BWP, PF plywood and cavity keeping CPU as per design / drawing. The counter top have a neat hole to be made in the table for connecting the wires which is to be covered with a white colored PVC insert (wire manager) with moveable parts to put the wires and sockets to cover the hole neatly. The exposed block – board/ plywood to be covered with 0.8 mm thick blue / white high gloss/matt finish laminate of approved or equivalent make of approved shade and colour. Exposed portions to be also covered with 0.8 mm thick blue/white high gloss/matt finish laminate of approved shade and colour. The internal and non-visible side of all drawers, cabinets and counter table shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. Providing and fixing 12 mm thick toughen glass of approved make as per design and specification securely fixed in toughen section as per design and details and all necessary standard quality of fittings, hard wares, locks (make or equivalent). Door shutter of 19 mm BWP board to be fixed at the rear side of counter with automatic locking system from Godrej or equivalent (Door shutter lock to be paid separately). All work to be completed as per approved materials Colour & Laminate etc and specification and direction of Engineer-in-charge.				
2	Wooden stud partition near reception/Lounge	Sqm	6.51		
	Providing and fixing wooden partition up to 900 made by G.I frame section fixed 6mm MR ply finished with both sides and top 0.8mm thick high pressured laminates of approved make & shade etc.and 50x50 mm 9mm ply boxes as per design finished wooden texture laminate and				
	Providing and fixing panelling on wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 25 mm @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 6mm thk. MR Ply finished in approved 0.8 mm. Thk. Laminate high pressure laminate / Veneer finished in melamine polish. Wooden moulding, lipping etc. as directed by Bank / architect shall be provided wherever required.				

	All electrical wires, accessories, telephone wires, etc, shall be run in the panelling as per Electrical Drawings and designs. Nothing extra shall be paid for the co-ordination of the same.				
	All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings.				
	All complete as per drawings, designs, specifications and directions of Engineer-in-Charge.				
3	Column / Wall Panelling (upto false ceiling ht)				
	Providing and fixing in position panelling made out of GI /BWP PLY frame with intermediate spacing of 600mm c/c horizontally as well as vertically. Frame to be covered with 8mm thick BWP Grade ply/ 12mm thick MR GRADE MDF board (of approved/equivalent make). The surface so prepared shall be pasted with 0.8 mm thick blue / white high glosive/matt finish laminate (of approved or equivalent make). Measurement will be done upto false ceiling only. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank.				
3.1	Wall panelling	Sq.M.	130.00		
3.2	Column panelling	Sq.M.	4.00		
	DOOR				
4	FRAMELESS GLASS DOOR WITH PATCH FITTING MAIN ENTRY/CM CABIN				
4.1	Providing and fixing frameless fully glazed 12mm thk toughened glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	Sq.M.	5.90		
4.2	FIXED GLASS ABOVE OPENING DOOR AND AREA ADJACENT TO DOOR	Sq.M.	26.50		
5	DOOR				
	Providing and fixing solid/SEMI GLAZED doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 50MMx100MM WPC frame section shall be provided finished in 0.8MM high pressure laminate as per approved make and shade . Rate shall include approved make (Godrej Eppco) NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 250mm SS Brushed finished, 150mm hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.	Sq.M.	4.50		
6	FROSTING FILM on clear glass	Sq.M.	12.00		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyester film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.) 3M - CRYSTAL GLASS FINISHES 7725 SE325				

7	CABINET BELOW GRANITE COUNTERS IN PANTRY AREA 750MM HT	Sq.M.	2.00		
	Providing and fixing 19mm thk. MR ply shutters with GI /ply frame 50x25mm , all side with double 19mm ply for support and 19mm on the top for granite ,skirting gap as shown in the drawing shall be maintained. Division of shutters shall be made equally according to the length of the counter.				
	Shutters shall be hinged to the framework and finished with 1.0mm thk. PVC Laminate of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
8	GYPSUM FALSE CEILING				
	Providing and fixing false ceiling at all height including providing andfixing of frame work made of special sections, power pressed fromM.S. sheets and galvanized with zinc coating of 120 gms/sqm (bothside inclusive) as per IS : 277 and consisting of angle cleats of size25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at1200 mm centre to centre, one flange fixed to the ceiling with dashfastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flangeof cleat fixed to the angle hangers of 25x10x0.50 mm of requiredlength with nuts & bolts of required size and other end of anglehanger fixed with intermediate G.I. channels 45x15x0.9 mm runningat the spacing of 1200 mm centre to centre, to which the ceilingsection 0.5 mm thick bottom wedge of 80 mm with tapered flangesof 26 mm each having lips of 10.5 mm, at 450 mm centre to centre,shall be fixed in a direction perpendicular to G.I. intermediate channelwith connecting clips made out of 2.64 mm dia x 230 mm long G.I.wire at every junction, including fixing perimeter channels 0.5 mmthick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with				
	wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be be fixed in a direction perpendicular to G. I. channel with connecting clips made out of 2.64 mm dia x 230 mm long G. I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long .				
	including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finishof tapered and square edges of the board with recommended jointingcompound , jointing tapes , finishing with jointing compound in 3layers covering upto 150 mm on both sides of joint and two coats ofprimer suitable for board, all as per manufacturer's specification andalso including the cost of making openings for light fittings, grills,diffusers, cutouts made with frame of perimeter channels suitablyfixed, all complete as per drawings, specification and direction ofthe Engineer in Charge including the cost of putty and painting with specification as below :				
	Plastic Emulsion paint on gypboard false ceiling: Wall/ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade in Two or more coats on new work. White cement based putty on false ceiling: Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				

A	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) For the area where vertical design etc to be done measurement shall be made in running metre for the verticals and shall be payable additional to plan area.	Sq.M	95.35		
9	Wooden false ceiling				
	Suspended wooden false ceiling in Conference room and CM Cabin, lounge and Reception area or as per design				
	providing and fixing 12mm MR ply finished by laminate/charcoal plank as per design or selection by Bank Engineers/ architect hanging false ceiling chanel as per gypsum board same as above item				
A	High glossy laminate in pattern in CM CABIN	Sq.M	13.00		
C	Charcoal plank /louvers Make - Europrateek RECEPTION AREA	Sq.M	4.00		
10	GRID Sierra OP Ceiling With WITH SILHOUETTE 38 IN SME HALL	Sq.M.	103.00		
	Providing and Fixing Providing & Fixing of Knauf Ceiling solution Mineral Fibre Acoustical Suspended Ceiling System with 15mm thick Sierra OP Tegular 15/90 Edge Tiles with Knauf Ceiling solution Silhouette 15mm face exposed grid.The tiles shall have smooth laminated visual with Humidity Resistance (RH) of 95%, NRC 0.90 (Average value of Absorption Co-efficient readings taken at 250 Hz, 500 Hz, 1000 Hz and 2000 Hz) as per ASTM C423 standard, CAC of 25db as per ASTM E1414, Light Reflectance $\geq 86\%$ as per ASTM E-1477, Thermal Conductivity $\lambda = 0.040$ W/mK, Colour Global White, Fire Performance of class A2-s1, d0 according to EN 13501-1 with 15mm Tegular 15/90° edge and 8mm drop in module size of 600 x 600mm. The scrim on the face of the tile shall be cleanable and classified as ISO 14644-1 cleanroom class 5. It shall be suitable for Green Building application, with Recycled content of 43% and VOC Emissions (French) class of A+. The tile shall have Environmental Product Declaration as per ISO 14025 and EN 15804+A2. The tile shall have certifications from GRIHA and GreenPro thereby confirming that it is an environment friendly product.				
	The tile shall be laid on Knauf Ceiling solution Silhouette 38 with 15 mm wide T - section flanges colour global white (matching to tile color) having roll formed double stroke rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32mm (all sections). Manufacturers Test Certificate mentioning site address duly signed Manufacturer to ensure specification of tiles is required.				
	omprise main runner spaced at 1200mm securely fixed to the structural soffit using Knauf Ceiling solution suspension system (specifications above) at 1200mm maximum. The First/Last suspension system at the end of each main runner shall not be greater than 450mm from the adjacent wall along with the first and the last main beam shall be at less than 600mm from the wall.Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees.				
	Accessories supplied consisting of M6 Anchor Fasteners with hanger hole, pre-straightened hanger wire of dia – 2.5 mm of 1.80 m to 4 Mtr length (Optionally, adjustable hook clips made of 0.7mm thick Grade 1 C55 galvanized spring steel of dimension 100 x 20mm and 4 mm aquiline wire to be used for level adjustment during installation purpose in main runners).				
	Approved Make: Armstrong, Knauf Ceiling Solutions, Saint Gobain, Nittobo. Deduction for use of old 2x2 tile shall be made @80% from the plan area.				

11	OFFICER'S TABLE				
	Providing and fixing the Officer's table made out 19mm BWP ply board with 0.8mm laminate as per drawing detail enclosed ,storage unit with 3 drawer, and keyboard and pencil drawer on channels, cable manager , and laminated apron to match decor. Drawer unit and verticals made out of 19mm BWP ply board with keyboard drawers ,PC stands for PC below worktop and 12mm ply board for footrest . All Drawers to be provided with Godrej lock & SS handle of approved make . The exposed side of front facade ,drawer front shall be finished with 0.8mm laminate as per drawing . the inside surface also finished with white/blue colour paint as per approved A/E/I/Bank				
	a CM TABLE	Nos	1		
	(6'6"X3'6"X2'6") LXWXH WITH 3'6"x1'6"x2'6"CREDENZA				
12	CORIAN WORK (TABLE TOP)	Sq.M.	5		
	Providing and fixing 12mm corian sheet on the top of CM table with credenza and top of back low ht cabinete with all polishing work including 50 mm front facia , colour shade as per selection of Bank and Architect.Make marino				
13	STEEL T/U BEAT (Reception table & wall panelling as per design requirement)				
	Providing & Fixing SS Finished Aliminium strip in partitions / panelling, made of HETTICH / Enox E approved equivalent profile, elevation width of min 20mm or more, finish SS, all complete, with neat installation in perfect line & level, cutting, insertion, making good, matching, etc., in panelling / partition / etc. as required.	Rmt	20.00		
14	ROLLER BLINDS /ZEBRA BLINDS				
	a Supply and installation of dual layer zebra roller shades light filtering Share Dimout blinds (Zebra Blinds)for window of polyester based fabric of Vista make all complete and inclusive the all taxes as per the direction of Architect/E/I/Bank	Sq.M.	16.50		
15	DISMANTLING, TRANSPORTATION AND REFIXING OF WOODEN AND GLASS ITEMS				
	Dismantling of existing fully glazed/panelled/semiglazed partition, cabinet, glass door, tables etc from old premise and shifting it to new premise and fixing as per requirement and direction of EIC.	Nos	1.00		
16	REPAIR WORK ON OLD CABINET, TABLE, PARTITIONS				
	Repair work on old low storage cabinets, partitions, tables , doors etc as per requirement etc. Payment shall be made for repaired area as per actual. (mica pasting and other minor epair work including suply of 0.8mm mica, 6or 3mm ply/mdf as per requirement. Rate is inclusive of cutting and finishing.	Sq.M.	15.00		
17	ACP PANELLING/ROLLING SHUTTER BOX				
	Providing and fixing ACP for panelling and rolling shutter cover: Providing and fixing of ACP cover for rolling shutterset within inner Al box section cover frame work and covered with wooden placed at suitable spacinfng not exceeding 600mmc/c. The framework shall be covered with 12mm thick BWR Plywood. The work is to be finished with 3mm thick exterior grade Aluminium Composite Panel (ACP) cladding of approved make and shade with grooves duly treated with silicon sealant. The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for fin-ished work.	Sq.M.	10.00		
TOTAL INTERIOR & FURNISHING WORK				INR	
Amount in word: Rs.					

	Note:-	
1)	Extra members, wherever required for stability / otherwise, to be provided with the required finish without any extra charges.	ALL PLY/MDF MAKE -Green ply /Century/Austin/ACTION TESA/Green panel/as per technical specs
2)	Any damages caused to the walls, ceilings, floors, etc. shall be made good by the Contractor by refinishing the same in exactly the same manner, so as to leave the surfaces in a good-as-new condition. A final coat of paint on all painted surfaces shall be deemed to be included in the occupation, so as to leave the premises in a suitable condition for occupancy.	Laminate/Mica - Greenlam/Marino/Century/Europrateck/as per technical specs Hard ware and fitting as mentioned in specification refer technical specs/item description
3)	Contractor shall made and get approved shop drawings of all items prior to fabrication / manufacturing of the same.	
4)	In case of partitions / panelling / etc., if any corbellings, cornices, etc. are called for, these shall be done as shown in the drawings, designs, etc., or as per the requirement of the Employer / Architect, and these shall be paid for at the square foot rate quoted by the contractor. Nothing extra over and above the square foot rate shall be payable to the contractor	
5)	The contractor shall extend full co-operation to the other contractors viz. Electrical, Airconditioning, and any others who may be working in the said premises.	

(Signature)
AUTHORIZED SIGNATORY