

**Price Bid of Interior works for SBI Proposed RACC Branch at Uttarkashi**

S.NO	Description	Unit	Qty.	Rate	Amount
<b>A</b>	<b>False ceiling works</b>				
<b>1</b>	<b>Gypsum False ceiling works</b>	<b>Sqm</b>	80.00		Rs. 0.00
	<p>Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts &amp; bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm (Gyproc make) running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I.wire at every junction,</p>				

	including fixing of 12.5mm thick gypsum board (Gyproc make) to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes and finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint , all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, fire and other services etc complete ,cutouts made with frame of perimeter channels suitably fixed, including trap door with 19 mm thick MR grade plywood with moulding in edges including primer and plastic emulsion paint all complete as per specification and combined services drawings direction of the Engineer in Charge . No extra will be paid for light cuttings etc. No extra channel will be paid if its is required for additional support etc.				
<b>Note</b>	Item includes cove in false ceiling as per drawings & instructions & finishing smooth with three coats of plastic emulsion paint of approved quality.For light fittings and cut outs etc. have to be made with the frame of perimeter channels of size Lay on cross tee twist and rotation for greater stability 20 x 27x30 x 0.55 mm thick, supported suitable. Angle beads edge beads control joints as required to be provided. The quoted rate to be include all the above items. Ceiling to be painted with minimum three coats of plastic emulsion paints over POP punning, base preparation etc. work to be complete as per drawing and direction of Bank/Architect. (Only flat surface shall be measured and paid)				
<b>2</b>	<b>Armstrong tile ceiling</b>	<b>Sqm</b>	76.00		Rs. 0.00

	Supply and installation of (Micro Perforated) Acoustical Mineral Fiber Ceiling Panels Optra RH 95 NRC 0.90 of size 600 X 600 X 15 mm, Sillhouette steel angle grid system of armstrong, main tee are dould web design roll formed from hot dipped galvanized steel with prepainted steel capping, Main Tees are 3600 X 38 mm long with Base Metal thickness of 0.38 mm, has cross Tee slots at 100 mm centres and suspension holes in the bulb conveniently located at every 52mm, suspended with CL 315 Clip with heavy duty plugs to be suspended with the ceiling. Cross Tee are 1200 X 28mm and 600 X 28 mm and 600 X 28 mm long. Lay visual appeal. Perimetre wall angle is 3000 X 24 X 24 mm with Base metal thickness of 0.45mm. <b>Armstrong tile ceiling in the gird including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.</b>				
<b>B</b>	<b>Partition works</b>				
<b>1</b>	<b>Full Height Laminate partition</b>	<b>Sqm</b>	59.00		Rs. 0.00
	Providing and fixing 75mm thick partition which includes 8mm BWP Ply both side screw fixed with Frame work to be 50X50X1.60mm thick aluminum tube weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed. Floor or slab with 65 to 75 mm long screw. The vertical GI member shall be placed at 450 to 500 mm center to center and horizontal members to be placed at 600 mm c/c or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc.Finally partition is finished with both side 1mm thick matt finished laminates .All exposed wooden members to be finished in PU ACRYLIC gloss polish, SIRCA or equivalent, in approved shade or as as per instruction				
	<b>Note : a.All frame works to be fixed upto RCC slab/Beam bottoms. b.Ply/Boards shall be fixed upto RCC slab/Beam bottoms. c. Finishings shall be done upto False ceiling level, and measurements for payments shall be done for finished levels.</b>				
<b>2</b>	<b>12 mm thick toughened glass fixed Partition</b>	<b>Sqm</b>	32.00		Rs. 0.00

	Providing & fixing of Fixed glass partition with 12mm thick toughened using PT standard fittings like PT90/PT92 of Dorma make at the top and grouting at the bottom with U- shaped Aluminium rail and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top PT standard fittings to be fitted to the wooden section fixed above the Gypsum board in the level of GI channels of False ceiling complete to the satisfaction of Architect/ Bank's Engineer.				
<b>3</b>	<b>12 mm thick toughened glass Frameless door</b>	<b>Sqm</b>	9.50		Rs. 0.00
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with Dorma make patch fittings including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film of approved design and pattern. 1 pair of 1000mm long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items. Dorma Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Centre Lock US-20, Handle - TG DIH600 - 38mm dia X 600mm length				
<b>4</b>	<b>Low Height partition</b>	<b>Sqm</b>	30.00		Rs. 0.00
(i)	Providing & fixing <b>Low Height Partition</b> consisting of:				

(ii)	<p>Providing and fixing in position 1250/1200 mm height double skin wooden partition made out of Frame work to be 50X50X1.60mm thick aluminum tube weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed. The spacing of the members may vary either side depending upon the site conditions as per approval of Bank Engineer. The partition shall be provided <b>8mm thick BWP Ply</b> to be fixed over the frame work on both side.approved make on both sides finished with 1.0mm thick matt finished laminates of approved makes in combination and shade up to about 750mm height. The remaining upper portions of the partitions shall have 12 mm thick toughened glass with etching and polished edges of SAINTGOBIN/MODI/TRIVENI. Rate inclusive of beadings etc. complete in all respects.</p>				
(iii)	<p>Providing &amp; fixing 80 x 25 teak wood profile over top of partition &amp; side</p>				
5	<b>Fire Rated Door (3'-6"x 7'-0")</b>	<b>Nos</b>	1.00		Rs. 0.00

	<p>Providing and Fixing IS approved 2 Hour Fire Resistant Door with undernoted specifications</p> <p><b>DOOR SHUTTER</b></p> <p>50 mm thick fire resistant door shutters of 120 minutes fire rating conforming to IS:3614 (Part-II), tested and certified as per laboratory approved by Engineer-in-charge, with suitable mounting on door frame, consisting of vertical styles, lock rail, top rail 100 mm wide, bottom rail 200 mm wide, made out of 16 SWG G.I.sheet (zinc coating not less than 120 gm/m<sup>2</sup>) duly filled FR insulation material and fixing with necessary stainless steel ball bearing hinges of approved make, including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer-in-charge <b>(All including hardware &amp; Fitting)</b></p> <p><b>(DOOR FRAME)</b></p> <p>Fire resistant door frame of section 50 x 60 mm on horizontal side &amp; 35 x 60 mm on vertical sides having built in rebate made out of 1.6 mm thick GI sheet ( Zinc coating not less than 120gm/ m<sup>2</sup>) suitable for mounting 120 min Fire Rated Glazed Door Shutters. The frame shall be filled with Mineral wool Insulation having density min 96Kg/m<sup>3</sup> . The frame will have a provision of G.I. Anchor fastners 14 nos ( 5 each on vertical style &amp; 4 on horizontal style of size M10 x 80 ) suitable for</p>				
<b>6</b>	<b>Laminate wooden door with 5mm thick view pane glass</b>				
	<p>Providing &amp; fixing Deodar wood frame of size 50x75mm including making rebate for shutters,with 38 mm thick flush door including finishing with 1 mm laminate both sides, including HAFFLE, HETTICH hardware cylindrical knob and handle lock and, stopper , tower bolt, door closures etc. complete of SS approved quality . All exposed wooden members to be finished in PU polish, in approved shade and pattern to match with partition or as as per instruction.</p>				
<b>i</b>	<b>Record door &amp; Pantry 3'-0" x 7'-0"</b>	<b>Nos</b>	2.00		Rs. 0.00
<b>C</b>	<b>Paneling works</b>				
<b>1</b>	<b>Laminate Paneling</b>	<b>Sqm</b>	102.00		Rs. 0.00
<b>i</b>	Providing & fixing <b>Panelling</b> consisting of:				

ii	Providing & fixing Panelling consisting of: Frame work to be 50X50X1.60mm thick aluminum tube weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed				
iii	Facing with <b>8 mm thick BWP Ply</b> well secured to frame work by means of screws and nails.				
iv	Finishing with 1.0 mm thick Matt finish Laminates with grooves as per drawing and design.				
v	Fixing 100mm high skirting of 1mm thickness Matt finish Laminates as per approved sample on exposed partition				
<b>2</b>	<b>Lacqured glass panelling</b>	<b>Sqm</b>	23.00		Rs. 0.00
i	Providing & fixing Panelling consisting of: Frame work to be 50X50X1.60mm thick aluminum tube weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed				
ii	Facing with <b>8 mm thick BWP Ply</b> well secured to frame work by means of screws and nails.				
iii	Finishing with 4mm thick lacqured glass with adhesive etc. as per design and complete to the satisfaction of Architect / Bank's Engineer.				
<b>3</b>	<b>Extra for panelling with level difference form basic finish level upto 150mm</b>	<b>Sqm</b>	12.00		Rs. 0.00
<b>4</b>	<b>ACP cladding works</b>	<b>Sqm</b>	24.00		Rs. 0.00
	<b>Aluminum Composite Panel:-</b> Providing & Fixing of 4mm thick PVDF coated Exterior Grade Aluminum Composite Panel sheet <b>make Alucobond/Alstrong/Reynobond</b> Cladding consist of LDPE core laminated between two sheets of aluminum coils (0.50mm+3mm+.50mm=4mm) thickness of a same grade on both sides as per ASTM standard ensuring no Air Entrapment between PE core and Aluminum Coil in desired color as may be approved by the Architects as per Elevation Drawings and Plan Drawings. The basic frame work shall be created by 38mm x 38mmx16 gauge thick. Make Jindal/ Hindalco Extruded Aluminum Rectangular Tube in the vertical and horizontal distance 750mm c/c plane of the cladding.				

	The Extruded Aluminum Rectangular Tube shall be provided with 50mm long Aluminum Extruded Angle (Brackets) of 25x25x3 mm thick (Or 38x25x4 mm thick-50x25x3 mm thick or as may be required at site at respective locations) at every 900mm internal on both sides of the Tube, fixed with 3 Nos. of Aluminum Rivets for each angle. Fixing of the basic framework shall be done by drilling holes by an Electric Drill in the Masonry/Reinforced Cement Concrete, inserting 50mm long Nylon Sleeves of Fischer make and 10x25 or 50 or 75mm long stainless Steel CSK Wooden Screw (2 Nos. per Bracket). Wherever the basic frame work is required to be fixed on to Metal Structural Framework, the same shall be done by drilling holes and fixed with Stainless Steel self tapping screws. ACP shall be sealed with "Non-Staining" Silicon Weather				
<b>5</b>	<b>Soft board</b>	<b>Sqm</b>	10.00		Rs. 0.00
	Softboards -Providing and fixing pin up boards with 12mm thick soft board panels with 6mm thk. BWP Ply backing and covered with approved fabric (cost not more than Rs 150/=per mt). A 6mm thick melamine polished TW lipping to be fixed around the corners. The pinup board need to be fixed either on the wall or over the partition.				
<b>D</b>	<b>Miscellaneous works</b>				
<b>1</b>	<b>ROLLER BLINDS</b>	<b>Sqm</b>	5.00		Rs. 0.00
	Supplying fitting and fixing Roller Blind with 100% Polyester fabric (plain/ ribbed fabric of approved colour and shade). Nominal thickness of fabric shall be 0.60-0.80 mm and nominal weight 255 - 450 grams per square metre, hanging excellent hanging properties and very high tearing strength, Coating of the fabric shall be of Acrylic, which shall be resistant to cracking and fraying. The fabric shall be suspended from the top channel made of extruded anodised alloy of 1.25-2.00 mm nominal thickness and 38 mm nominal diameter. The top channel shall be fixed with powder coated				
	The operating mechanism fixed to the top channel shall be made of high strength ABS plastic having ultra-smooth gear with spring booster of high carbon steel. The mechanism shall be operated with tilt chain having 4.50 mm balls made of ABS plastic linked with 1.50 -2.00 mm polyester chord. The mechanism shall allow the blind to stop in desired position with the help of stop lock. The bottom channels shall be of aluminium tube of 21 mm nominal diameter and 1.50-2.00 mm nominal thickness. The fabric shall be enclosed in suitably created pocket along the tubes, which shall be closed				



	<b>Make : Aerolux, Vista levelor, Mac, Dack</b>				
<b>2</b>	<b>Etching film</b>	<b>Sqm</b>	24.00		Rs. 0.00
	Providing & fixing in Printed or as per design & drawing Etching frosted glass film in stardust range fixed to glass as per pattern. Area of application to be measured as maximum length x maximum height of				
<b>3</b>	<b>Cleaning all old window, doors glass panes</b>	<b>Sqm</b>	5.00		Rs. 0.00
<b>4</b>	<b>Louver Shutter for electrical panel</b>	<b>Sqm</b>	4.00		Rs. 0.00
	Providing & fixing Shutter Boxing for electrical panel shutter made 19mm thick BWP Board finished with 1.0mm thick Matt Finish laminate including hinged cover & SS vent to be provided as per approval of Architect / Bank's Engineer.				
<b>5</b>	Providing & applying the walls, ceiling and elsewhere with <b>Plastic Emulsion Paint (roller finish)</b> after preparing the base by New Surface/ finish and applying 2-3 coats of birla white putty for making the surface plane & smooth and than applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.ft	70.00		Rs. 0.00
<b>E</b>	<b>Storages works</b>				
<b>1</b>	<b>Low/ Full Height Storages</b>	<b>Sqm</b>	18.50		Rs. 0.00
	Providing and fixing in position Low/ Full Height Storage 450mm deep (overall) with shutters made of 19 mm thick. BWP block board & shelves made of 19mm BWP block board, back side of the storage to be made of 8mm thick BWP block board. The storage interior & exterior shall be finished with 1mm thk high gloss laminate as per specifications with brass oxidised hinges, tower bolts, ballcatches lock, handle (4" SS handle) etc. complete in all respects as per drawing & instructions of Architect / Bank's Engineer. All exposed wood work / ply wood to be PU matt polished				

<b>2</b>	<b>Below the Counter : 600mm deep Storage. (In Pantry)</b>	Sqm	2.00		Rs. 0.00
	Providing and fixing in position Below counter Storage 600mm deep with shutters made of 19 mm thick. BWP block board & shelves out of 19mm BWP block board. The storage interior & exterior shall be finished with 1mm thk high gloss laminate as per specifications with brass oxidised hinges, tower bolts, ballcatches lock, handle (4" SS handle) etc. complete in all respects as per drawing & instructions of Architect / Bank's Engineer. All exposed wood work / board wood to be PU matt polished				
<b>3</b>	<b>Over Head Storages above the Counter : 450mm deep Storage. (In Pantry)</b>	Sqm	2.00		Rs. 0.00
	Providing and fixing in position Below counter Storage 600mm deep with shutters made of 19 mm thick. BWP block board & shelves out of 19mm BWP block board. The storage interior & exterior shall be finished with 1mm thkhigh gloss laminate as per specifications with brass oxidised hinges, tower bolts, ballcatches lock, handle (4" SS handle) etc. complete in all respects as per drawing & instructions of Architect / Bank's Engineer. All exposed wood work / board wood to be PU matt polished				
<b>F</b>	<b>Furniture works</b>				

1	<p>Providing and placing Table as per drawing made of 19mm thick BWP block board. Table top to be of 25mm thick BWP block board finished with 1mm thick high gloss laminate on top with side table &amp; back storage unit. Table to be provided with storage cabinet with drawers made of 12mm thick BWP block board front side and back faces &amp; drawer, bottom with 12mm thick BWP block board. The table to be provided platform type of foot rest of size 450mm x 600mm. including Cable manager, locks, handles, telescopic slides for drawers, computer key board tray (hettich) with retractable mouse pad, mobile CPU trolley (ebco), etc. all complete to be satisfaction of Architect / Bank's Engineer. All interior &amp; exterior to be finished with 1mm thk high gloss laminate (Century/Green ply/ Archid ply). All exposed wood work / ply wood to be PU matt polish as per specification to approved colour. Table finishes as per drawing. On customer side fascia of as per drawing.</p>				
	<b>Laminate make: Century/ Green/ Archid</b>				
i	CM RACC Table -: 1500 x 750 x 750, Side Table: 1000 x 450 x 750, Back storage: 3530 x 450 x 750	Nos	1.00		Rs. 0.00
ii	CM RBO Table -: 1500 x 750 x 750, Side Table: 1000 x 450 x 750, Back storage: 1800 x 450 x 750	Nos	1.00		Rs. 0.00

2	<p>Providing and placing Table as per drawing made of 19mm thick BWP block board. Table top to be of 25mm thick BWP block board finished with 1mm thick high gloss laminate on top with side table unit. Table to be provided with storage cabinet with drawers made of 12mm thick BWP block board front side and back faces &amp; drawer, bottom with 12mm thick BWP block board. The table to be provided platform type of foot rest of size 450mm x 600mm. including Cable manager, locks, handles, telescopic slides for drawers, computer key board tray (hettich) with retractable mouse pad, mobile CPU trolley (ebco),etc. all complete to be satisfaction of Architect / Bank's Engineer. All interior &amp; exterior to be finished with 1mm thk high gloss laminate (Century/Green ply/ Archid ply). All exposed wood work / ply wood to be PU matt polish as per specification to approved colour. Table finishes as per drawing. On customer side fascia of as per drawing.</p>				
i	<p>Manager Sanction/ Maintenance/ Auditor/ Processing Officer's Table -: 1500 x750x 750, Side Table:900 x 450 x750,</p>	Nos	6.00		Rs. 0.00
3	Workstation				

	Providing and placing Table as per drawing made of 19mm thick BWP block board. Table top to be of 25mm thick BWP block board finished with 1mm high gloss laminate on top with side table. Table to be provided with storage cabinet with drawers made of 12mm thick BWP block board front side and back faces & drawer, bottom with 12mm thick BWP block board. The table to be provided platform for CPU trolley including Cable manager, locks, handles, telescopic slides for drawers, computer key board tray (hettich) with retractable mouse pad, mobile CPU trolley (ebco), etc. all complete to be satisfaction of Architect / Bank's Engineer. All interior & exterior to be finished with 1mm thk high gloss laminate. All exposed wood work / ply wood to be PU matt polish as per specification to approved colour. Table finishes as per drawing. Hardware to be SS of HETTICH, HAFFLE make. Laminate Basic Rate - 520/sqm+GST				
i	L - Shape workstation 1500 x 450 x 750, 1175 x 450 x 750	NOS	5		Rs. 0.00
6	<b>10mm thick Toughened glass on Table tops</b>	Sqm	18.00		Rs. 0.00
	Providing and fixing 10mm thick glass on table top size 1350 to 1800mm including with edge polishing and making holes for cable manager				
	<b>Total Amount of Interior works</b>				<b>Rs. 0.00</b>

GST Extra as applicable