S.No.	Description of Item	Unit	Qty	Rate	Amount
	Interior Works :				
	Mode of Measurements : Area of exposed and finished surfaces				
	will be measured.				
	False Ceilings :				
1	Gypsum Board False Ceiling :				
	Providing, making and fixing Gypsum Board False Ceiling :- 12.5 mm thick G.I. Perimeter Channels of size 0.55mm thick. G.I. intermediate	Sqm	115		
	channels of size 45mm from the soffit at 900mm centres with ceiling				
	angle of width 25mm X 10mm X 0.55mm thick intermediate channel at				
	450-600 mm c/c Two coats of primer + two or more coats of plastic				
	emulsion paint Note -Including all fittings,material, labour,cut outs				
	required for light fixtures, Speakers, screws and joint paper/fibre tape				
	etc. complete.				
2	Cove in ceiling :				
	Same as above but providing, making and fixing Gypsum cove (inside	Rmt	150		
	height 150 - 200 mm and border 75 mm) to hide strip/cove light in				
	ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				
3	Mineral Fibre Grid Tile Ceiling :				
0	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all	Sam	160		
	heights & in spirit level, Acoustical Ceiling System @ Office areas with	94			
	Armstrong, Gyproc or equivalent make mineral fibre acoustical				
	suspended ceiling system as per Manufacturer's specification with pin-				
	hole tiles, tegular edge with 24 mm exposed grid. The tiles should have				
	Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system				
	Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as				
	per manufacturer's specifications. The grid should be laid on				
	Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid				
	systems with 24 mm wide T-section flanges color white, the tile will be				
	laid on frame work made of Armstrong Prelude 32 with 24 mm wide T				
	- section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm				
	Cross Tees with a web height of 32 mm and 27mm ,25 mm				
	respectively. The cost shall include all fittings and materials complete				
	including proper installation and provisioning etc. The work is to be				
	completed as per manufacturer's specification .				
	Partitions :				
	Rate to be included of all kinds of planes/levels, profiles and cut outs,				
	etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported				
	with metallic section etc. suitably fixed all complete as per drawing				
	and direction. ii) The contractor must co-ordinate with electrical & AC				
	Works for cabling, AC pipe works, etc.				
4	Full Height Partly Glazed/ Solid Wooden Partitions with Door				
	Providing and fixing full height partly wooden, partly glazed/ Solid	Sqm	60		
	partitions- specifications (Measurement shall be taken up to finished				
	partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm				
	thick 450/600 mm c/c both ways 8 mm thk. MR plywood Termite &				
	Borer proof from both the sides 1.0mm thick approved shades of				
	laminate 5 mm thick float glass (for Partly Glazed Partitions) Eitching				
	as per approved design. The door shall be flush door of approx. 32-38				
	mm thickness, both sides 1 mm thk laminate as per design. Cost shall				
	be inclusive of beadings, all accessories like SS hinges, medium				
	quality mortise handles/locks, baby latches, stopper, etc. Fittings shall be in SS finish as per approval. The cost shall also include providing				
	and applying paint/polish on all surfaces including 6 mm lippings et				
	Note -Including all fittings,material, screw, labour etc. Complete.				

S.No.	Description of Item	Unit	Qty	Rate	Amount
5	Low Height partitions With / Without Glass :				
	Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. MR plywood Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Eitching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision for items like softboards, white boards,etc. as & where required.	Sqm	42		
6	Full Height Cement Board Double Skin Partition :with door				
	Providing and Fixing full height cement board double skin partition made out of 65X65X3 mm thick aliuminium section and 10 mm thick cement board of Bison or equivalent make. Alum. section to be fixed at maximum 600 mm centre to centre for verticle members and at 0', 900 mm, 2100 mm and ceiling levels for horizontal member fixed with wooden screws, Painting will be paid seperately.	Sqm	18		
7	Panelling Works (Walls , Columns, etc):				
	Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc.				
8	Wall/Column Panelling				
	Providing, making and fixing single skin paneling (Using 8 mm thick MR plywood), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of $0.10 - 0.45$ mt. ht., as required, made out of $50 \times 25 \times 1.0$ mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade ( in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as directed.	Sqm	118		
9	Cabinet for Electric Panel :				
9	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).	Sqm	3		
10	Main Door – Toughned Glass				
-	Providing, making and fixing Thoughend Glass Door:- 12mm thk single/double shutter toughened glass doors, <b>Including Floor</b> <b>springs</b> make Hardwvn/ozone/Dorma or equivalent set, Upper patch, lower patch, lock key plate, provision of locking system, etc. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of appoved make Including Etching pattern, Note- Including, labour, transport, material, delivered and placed in position at site of work.	Sqm	7		

S.No.	Description of Item	Unit	Qty	Rate	Amount
11	Toughened Glass Fixed Glazing				
	Providing, making and fixing Toughened Glass :- a. 12mm thick toughened clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc.,		8		
12	Aluminium Frame Glass Door for UPS / Server Room :				
12	Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size $100 \times 50 \times 2.0$ mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement ,with SS handles, all necessary fittings, all labour, materials, etc complete. (to be fixed in sever & UPS room)		2		
	Furnishing Works :				
	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. On the left side platform at bottom for CPU.The bottom compartment made up of 18mm thick. MR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished. One M S powder coated keyboard tray with mouse tray as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.				
	Tables :-				
	Providing and supplying table detailed below : 118 mm thick MR Plywood 2 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved made 3 TW half round beading of sect 20 x 12 mm duly polished 4 Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5Drawer made of 18 mm thk. MR Ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thk MR ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note all fittings, fixtures, locking arrangement, handles, etc. Complete.				
13	Executives Branch Manager Table :	Nos.	1		
	same as above but providing and supplying Executives Branch Manager of <b>size -1.80 m x 0.90 m x 0.75 m ht.</b>				
14	Officer / Relationship Manager/ Auditor Tables :	Nos.	5		
	same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 1.65 - 1.50 m x 0.75 m x 0.75 m ht.		-		
15	Single Window Operator Counters :				
	Single Window Operator Counters : Single Window Operator Counters : same as above item & Following specifications and per dimensions specified.:- a. Size- 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. b. 18 mm thick MR Plywood c. 1 mm thick laminate d. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood e. Finished with 1 mm thick Plain or Textured Laminate Hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate.incliding all fitting labour, material etc complete.		7.5		
16	LUNCH TABLE				
10	Providing and fixing Lunch table of size- 8'x3' made 19mm tk MR Ply with 1mm laminate finish as per drawing including all material, labour etc complete and		1		

S.No.	Description of Item	Unit	Qty	Rate	Amount
17	Wall Mounted Writing desk :				
	Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. MR plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed. The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.	Nos.	1		
18	Storages / Credenza :				
10	Officer Storage/Side Credenza/Back Credenza :				
	Providing, making and placing in position Side Credenza storage:- Size 375mm depth, height of 750 to 900 mm 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. 4- All drawers shall be fitted with telescopic channels and locking arrangement laminated with 1 mm thick plain external surfaces and 0.8 mm thick white lamination on internal surfaces Note- SS Hinge, SS handles, magnetic catchers Godrej or ebco lock & brass handles all approved make etc.	Sqm	20		
	Glass Works :				
19	Plane Glass Dividers For Single Window Counters and Front Partition Glazing / ATM :				
	Providing, making and fixing Plane Glass :- a. 12mm thick clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc.,	Sqm	15		
20	Sofa set :				
	Providing, making and fixing in position sofa set with side arms :- 12 mm thick commercial ply 8mm thick commercial ply back side 150 mm thick high density foam rubber of approved quality to seat of zigzag spring approved Shade Leatherite 50 mm thick foam rubber of approved quality, density mini. 32 to back covered Note-Rate inclusive of cost of material, transportation, loading/unloading, labour tools & tackles up to any lead and lift etc. Measurement : no. of seats	seat	6		
01	Ocretes teble				
21	Center table Providing, making and fixing in position Cenetr table of size- 3'x2' with top 10 mm Thoughned glass with s.s stude finish with 1 mm Laminates including all material, labour etc complete	Nos.	1		
22	NOTICE BOARD : Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.	Nos.	1		
	Duran & Ormulaint Days				
23	Drop & Complaint Box : Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	Nos.	2		

S.No.	Description of Item	Unit	Qty	Rate	Amount
24	Vertical Blinds :				
	Providing & installing Vertical Blinds of Trac / Vista or equivalent, 100 mm wide, in two colours, of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail shall be with special GI brackets at approx 1meter c/c. complete as directed by the SBIIMS.		10		
	TOTAL AMOUNT FOR INTERIOR WORKS				