

BOQ FOR CIVIL WORK AT					
KOKRAJHAR BRANCH					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	Providing and fixing of 600x600 mm size non skid vitrified flooring of minimum 8 mm thick in 1:4 cement mortar (20 mm thick bed)/synthetic adhesive as applicable. all joints filling shall be completed in all respect. Rate shall include the finishing joints joints with matching colour pigments. Rate to include cost of floor leveling properly before fixing of tiles with adhesive after proper hacking of the existing tiles. Double charge Make-KAJARIA/ORIENT BELL/JOHNSON .Cost to include dismantling existing floor tiles , and disposing off same to dumping yard	sqm	1190		
2	Providing & applying 2coats of plastic emulsion paint after scrapping and preparing the old surface by way of POP punning 6 MM and filling up to even finish/as per approved make/shade including removing splashes & cleaning	sqm	1200		
3	Painting two coat (including appropriate priming coat) on previously painted wood and steel/other metal surface with enamel paint of approved brand and manufacture(Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.The rate also includes cost of primer.	sqm	450		
4	Finishing wall with two coats of acrylic emulsion exterior coatings of Unicem "Rakshak" brand of required shade by thinning 1ltr. of paint with 750ml of water to give an even shade after thoroughly brooming the surfaces to remove all dirt and remains of loose powdered materials as specified and directed by the department.The rate includes primer applied @ 2.2 Kg/10 sqm.The rate also includes applying of wall putty wherever necessary and as instructed by Bank/EIC.	sqm	2646		

**The rates are exclusive of statutory taxes (GST)**