

**INDICATIVE PRICE BID FOR INTERIOR WORKS FOR UNIFORM LAYOUT IMPLEMENTATION IN SBI NEDUMANGAD TOWN BRANCH, UNDER RBO-IV TVM, AO TVM. (PARTIAL RENOVATION WITH LAMINATE CHANGE ):-**

SI No.	Description of work	Quantity	Unit	Rate	Amount
1	<b><u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u></b>				
	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	16.00	Sq.M		
2	<b><u>Counter Top with Laminate Finish:-</u></b> Providing, fitting and fixing the counters with 18mm thick plywood of approved shade and make as per drawing and design finished with 1mm thick flexi mica.The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work. <b>12 mm thick glass with polished bevelled edges to be provided for the counter table top with necessary wire manager.</b>	16.00	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	15	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings, drawer locks and any other fittings etc. complete. Area of partition excluding existing glass area to be measured for payment.	101	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	44	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	6	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	241	Sq.M		
9	Painting the walls/ ceiling using approved quality ' Asian paint or equivalent two coats without putty finish to walls and ceiling.	368	Sq.M		
10	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade over one coat of putty including cleaning the surface.	216	Sq.M		

11	<b><u>LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM:-</u></b>	2.00	Sq.M		
	Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Existing Clear float glass of 12 mm thick to be removed and refixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided.				
12	<b>Custom Made Full Height Solid Partition:</b> Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beedings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	9.00	Sq.M		

13	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	4.00	Sq.M		
14	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	8.00	Sq.M		
15	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using <b>PT</b> Standard fittings like PT 90/PT 92 of <b>Dorma or equivalent make</b> at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	19.00	Sq.M		
16	Providing and Fixing Vertical Blinds of Vista Levton or approved equivalent make and colour.	23.00	Sq.M		
17	Enamel Painting of window grills, rolling shutter, collapsible grill, inside counters, tables, draws, storages etc with two coats of enamel paint of approved color over a coat of primer after cleaning the surface atc complete.	236.00	Sq.M		
18	Dismantling existing aluminium partitions, full height glass partitions, low height partitions and wall panelling, existing laminate/plywood etc as per requirement for relocation for temporary working, stacking the usable items after temporary usage as directed or stacking after removal as directed and disposal of debris away from site.	1	LS		

19	<u>Gypsum Board False Ceiling:-</u> Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. Rate to include closing of all wall openings with masonry or plywood, above the false ceiling level, as per Engineer's instructions.	45	Sq.M		
	<b>Rate includes removal of the existing old grid ceiling and removal of debris away from site.</b>				
20	<u>Full height partly solid and partly Glazed partition :-</u> Providing and fixing in position partly panelled and partly glazed partition as per specification in item no.(8) above but with 8 mm thick float glass with etching between 900 mm and 2100 mm level between the solid partition as per size required at site fixed with necessary SS D brackets. The edges of partition is to be finished with 1 mm thick laminate. Measurement for the partition area shall be consider from the floor level to false ceiling level only.	24.00	Sq.M		
21	Providing PVC telescopic key board tray with channel wherever necessary, to replace damaged ones only.	9.00	Nos.		
22	Removing the existing drawer channel and fixing new telescopic channel of approved make, for replacement of damaged channels only.	4.00	set		
23	Providing and fixing Godrej auto lock or equivalent, for cash drawers.	12.00	Nos.		
24	Providing and fixing Godrej Night Latch or equivalent, for wicket doors of Single window counters.	5.00	Nos.		
25	Providing and fixing Godrej lock or equivalent, for storage doors etc.	12.00	Nos.		
26	Providing and fixing stainless steel handles, for low height storage doors etc.	12.00	Nos.		
27	Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.	1	No.		

28	Providing and fixing table of size 1200 x 600 X 750 mm high to detail as shown in drg. as per specification in item no.13 above. 12 mm thick glass with polished edges to be provided on table top.	2	Nos.		
29	<b>Side Table For Officer :-</b> Providing and fixing side unit for Officer table to detail as per drg. of size 1000mm x 450 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	Nos.		
30	Providing and fixing good quality <b>Aluminium composite panelling</b> for front portion of Bank and <b>ATM</b> , at the exterior columns, with white coloured panels or as per the directions given.	29	Sqm		
31	GRID Ceiling:- with fissured mineral fibre board tile 600 x 600 x 12 mm thick (amstrong or approved equivalent) over the suspended grid system with hot dipped pre-coated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions T Sections 24 x 38x 0.7 mm size in bottom directions to form 600 x 600 grid. Necessary cutouts for lighting fixtures, air conditioner, air conditionin grills etc to be provided.	11	Sq.M		
32	Providing and fixing wall mounted writing desk of 1200 x 350 mm in 19 mm plywood with 1 mm laminate on all exposed surfaces. Top portion is to be provided with 12 mm clear glass with polished edges, with shelves to keep slip books including frosting of approved design and exposed edges to be fixed with TW beeding with melamine polish. A provision to be made for keeping Banks printed Broachers for public etc. complete.	1	No.		
	<b>TOTAL</b>				
	<b>GST @ 18%</b>				
	<b>GRAND TOTAL</b>				