

BOQ FOR INTERIOR & FURNITURE WORKS AT					
NEW PREMISE OF SBI SME TEZPUR, ASSAM					
Sl.No	Description of items	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Supply and installing of size- <b>2130 mm x 1830 mm x 750 mm</b> including cost of <b>side credenza (1200mm x 600mm x 750 mm)</b> for <b>Branch Manager</b> made up of 19mm thick Block board all around, finished with <b>1.00 mm thick laminate</b> of colour, shade & brand as approved. The table cost to include (pedestal), three drawers of 450 mm wide made with 6mm/12mm ply on right hand side on telescopic slider and a keyboard tray 250mm wide, <b>CPU stand, foot rest</b> as per design and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/ bidding of required size stained to match the desk and melamine finished. <b>All inner surface to be finished with 0.8 mm thick laminate.</b> The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & <b>8 mm thick glass duly finished to be placed on top of table &amp; credenza</b> and necessary cut-out to accommodate wires, edges to be m/c polished, with <b>ms powder coated wire manager</b> complete as per Bank's new uniform colour, layout & elevation policy. Rate shall include dismantling of existing item if any.  Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	Each	1		
2	<b>Staff Tables:</b> applying and installing Tables of Overall size - <b>1680 mm X 1830 mm x 750 mm including cost of side credenza (1230 mm x 450 mm x 750 mm)</b> made up of 19mm thick block board of approved brand all around and finished with <b>1.00 mm thick laminate</b> colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with <b>CPU stand and foot rest</b> as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type.Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & <b>8 mm thick glass duly finished to be placed on top of table &amp; credenza</b> and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Rate shall include dismantling of existing items if any.  Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	Each	8		
3	Providing and fixing floor mounted <b>Writing Desk</b> of size <b>1200mm x 300mm x 900mm (H)</b> made of 19 mm/ 12 mm ply finish with <b>1.00 mm thick laminate</b> and with <b>12 mm thick float glass on top</b> and voucher pigeon holes as per design & direction of bank, with laminated boards support.	Each	1		
4	<b>Storage Unit:</b> Providing and fixing storage unit of size <b>1200mm x 750 mm</b> , made up of 19 mm thick block board of approved brand on top & vertical support and finished with <b>1.00 mm thick laminate</b> of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19 mm thick plywood and finished in 0.8 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. <b>All inner surface to be finished with mat finish enamel paint of approve brand.</b> The works to include all hardwares such as: castors, brass hinges, ball catchers, locks , handles etc. of Godrej or approved make. Rate shall include dismantling of existing storage if any.  Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	RM	12		
5	Fabricating and fixing <b>Column/ Wall Panelling</b> with 12 mm thick ply finished with <b>1.00 mm thick laminate</b> of approved shade and brand over <b>25 mm * 35 mm (thickness not less than 1.5 mm) Aluminium Section framework</b> of approved brand at <b>spacing not exceeding 600 mm both ways (horizontal and vertical)</b> . Panelling framework to be secured to wall surface / column surface Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	76		
6	Fabricating and fixing <b>Full Height Solid Partition (FHSP)</b> , made of <b>6 mm</b> ply approved brand both side and to be finished with <b>1.00 mm thick laminate</b> of approved brand, colour and shade over <b>50 mm x 50 mm</b> ( thickness not less than 1.5 mm) <b>Aluminium Section</b> framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood bidding/lipping of required size with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition if any.  Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	26		

7	<p>Fabricating and fixing <b>Full Height Semi Glazed Partition (FHSGP)</b>, made of <b>6 mm thick ply</b> of approved brand in both side and to be finished with <b>1.00 mm thick laminate</b> of approved brand, colour and shade over <b>50 mm x 50 mm (thickness not less than 1.5 mm) Aluminium Section</b> framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. <b>Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass</b> (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall includes etching of glass as required by bank. Rate shall include dismantling of existing partition if any.</p> <p>Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	39		
8	<p>Providing and fixing low height semi glazed wooden partitions (<b>Total height 4.0 feet</b>) made of 6 mm ply of approved brand in both side and to be finished with <b>1.00 mm thick laminate</b> of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). <b>Top portion from 2.5 feet to 4.0 feet height shall have 12 mm thick plain float glass</b> (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished as per design and direction by bank. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Rate shall includes making provision for fixing of counter top 12 mm glass on its edges with necessary fixing arrangement as directed. Rate shall includes etching of glass as required by bank. Rate shall include dismantling of existing partition if any.</p> <p>Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	10		
9	<p>Providing and fixing <b>Solid Door Shutter</b> made up of 38 mm thick block board of approved brand and quality, finished both side with <b>1.00 mm thick laminate</b> of approved brand, colour and shade. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as required by bank.</p> <p>Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	13		
10	<p>Providing and fixing <b>Semi Glazed Door Shutter</b> made up of 38 mm thick block board of approved brand and quality, finished both side with <b>1.00 mm thick laminate</b> of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as required by bank.</p> <p>Ply/Block Board Make: MR Grade of Century/Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	5		
11	<p><b>Main Gate:</b> Providing and fixing <b>Glazed Door</b> made of 12 mm thick float glass with frosted film fixed in between top &amp; bottom rail and side stile of plywood framework of size 125 mm x 50 mm. The framework to be finished with <b>1.00 mm thick laminate</b> on both side. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on <b>heavy duty floor spring/door closer</b>. Rate shall includes all hardwears such as: Two nos S.S. finish handle, lock, door stoper, hinge, tower bolt etc. of approved make.</p>	SQM	4		
12	<p>Providing &amp; fixing in position <b>Aluminium Composite Panel (ACP) / Shutter Boxing</b> Panelling with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the framwork with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.</p>	SQM	2		
13	<p><b>Grid False Ceiling</b> : Providing and fixing suspended false ceiling with <b>600x600 mm size &amp; 12mm thick</b> mineral fiber ceiling tiles of <b>Armstrong</b> dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.</p>	SQM	115		
14	<p><b>Gypsum Board False Ceiling</b> : Providing and fixing suspended <b>12mm thick</b> Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern &amp; cut outs for light fittings, cove light etc. complete as per design direction by bank.</p>	SQM	50		
15	<p>Providing &amp; fixing in place 100 mm. <b>Vertical Blinds with Scotch Guard</b> of approved make, quality and colour shade &amp; pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform &amp; adequate.</p>	SQM	15		
<b>Total Cost (Excluding GST)</b>					