SCHEDULE OF QUANTITIES

Sr. No.	Item Description	Units	Qty	Rate	Amount
1	Plastering with Cement Mortar 1:4, 12mm thick one coat floated hard and trovelled smooth to compound walls inluding providing necessary coping.	Sq.m	10		
	Einiching the new coment plantaged				
2	Finishing the new cement plastered wall with one coat of primer, 2 coat putty and painted with 2 coat of exterior grade plastic emulsion paint after clearing the surface.	Sa m	10		
3	Providing and fixing pre-fabricated structure (ladder cum pathway) consisting of 2" X 2", 14 gauge G.I sections and 1" X 1", 14 gauge G.I sections as per the given drawing for maintenance activity in the central atrium of A.O. building. Rates also to include painting with 2 coats of iron primer & 2 coats of enamel paint, labour charges, materials, transportation, scaffolding etc. as per the directions of Engineer In Charge.	Kg	2700		
	TOTAL (Excluding GST)				

GST as applicable will be paid extra