## **BOO FOR THE PROPOSED WORKS OF RENOVATION/INTERIOR/FURNISHING OF BRANCH** FOR STATE BANK OF INDIA BRANCH DETAIL: RAMA INDUSTRIES, JHABUA (M.P.) INTERIOR FURNISHING AND CHAIRS S.N. Description of Item Unit Quantity Rate <u>Amount</u> False Ceiling and Repairs Providing and fixing and finishing Gypsum Board False Ceiling as per drawing made from 60mm x 36mm (approx.) G.I. 'C' main supports suspended from the ceiling by means of 25 mm x 18 mm (approx.) G.I. suspenders fitted to the ceiling above with anchor fasteners and rowl plugs in concrete ceilings and other suitable approved means on all other type of ceilings as required and as per design, having pattas/ concealed coves as indicated in drawings. Fixing 11-12.5 mm (approx.) thick gypsum board on GI channels using good quality self-tapping screws, finishing and jointing two boards with adhesive and jointing tapes finished complete in lines and level including providing coves, cut-outs for light fittings and extra frame work as necessary for AC grills and/or any other cutouts etc. complete in all respects. Quoted rate to include cost of making opening for light fittings, grills, diffusers, coves for fitting of diffused lights etc. as required and making good the same. Cost of additional frame required and/or as directed shall also be included in the rate). It may be noted that the vertical surfaces shall also be measured for payments and the quoted rates should take into account this area. Rate shall include 2 coat putty and 1 coat acrylic putty followed by three coats of Plastic Emulsion paint of sqM 156.00 Providing & fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with Classic Lite (Tegular) EDGE TILES WITH ARMSTRONG 24mm **EXPOSED GRID.** The tile should have Humidity Resistance (RH) of 99%, NRC 0.5, Light Reflectance ≥84%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm with Bio Block coating on the face of the tile, suitable for Green Building application, with Recycled content of 35 - 38%. The tile shall be laid on Armstrong Prelude32 with 24 mm wide T section flanges colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm, 25 mm respectively. The cost shall include all fittings and materials, scaffoldings, walkways etc. complete including 71.00 Sq.M proper installation and provisioning etc. Providing and fixing **coves** for lighting in any shape RMt. 60.00 **Panellings and Partitions**

S.N. 4	Description of Item	11			
4	B . I I.C	<u>Unit</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
	Providing and fixing single skin panelling on walls/columns with laminate finish.  Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 8 mm shall be fixed as per the design in the drawing or as directed by Architect, with required molding/lipping patty on the edges and finished with laminate comprising as under:-  (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick (approx.) extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columnns in perfect line, level and plumb. or alternatively if required and as required with ply levelling framework or aluminum framework panelling and 18 mm thick ply of approved ISI grade for panelling of columns etc.  (ii) Panel Finishing:- Providing & fixing 8 mm thick approved make BWR plywood as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate of reputed makes (up to Rs.650 per sq.mt.) using approved adhesive, in approved pattern & design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.  (iii) Providing approved quality, seasoned, full length, Teak Wood moldings/lipping patti with adequate width as required at site, to all openings, cutouts etc duly				
	-contd-Teakwood lipping etc shall be provided where required or directed and shall be finished with 1mm thick textured laminate as approved and the rates shall be including provision for items like soft board/ white board, electrical switchboards, telephone and electrical wiring etc as and where required (but excluding the cost for the items).	Sq.M	116.50		

N.	<u>Description of Item</u>	<u>Unit</u>	Quantity	<u>Rate</u>	<u>Amount</u>
5	Providing and fixing <b>FULL HEIGHT DOUBLE SKIN</b>				
	PARTLY GLAZED/ UNGLAZED PLY PARTITION in				
	position 70mm thick +/- 2mm full height solid/opaque ply				
	partitions finished with laminate on both sides comprising				
	as under:-				
	(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick				
	(approx.) or other appropriate approved hollow aluminium				
	square sections at spacing not exceeding 600 mm (may				
	slightly vary as per unavoidable site conditions) both ways				
	(horizontal and vertical) fixed rigidly on floor, wall / column				
	& ceiling.				
	(ii) Plywood skin:- Providing & fixing 8 mm thick BWR				
	plywood as per the design to Aluminum framework				
	(iii) Finishing:- Providing 1.00 mm thick approved quality				
	and shade laminate of reputed makes (up to Rs.650 per				
	sq.mt.) using approved adhesive, in approved pattern &				
	design, including approved quality and shade laminate, on				
	both sides of partitions in approved design & pattern				
	including making grooves as per Architectural drawing or				
	as directed by the Engineer-in-charge using approve				
	quality adhesive complete.				
	(iv) Making suitable cutouts/ openings/ channels for Doors,				
	electrical conduits, cables & switch boards, AC ducts etc				
	including providing necessary wooden supports wherever				
	required and directed at site.				
	(v) Providing and making suitable door frame (wherever				
	flush doors are to be fitted) with rebate for door shutters				
	using approved quality seasoned full-length Teak Wood				
	having finished sectional size. Teakwood lipping etc shall be				
	provided where required or directed and shall be finished				
	-contd- the rates shall be including provision for items like				
	soft board/ white board, electrical switchboards, telephone and electrical wiring etc as and where required (but				
	• • • • • • • • • • • • • • • • • • • •				
	excluding the cost for the items). All glazed openings in partitions having 5 mm thick glass shall be counted in				
	partitions riaving 5 min trick glass shall be counted in partition areas and cost shall include all lippings, beadings				
	etc. complete required for framing etc. 8mm, 12mm glass				
	openings wherever applied shall neither be included in				
	measurements nor costing and shall be considered as				
	separate item to be paid under the relevant item in the				
	tender. Providing, finishing and fixing of lippings/ beadings				
	for these shall be included in the cost of partition. <b>The</b>				
	internal framework for partition shall be extended so				
	as to secured the partition to available concrete				
	ceiling/beams etc. The extended part shall remain				
	without the 8mm ply/laminate on both sides.				
	MEASUREMENT FOR THE PAYMENTS SHALL BE DONE				
	ONLY BELOW THE FALSE CEILING, THE RATE				
	·	Sq.M	22.00		

١.	<u>Description of Item</u>	<u>Unit</u>	Quantity	<u>Rate</u>	<u>Amount</u>
T	Providing and fixing HALF HEIGHT DOUBLE SKIN				
- 1	GLAZED/UNGLAZED PLY PARTITION in position 70mm				
ŀ	thick +/- 2mm half height approx. 1.2m high solid/opaque				
١	ply and/or 0.9m solid partitions with 12mm thick glass upto				
	1.2m height supported on d-buttons or grooves or lippings				
l	in cutouts, partition shall be finished with laminate on both				
ŀ	sides comprising as under:-				
	(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick				
	(approx.) or other appropriate approved hollow aluminium				
	square sections at spacing not exceeding 600 mm (may				
	slightly vary as per unavoidable site conditions) both ways				
	(horizontal and vertical) fixed rigidly on floor, wall /				
	column/ furniture.				
	(ii) Plywood skin:- Providing & fixing 8 mm thick BWR				
	plywood as per the design to Aluminum framework				
	(iii) Finishing:- Providing 1.00 mm thick approved quality				
	and shade laminate of reputed makes (up to Rs.650 per				
	sq.mt.) using approved adhesive, in approved pattern &				
	design, including approved quality and shade laminate, on				
- 1	both sides of partitions in approved design & pattern				
	including making grooves as per Architectural drawing or				
	as directed by the Engineer-in-charge using approve				
- 1	quality adhesive complete.				
	(iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc				
	-contd- (v) Teakwood lipping etc shall be provided where				
	required or directed and shall be finished with 1mm thick				
- 1	textured laminate as approved and the rates shall be				
	including provision for items like soft board/ white board,				
- 1	electricalswitchboards, telephone and electrical wiring etc				
- 1	as and where required (but excluding the cost for the				
	items). All glass work above the partition shall be counted				
- 1	in partition areas and cost shall include all lippings,				
	beadings etc. complete required for framing etc.	Sq.M	15.50		
t	Fabrication of Aluminum Composite Panel (ACP)	oq.i.i	13.30		
	Facias/column claddings etc. as per drawings and				
	specifications with 4 mm thick exterior grade composite				
	(AL-PE-AL) panels of choice and of reputed brands like				
	Viva, Alstrong, Alstar as approved having two aluminum				
	skins pre-coated and thermally bonded on each side of non				
	toxic polyethylene core. The structure shall be fabricated				
	using fresh, 18 guage 25mmx50mm (approx.) Aluminum				
	rectangular pipe section of good quality or members				
	recommended by the manufacturer and in accordance with				
i	the specifications and recommendations of the				
	manufacturer. The structure shall be fitted in place ON				
	walls/beams/columns/MS fabricated structures etc. as				
	instructed using recommended fixing method, adhesives,				
	sealers, etc. complete to the engineer-in-charge's				
	satisfaction. The cost shall include all scaffoldings, chase				
	making, lifting, cutting, on site adjustments, plaster	Sq.M	65.00		

5.N.	<u>Description of Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
8	Providing and fixing full & low height storage cabinets				
	as storage and/or runners from 400mm to 600 mm				
	depth in 18mm thk. ply construction with 6mm thk.comm.				
	ply backing complete as per detail/ specifications with				
	horizontal & vertical divisions and drawers as/detail. The				
	rate shall include all TW lippings, lamination of partitions,				
	shutters shall have wooden lipping/ and finished with 1mm				
	thick Textured Laminate (up to rs.850 per sq.mt.) on outer				
	face of the shutter and the shutter edges, storage top and				
	all exposed faces of the storage . Inside of storage and				
	shutter shall be finished with economical laminate in				
	matching or plain colour, as required. The handles & hinges				
	will be s s finish or as as/app. & shutters shall be on ebco				
	self closing hinges and drawers shall be on ebco telescopic				
	slides.	Sq.M	21.50		
9	Providing and fixing <b>Cabinet for Electrical</b>	Sq.in	21.50		
_	Panel/Distribution Board (for DBs outside electrical				
	room only) from 400mm to 600 mm depth in 18mm				
	thk. ply construction on open back (without 6mm				
	thk.comm. ply backing) fitted on ply framework (cost				
	included) to complete as per detail/ specifications. The rate				
	shall include all TW lippings, lamination etc. complete. the				
	shutters shall have wooden lipping/ and finished with 1mm				
	thick SF/Textured Laminate (up to rs.650 per sq.mt.) on				
	outer face of the shutter and the shutter edges and all				
	exposed faces of the storage . Inside and shutter inside				
	face shall be finished with economical laminate in matching				
	or plain colour, as required. The handles & hinges will be s				
	s finish or as as/app. & shutters shall be on ebco self				
	closing hinges.	Sq.M	3.78		
<b>D</b>	Tables	[5q.i <sup>4</sup> ]	3.70		
	Providing and fixing Executives Branch Manager Tables		T T		
0	having a top of approx size Length upto 1.8M-2.1mx				
	width upto 0.90m and standard height excluding cost				
	of runner. The table shall be made in 18mm ply				
	construction with C.P.U. space, single drawer and cabinet				
	below as per design and drawing. The table edges shall be				
	double thick and all visible surfaces including table tops				
	facia of drawers and outside of shutters etc. shall be				
	finished with 1 mm thick SF/Textured Laminate (up to				
	Rs.650/- per sq.mt.) as directed, the bottom and inside of				
	table shall be finished with 1mm thick laminate of approved				
	make, colour and design and all hidden areas like inside of				
	drawers, cabinets, finished with economical laminate. Cost				
	shall include providing and fixing Computer keyboard trays				
	(Powdercoated MS) EBCO make or equivalent as per	1			
	approval with keyboard and sliding mouse tray attachment	1			
	in colour as per approval under worktops as and where				
	instructed.The cost shall be complete with lippings,				
	mouldings, telescopic drawer channels, accessories, hinges				
	etc as per specifications.				
	lete as per specifications.	<b>].</b> .			
		Nos	1.00		

	INTERIOR FURNISH	1	1 1	-	
.N.	<u>Description of Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1	Providing and fixing OFFICER, RELATIONSHIP SERVICE				
	MANAGER and AUDITOR Tables approx size length				
	1.65-1.50mx width upto 0.75m and standard height				
	<b>excluding runner</b> in 18mm ply construction with C.P.U.				
	space, single drawer and cabinet below as per design and				
	drawing. The table edges shall be double thick and all				
	visible surfaces including table tops facia of drawers and				
	outside of shutters etc. shall be finished with 1 mm thick				
	SF/Textured Laminate (up to Rs.650/- per sq.mt.) as				
	directed, the bottom and inside of table shall be finished				
	with 1mm thick laminate of approved make, colour and				
	design and all hidden areas like inside of drawers, cabinets,				
	finished with economical laminate. Cost shall include				
	providing and fixing Computer keyboard trays				
	(Powdercoated MS) EBCO make or equivalent as per				
	approval with keyboard and sliding mouse tray attachment				
	in colour as per approval under worktops as and where				
	instructed. The cost shall be complete with lippings,				
	mouldings, telescopic drawer channels, accessories, hinges	Nos	2.00		
12	Providing and fixing Assistant/Clerical Staff (Clerks,				
	SBI Counters) Tables approx size 1.5-1.35mx0.75m				
	and excluding runner in 18mm ply construction with				
	C.P.U. space, single drawer and cabinet below as per				
	design and drawing. The table edges shall be double thick				
	and all visible surfaces including table tops facia of drawers				
	and outside of shutters etc. shall be finished with 1 mm				
	thick SF/Textured Laminate (up to Rs.650/- per sq.mt.) as				
	directed, the bottom and inside of table shall be finished				
	with 1mm thick laminate of approved make, colour and				
	design and all hidden areas like inside of drawers, cabinets,				
	finished with economical laminate. Cost shall include				
	providing and fixing Computer keyboard trays				
	(Powdercoated MS) EBCO make or equivalent as per				
	approval with keyboard and sliding mouse tray attachment				
	in colour as per approval under worktops as and where				
	instructed. The cost shall be complete with lippings,				
	mouldings, telescopic drawer channels, accessories, hinges				
	etc as per specifications.	Nos	2.00		
L3	Providing and fixing <b>SERVICE WINDOW OFFICER</b>				
	COUNTERS Tables approx size 1.5-1.35m x0.9-0.8m x				
	<b>0.75m and excluding runner</b> in 18mm ply construction				
	with C.P.U. space, single drawer and cabinet below as per				
	design and drawing. The table edges shall be double thick				
	and all visible surfaces including table tops facia of drawers				
	and outside of shutters etc. shall be finished with 1 mm				
	thick SF/Textured Laminate (up to Rs.650/- per sq.mt.) as				
	directed, the bottom and inside of table shall be finished	1			
	with 1mm thick laminate of approved make, colour and	1			
	design and all hidden areas like inside of drawers, cabinets,				
	finished with economical laminate. Cost shall include				
	providing and fixing Computer keyboard trays	1			
	(Powdercoated MS) EBCO make or equivalent as per				
	approval with keyboard and sliding mouse tray attachment				
	in colour as per approval under worktops as and where				
	instructed. The cost shall be complete with lippings,				
	mouldings, telescopic drawer channels, accessories, hinges	RMt.	4.50		

	INTERIOR FURNISH	NG AN	D CHAIRS	5	
S.N.	<u>Description of Item</u>	<u>Unit</u>	Quantity	<u>Rate</u>	<u>Amount</u>
14	Providing & placing <b>Grahak Mitra approx size</b> 1.65mx0.8-0.9mx0.9-0.75m excluding runner in 18mm ply construction with C.P.U. space, single drawer and cabinet below as per design and drawing. The Design shall carry arch shape and matching elements which shall be made using 3 nos 6mm thick flexible ply of approved brand, bonded together with synthetic adhesives like fevicol etc. using ply formwork, jigs and fixtures (cost included in the quote). The table edges shall be double thick and all visible surfaces including table tops facia of drawers and outside of shutters etc. shall be finished with 1 mm thick SF/Textured Laminate (up to Rs.650/- per sq.mt.) as directed, the bottom and inside of table shall be finished with 1mm thick laminate of approved make, colour and design and all hidden areas like inside of drawers, cabinets, finished with economical laminate. Cost shall include providing and fixing Computer keyboard trays (Powdercoated MS) EBCO make or equivalent as per approval with keyboard and sliding mouse tray attachment in colour as per approval under worktops as and where instructed. The cost shall be complete with lippings, mouldings, telescopic drawer channels, accessories, hinges				
	etc as per specifications	Nos	1.00		
16	Providing & placing <b>Wall Mounted Writing desk</b> in 18mm ply construction as per design and drawing. The table top shall be in 12 mm thick glass. The table edges shall be double thick and all visible surfaces shall be finished with 1 mm thick SF/Textured Laminate (up to Rs. 650/- per sq.mt.) as directed, of approved make, colour and design as directed. <b>SQUARE, RECTANGULAR, CIRCULAR or CURVE SHAPED Centre/Side tables</b> of approx. 400 to 500mm height in 18mm thk. Ply in simple box type construction. The table sides and all visible surfaces shall be finished with laminate of upto two colours with 1 mm thick SF/Textured Laminate (up to Rs. 650/- per sq.mt.) as directed, approved make, colour and design if required. 12 mm thick glass (cost not included) shall be placed on the top if instructed.	Nos Sq.M	1.00		
E	CORIAN AND GLASS				
19	Providing and fixing 12 mm thk TOUGHENED fixed glass for glazing at entrances etc. and half height partitions of Single Window Counters (of approximate size 1450mm x 400mm - 100mm cut and edge polished in curvilinear/tapered shape) fitted with suitable SS Patch Fittings of reputed makes and size as demarcated and adjoining the doors etc and/or as required. The glazing shall be of 12 mm thk. clear float glass, cut to size/shape etc. as directed, edge polished and TOUGHENED, fixed as per SS Fitting manufacturer's recommendations and specifications, fixed to walls, granite pattas, furnitures, adjoining doors or wooden frames/partitions, panellings etc. as required, The fittings shall be in approved finish. Rates shall take into consideration all aspects like edge polishing, hole making, toughening, supply of S S Patches, transportation, handling, lifting etc.				

.N.	Description of Item	<u>Unit</u>	Quantity	<u>Rate</u>	<u>Amount</u>
20	Providing and fixing 12 mm thk fixed glass for glazing/				
	Partition / Glass on Transaction side of Single				
	Window Operator Counters of size as demarcated and				
	adjoining the partitions/doors etc and/or as required made				
	out of 12 mm thk. clear float glass, edge polished fixed in				
	grooves, ply framework with wooden lippings and/or				
	wooden top and bottom rails adjoining doors or wooden				
	frames/ partitions with wooden ribs etc. and/or jointed to other glasses with UV setting glass adhesive as required.				
	Cost shall include provision of Lamination of glass with				
	etching film of sticker type as per the architects designs				
	where required.	caM	6.00		
F	DOORS	sqM	6.00		
	Providing and fixing 12mm thk Toughened Glass Doors				
•	of any size at Entrances/ Conference room/ Cabins				
	etc. single or a set of two where required, and of size				
	as demarcated, swing type door openable both sides made				
	out of 12 mm thk. clear <b>toughened</b> float glass, edge				
	polished fixed in SS patch fittings of Dorma or equivalent				
	patch fittings as per the manufacturers recommended				
	process and methods, of approved finish and as per the				
	placement in drawings and specifications fixed on				
	Everite/ozone/ Hardwyn/ Dorma or equivalent floor springs				
	and provision of approved locking system, one set of				
	25mm dia S. S. brush finish pull handles as per approval				
	complete. Each door shutter shall be treated individually				
	with complete set of accessories to be provided on each				
	door, measurement shall be done of the opening in Sq.M.	Sq.M	9.50		
26	Aluminum Framed Glass Door for UPS / Server Room	3q.M	9.30		
	powder coated aluminum sections (heavy duty) having				
	both verticle styles and horizontal top, middle (lock rail) &				
	bottom sections as per standards having panels with 6.0				
	mm thick plain FLOAT glass in top panel and bakelite sheet				
	of approved colour in the bottom panel. The aluminum				
	frame shall be of minimum 18 guage, of standard top,				
	middle and bottom rails and styles, ply infill on the hinged				
	side style, aluminum centre lock, aluminum door handle,				
	door stopper on the outside and tower bolt from inside. All				
	the required gaskets, angle cleats, brush gaskets shall be				
	included in the cost. Door Closer shall be fitted separately if				
	required and it's cost shall not be included in the door.	SqM	2.00		
7	Providing and fixing <b>Door closers</b> on doors of make	·			
	Everite/Ozone/ Hardwyn/ Dorma or equivalent upon				
	approval including all packing, levelling, etc. as required				
	and upto the architects satisfaction.	Nos	2.00		
	Providing and fixing additional <b>Night Latch type Lock</b>				
	(without handle) on doors of make Godrej/Ozone/Europa				
	or approved equivalent make and design. The latch shall				
	have minimum 3 keys and shall have automatic locking,				
	openable from inside with knob/sliding bolt and with keys from outside. The rate shall be inclusive of all required				
	carpentry works, all required guideplates, hardware, hole				
	cutting etc. complete.				
	catting etc. complete.	Nos	1.00		

N.	<u>Description of Item</u>	<u>Unit</u>	Quantity	<u>Rate</u>	<u>Amount</u>
9	Providing & finishing walls with <b>dual tone decorative</b>				
	texture/duotone paint effects of Asian/ Nerolac or				
	equivalent make as per approval complete having minimum				
	one colour or two colours laid as per the manufacturer's/				
	applicator's recommendations using appropriate				
	tools/rollers/base paints etc. as required to achieve evenly				
	spread, evenly shaded texture/paint effect to the				
	satisfaction of the Bank Engineer/ Architect. The rate shall				
	include cost of fixing of 4mm thick MDF of reputed brands if				
	required, preparation of surface, all required tools/				
	scaffoldings/etc. complete and shall include recommended				
	layers of waterproof and/or protective coating of treated /				
	textured/ nainted surface complete as directed	SqM	18.00		
30	Providing & finishing walls with <b>Premium Quality</b>				
	Wallpaper of approved design, colour, texture and quality				
	(basic rate upto Rs.700 per sq.M or Rs.65 per sq.ft). The				
	rate shall include surface preparation, levelling and				
	smoothening of wall with suitable cement based putty, all				
	labour and materials including required and recommended				
	adhesives all required tools/ scaffoldings/etc. complete to				
	the satisfaction of the Bank Engineer/ Architect. The				
	measurement shall be done for the application area only				
	and not based on rolls ordered.	CaM	5.00		
22		SqM	5.00		
32	Providing and applying <b>Premium Emulsion Paint on</b>				
	walls, ceiling, partitions etc. (Old or Fresh Putty				
	Finish Work) including surface preparation, cleaning,				
	scraping & scrubbing the flaky portions of old paint and				
	roughening of paint layers in good conditions. The scope				
	shall include putty touchup at all required areas, application				
	of primer etc. as per good practices and finishing with upto				
	two or more coats of ICI Dulux washable emulsion				
	<pre>paint or equivalent - roller finish (matt) to all indicated</pre>				
	wall surfaces. The paint shall be applied after thorough				
	cleaning of the existing painted/fresh work surfaces so as				
	to achieve a dirt-free, grease-free, plain surface free of				
	residual paints before painting with the emulsion. The paint				
	shall be applied as per the manufacturer's				
	recommendations, evenly to produce uniform well finished				
	surface, scope shall be including thorough final cleaning of				
	the premises to the Bank Engineer's / Architect's				
	satisfaction and complete at all level.	sqM	50.00		
Н	Chairs:	104	20.00		
	<b>C-1-</b> Executive chairs for BM cabin costing for High Back,				
در	swivel and synchro type chairs with castors and handrests				
	as per choice of quality and design (Featherlite Make				
	Design "Bodyline" cat no. BOD HB or equivalent upon				
	approval)	Nos	1.00		
34	C-2- Officer, Service Manager, Cash Officer, Conference		1.00		
	Room and Visitor Chairs for BM cabin costing for Medium				
	Back, swivel type chair with castors and handrests as per				
	choice of quality and design (Featherlite Make Design				
	. ,				
	"Bodyline" cat no. BOD MB or equivalent upon approval)	Nos	5.00		
35	<b>C-3-</b> Visitor Chair / Workstation / visitor /lunch room chairs	1	1 2.23		
	costing for Low Back, swivel type chairs with handrests and				
	castors, as per choice of quality and design (Featherlite				
	Make Design "Bodyline" cat no. BOD LB or equivalent upon				
	approval)				
	approvar)	Nos	7.00		
	Total of Interior Works and Chairs	1103	7.100		

	INTERIOR FURNISHING AND CHAIRS									
S.N.	<u>Description of Item</u>	<u>Unit</u>	<b>Quantity</b>	<u>Rate</u>	<u>Amount</u>					
IN W	IN WORDS RS.									