

CORRIGENDUM-1

**MODIFICATION AND EXTENSION OF LAST DATE OF BID SUBMISSION FOR AIR
CONDITIONING WORKS OF NEW BRANCH PREMISES OF RAHATGARH, RBO-5,
SAGAR**

**BHO-2023-24-JBP-56 : TENDER FOR AIR CONDITIONING WORKS OF RAHATGARH
BRANCH, RBO-5, SAGAR**

Please refer to the captioned tender document dated 23/03/2024

2. In this connection, it has been decided to modify the description of price bid point no. (3) to (8) and revise the last date of tender submission and Opening. The modified description (a) and revised dates (b) are given below:

(a)


S. No.	Existing Description in price Bid	Modification	
		Qty	Unit
1	Point no. 3 : Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, 5 STAR INVERTER RATING OF BEE AIR CONDITIONERS 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work	03	Nos.

JD C ✓

	<p>and material including copper piping of hard & prime quality of SIZE 12.5/22mm upto 3 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. The rates inclusive of all repairs of civil and carpentry work The cost includes original fill and additional top up of refrigerant gas as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only</p>	<p>The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The rates inclusive of all repairs of civil and carpentry work The out door unit should be anti-rust powder coated. The cost includes original fill and additional top up of refrigerant gas as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only</p>		
2	<p>Point no. 4: Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installtion. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:-</p>	<p>Point no. 4: Supply and installation of hard & prime quality of min. 22 G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/communication cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:-</p>	40	Mtr




	Superlon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells	Superlon/Aflex/Armacell/Kflex Make of cable:Finolex/RR		
3	Point no. 5: Drain Pipe (If Required additional) Applicable to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaining to mentioned work. (If required additionally, payment will made as per actual installation.) Make:- Kasta/supreme	Point no. 5: Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installation. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaining to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells	30	Mtr
4	Point no. 6: Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make:-Microtek, V-Gards (Voltage Range 150- 280 Volts)	Point no.6: Drain Pipe (If Required additional) Applicable to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaining to mentioned work. (If required additionally, payment will made as per actual installation.) Make:- Kasta/supreme	50	Mtr
5	Point no. 7: Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site	Point no.7: Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site	3	No.




	(For 2 Tr Split AC & Cassette AC) Make: Microtek, V-Gards (Voltage Range 150- 280 Volts)	(For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make:-Microtek, V-Gards (Voltage Range 150- 280 Volts)		
6	Point no. 8: Electronic Timer for auto swith on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T, and other Eq. ISI make	Point no. 8: Electronic Timer for auto swith on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T, and other Eq. ISI make	1	No.

(b)

S. No.	Description/ event	Existing Due Date and Time (as per captioned tender document)	Revised Due Date and Time
i	Last date & time for submission of Online Technical and Price bid, EMD and cost of tender document	Up to 3:00 P.M. on 05.04.2024	Up to 3:00 P.M. on 12.04.2024
ii	Date & Time of opening of e-tenders	3:30 P.M. on 05.04.2024	3:30 P.M. on 12.04.2024

3. All other terms & conditions in the tender document remain the same. Bidders are advised to submit the bids well in advance and avoid the last minute rush. SBI will not be responsible for bidders' failure to submit the bids within the time mentioned above.

Yours faithfully


Regional Manager
RBO-5
Sagar