

SCHEDULE FOR THE SUPPLY & INSTALLATION OF MACHINE ROOMLESS ELEVATOR FOR STATE BANK OF INDIA, KOTTAYAM TOWN BRANCH.

Item No.	QTY.	DESCRIPTION OF ITEMS	UNIT	RATE	RATE IN WORDS	AMOUNT
A		Machine roomless Elevator				
1	1.00	<p>Design, fabricating, supply, installation, testing & commissioning of one number Electric Traction Passenger Elevator (Machine roomless) with all accessories about 340 Kgs.(5 passengers) @ 0.63 metre speed per second to travel from Ground floor to Third floor with 4 stops and 4 openings (All openings on the same side). 415 Volts 3 phase 50 Hertz Alternating Current, A.C. Variable Voltage Variable Frequency (with speed encoder). Simplex Full Collective, microprocessor based moulder control system (Located on the top floor door column),gearless with permanent magnet motor (minimum 6.5 K.W) placed in the hoistway on top of the rails. About 950mm wide x1000mm deep 2100mm high inside car dimension.Scratch resistant Stainless steel Car body with mirror stainless steel handles on three sides with Granite / Vetrified tiles flooring and Stainless steel false ceiling with fan,and 1600x1200mm size mirror on the rear side of the car.</p> <p>Over load warning indication ,Floor annunciator with music, Simplex selective collective control,Car enterance is protected by centre opening stainless steel doors with clear opening about 700mm wide x 2000mm high.The door operation should be with infra Red Electronic door protection.One hour fire rated .The human interface should be,Hall button micro stroke push butttons combined 16 segments digital LED Disply position indicator,Full height car operating panel with micro stroke call push buttons (located on side panel),Door open and door close button on the car operating panel,2-way intercom with Press & Speak in COP, Dot matrix position indicator display integrated within the car operating panel,Battery operated Alarm / bell and emergency light,Fireman's switch at the main lobby. Automatic rescue devices,Indirect lighting system with LED, fan with automatic control etc. Providing sufficient lighting inside the well.</p> <p>Rate shall including cost and conveyance of all materials to site, labour charges for erection, lead, lift, transportation, handling charges, scaffolding cost and liaisioning charges for obtaining approval from electrical inspectorate etc complete.</p>	No			
		TOTAL				
		Add GST @ 18%				
		GRAND TOTAL (A)				

SCHEDULE FOR THE SUPPLY & INSTALLATION OF MACHINE ROOMLESS ELEVATOR FOR STATE BANK OF INDIA, KOTTAYAM TOWN BRANCH.

Item No.	QTY.	DESCRIPTION OF ITEMS	UNIT	RATE	RATE IN WORDS	AMOUNT
B		AMC OF ELEVATOR				
2		Comprehensive AMC for the above lift after one year warranty period. The frequency of servicing shall be monthly . ie 12 routine services every year and immediate service on break down calls				
		5 Passenger elevator-1 No.				
a		First year				
b		Second year				
c		Third year				
d		Forth year				
e		Fifth year				
		TOTAL				
		Add GST @ 18%				
		GRAND TOTAL (B)				
		TOTAL (A)+(B)				

(Signature(s) of the contractor(s))