

**PRICE BID FOR INTERIOR FURNISHING WORKS AT STATE BANK OF INDIA  
BRANCH AT KEYLONG (HP)**

**(PART -1)**

<b>S. N</b>	<b>DESCRIPTION OF ITEM</b>	<b>UNIT</b>	<b>QTY</b>	<b>RATE</b>	<b>AMOUNT</b>
<b>1</b>	<p><b>Officer's &amp; Staff Tables</b></p> <p>Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); Table Top to be clad with laminate 1mm thick (of approved shade), with 40 mm X 12 mm thick teak wood as per drawing. The front of the table top shall be projected as per drawing. The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.</p> <p>The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications.</p> <p>A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and 3/4" x 1/4" teakwood/MDF lipping on two visible sides. three lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood &amp; front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1 1/2" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg- space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood /MDF edges / lipping / beading shall be Spirit polished or Spray Painted as required.</p>				
<b>a</b>	Size 6'0" X 3'0" X 2'6"	Nos.	1.00		
<b>b</b>	Size 5'0" X 2'6" X 2'6"	Nos.	1.00		
<b>c</b>	Size 4'6" x 2'6" x 2'6"	Nos.	1.00		
<b>d</b>	Size 4'-0"x 2'6" x 2'6"	Nos.	2.00		

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
2	<p><b>Single Level SWO Counters</b>  Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick matt laminate of approved make and shade on outer visible surfaces (single color on horizontal surface &amp; two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer block board and finished with 6mm thk. flexi ply as base over curved area with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of approved make fixed on channels, as per manufacturer's instructions / specifications.</p> <p>Three drawers with top drawer having autolock running on both sides mounting Telescopic (channels) of approved make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 19 mm thick plywood, bottom of 19 mm thick plywood &amp; front of 19 mm thick commercial ply. Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 0.8mm thk. lining of white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes &amp; the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front if desired.</p>	Rmt	2.74		
3	<p><b>8.0 MM thk glass on top of officers tables.</b> All the edges of the glass shall be grinded polished including Hole for cable manager.</p>	Sq.mt	5.74		
4	<p><b>LACQUERED GLASS IN FRONT OF SW COUNTERS:</b>  Providing and fixing 6mm thick Lacquered Glass of approved color (Aqua Blue/ White) as/ design drawing. The glass shall be pasted with Dow Corning Silicon (Dowsil) Neutral Cure (DC 896 white), over the front of counter as per item no 1. The glass edges shall be grinded/ polished to satisfaction of the engineer-in-charge/ architect</p>	Sq.mt	1.16		
5	<p><b>12 MM thk. toughened glass for Banking / SWO Counters</b>  Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level &amp; to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions &amp; side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free</p>	Sq.mt	3.22		
6	<p>Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.</p>	Nos.	10.00		
7	<p>Providing and fixing (12mm thick) white <b>acrylic stone</b> (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including buffing and wastage. <b>(Make: Du-Pont.,LG,MERINO,HANEX_Glaciard White_)</b></p>	Sq.mt	4.65		
8	<p><b>Side Credenza</b>  Providing &amp; fixing Side credenza ( 15" to 18" deep ) made of 19 mm thick commercial ply and 6 mm thick plywood on back side &amp; 1mm thick laminate of approved shade on top horizontal surface &amp; vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontaly running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.</p>				

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
a	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0" / 3'-6" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	Rmt.	4.27		
9	<b>Full Height Storage In Store</b> Providing & fixing Full height storage 24" deep & 8'-0" HT made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on front horizontal surface & front vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The storage cupboard will be divided into 4 parts with shutters and shelves. The shutters with handle / knob and magnetic catcher shall be provided and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.	Sq.mt	12.64		
10	<b>Back credenza / Storage</b> Providing & fixing back credenza 18" deep ( top surface 18" to 24" as per site) & 36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer 4" high, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.	Sq.mt	4.11		
11	<b>False Ceiling With Steps. - Gypsum Board</b> Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp- board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade. The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps/ Vertical bands shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools,	Sq.mt	52.00		

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
12	<p><b>False Ceiling - (Mineral Fibre)</b>  Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 &amp; micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters &amp; screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.  Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner &amp; finishing of ceiling in all respect, the work includes provision of trap door if required.</p>	Sq.mt	40.00		
13	<p><b>Teak Ply Ceiling</b>  Providing and fixing 4mm thk. teak veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes esprit polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.</p>	Sq.mt	8.00		
14	<p><b>FULL HEIGHT PARTITIONS WITH ETCHING ON GLASSES- SOLID/PARTIALLY GLAZED:</b>  Providing and fixing partition made of 50mm x 38mm x 16 gauge aluminum extruded sections @ 2'0" to 2'6" c/c vertically &amp; horizontally. The bottom member shall be aluminum extruded sections of size 65mm X 38mm X 16 gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as RCC slab with rawl plugs/ steel lugs of Make: HILTI/ FISCHER. The frame work to be clad with 12mm thick BWP ply and 1mm thick Laminate of approved color/ shade as per pattern on both sides upto 3'0" height and above 7'0" height and 5mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1mm thick laminate of approved color/ shade. Work also includes providing and fixing of door as per drawing and specifications. All job to be done to Architect's satisfaction/ as per bank direction. Measurements to be taken upto false ceiling level &amp; Payments shall be made only for exposed surfaces &amp; actual measurement at site, no payment shall be made above false ceiling. Make: GREENLAM/ ARCHIDLAM/ SUNMICA (1mm thk Laminates of approved color/ shade by the Architect/Engineer-in-charge)</p>	Sq.mt	12.54		
15	<p><b>LOW HEIGHT PARTITIONS (4' HIGH):</b>  Providing and fixing low height partition made of 50mm x 38mm x 16 gauge aluminum extruded sections @ 16" vertically &amp; horizontally. The bottom member shall be aluminum extruded sections of size 65mm X 38mm X 16 gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level with rawl plugs/ steel lugs of Make: HILTI/ FISCHER. The frame work to be clad with 12mm thick BWP ply and 1mm thick Laminate of approved color/ shade as per pattern on both sides upto 4'-0" height. The skirting shall be finished with 1mm thick laminate of approved color/ shade. The partition shall be closed at top/ exposed edges with 3½" x ¼" teak wood beading which shall be payable as/ item no 18b. All beading shall be spirit polished as/ approved shade by the architect. All job to be done to Architect's satisfaction/ as per bank direction. Make: GREENLAM/ARCHIDLAM /SUNMICA (1mm thk Laminates of approved color/ shade by the Architect/Engineer-in-charge)</p>	Sq.mt	3.81		

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
16	<b>Wall Paneling</b> Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc.				
	i. Panelling with Teak Ply with Spirit Polish (Basic Teak Veneer Rate @ 70/- Sq.ft)	Sq.mt	37.53		
	ii. Panelling with laminate	Sq.mt	40.00		
17	<b>Fixed Glass / Glazing for B.M - Toughened Glass 12.0 mm thk. including frosted film as and where specified.</b> Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grainded, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessary etching film / logo all inclusive, complete	Sq.mt	4.18		
18	<b>Wall Connecting Profile</b> Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass., make: DORMA/OZONE	Rmt	1.52		
19	<b>Toughened Glass Doors</b> Providing & Fixing Openable 12mm thk. Toughened Glass Door, held with Patch fitting (i.e. bottom & top patch, L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make, fixed in position as per manufacturers guidelines. The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in the glass panel to facilitate the fixing of Patch fitting & Handle. The job shall be complete in all respects, including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.	Sq.mt	6.50		
20	<b>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop &amp; Suggestion Box</b> Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and 3/4" x 1/4" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	Nos.	1.00		
21	<b>FLUSH DOOR</b>				
a)	Providing and Fixing Factory manufactured flush doors along with 2-1/2" x 5" teak wood door frames fixed in position iron hinges,tower bolts (2 no),Stopper,8"SS Handle ( 2 No),etc (excluding the cost of any fitting other than specified above but including labour for fixing the same in position.Commercial with elm or gurjan facing on both sides with 1mm approved shade laminate on both sides and lipped edges 35mm thick	Sq.mt	9.10		
22	<b>Door Closer</b> - Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	Nos	4.00		
23	<b>Night latch</b> in cash cabin door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.	Nos.	2.00		

S. N.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
24	<b>PAINT (PLASTIC EMULSION)</b> Providing & applying PLASTIC EMULSION (ASIAN/ ICI/ NEROLAC) on walls, columns & ceilings. The rate shall include scrapping, leveling & preparing the surface with JK/ ASIAN/ BIRLA WHITE putty. Then, Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided	Sq.mt	450		
25	<b>Painting Work – Texture Paint</b> Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.	Sq.mt	90.00		
26	<b>ENAMEL PAINT</b> Providing and applying Black colour enamel paint mixed with termite treatment medicine of (BAYER / ALDERIN or equivalent make) finish of approved shade & make as per bank specification and architects instructions. Paint the area behind paneling, furniture such as tables, Credenza, storage etc.	Sq.mt	100.00		
27	<b>Paneling With Aluminium Composite Panels (With Aluminium Frames)</b> Supplying & fixing 3mm thick Aluminum component sheet of approved make and shade including making of ground of (1" X 2") aluminum hollow section as per design, with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum component sheet should be of virgin grade and having aluminum profile thickness of 0.25mm on both sides of the core. The rate is inclusive of all fixtures and fittings (with sealant) for a proper finish. The work includes front-face shutter boxing complete. the rate includes all required shuttering, scaffolding, labor, material, and complete.	Sq.mt	30.00		
27	<b>Laminated Wooden Flooring:</b> Providing and fixing of 12mm thick GREENLAM/PERGO/VISTA Laminated wooden flooring (Premium Shades), classification of use 31/23 with a surface abrasion resistance of class AC3 (average 3000 cycles) impact resistance of 7.7 mm, resistance to cigarette burn with a rating of 4 (En438-2:05) swelling after 24 hrs in water of 8.22%, modulus of rupture of 53.3 newton/mm2 internal bond 1.78 newton/mm2, surface soundness 2.62 newton mm2 (EN 13329:2000)with a 0.2 mm thick wear layer on top of a high Density fiber substrate core (density ~ 948.3 kgm/m3 of plank size 1206mmx193mmx8mm having locking arrangement (lock strength> 1100 lbs/ft) with an underlayment made of natural colour foam, with accessories like end profile, Transition profile, reducer, etc. complete. The Profiles	Sq.mt	15.00		
28	<b>Laminated Wooden Skirting:</b> Providing and fixing Greenlam Laminated wooden flooring in skirting etc. Classification of use 31/23 with a surface abrasion resistance of class AC3 (average 3000 cycles) impact resistance of 7.7 mm, resistance to cigarette burn with a rating of 4(En438- 2:05) swelling after 24 hrs in water of 8.22%, modulus of rupture of 53.3 newton/mm2internal bond 1.78 newton/mm2, surface soundness 2.62 newton mm2 (EN-13329:2000) with a 0.2 mm thick wear layer on top of a high-Density fiber substrate core (density ~ 948.3 kg/m3 of plank size 18 x 18 x 2400mm having locking arrangement (lock strength > 1100 lbs/ft) with an underlayment made of natural colour foam, with accessories like end profile, Transition profile, reducer, etc. complete the profiles are 100% matching.	Sq.mt	5.00		
	<b>TOTAL FOR INTERIOR WORKS PART1</b>				
	<b>DISCOUNTS IF ANY</b>				
	<b>GRAND TOTAL FOR INTERIOR WORKS PART 1</b>				

**PRICE BID FOR CIVIL/ RENOVATION WORKS AT STATE BANK OF INDIA BRANCH AT KEYLONG (HP)**

**(PART -2)**

S. N.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
1	<b>VITRIFIED TILE FLOORING</b>				

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	Providing & fixing vitrified tiles of size 800x800 mm of approved make in flooring laid in any pattern as specified over base of 20 mm thick cement coarse sand mortar 1:3, and jointed with white cement slurry mixed with pigment to match the shade to tiles. The tiles shall be of premium quality double charged (first quality) of reputed manufacture i.e. JOHNSON/NITCO/KAJARIA/NIRO GRANITE. The work also includes dismantling of existing floor/wall tiles or stone & removal of malba and disposal of the same to Dumping Yard.	Sq.mt	85		
<b>2</b>	<b>VITRIFIED TILE DADO &amp; FLOORING IN TOILETS</b>				
	Providing and laying 1st quality Vitrified glazed/matt finish tiles 300mmx 600mm (as specified in Dado (thickness to be specified by the manufacturer approx. 9mm) Water absorption of tiles shall be less than 0.5% and flexural strength (Modulus of Rupture) shall be more than 35 N/Sq mm. on 20 mm thick cement mortar 1:4(1 cement: 4 coarse) sand), including grouting the joints with white cement and matching pigments etc., complete. Approved makes: NITCO, JOHNSON, AGL, KAJARIA. Basic rate of tile: Rs 80/-per Sq.ft (Note: Work Incl. Dismantling of existing tiles and disposal of material to dumping yard.)	Sq.mt	70		
<b>3</b>	<b>GRANITE FLOORING</b>				
	Providing, Laying & fixing of granite stone <i>Lappato finish</i> (Grey shade) 15mm to 18mm thick in flooring/skirting treads & risers of steps, laid in any pattern as specified over base of 20mm thick cement slurry mixed with pigment to match the shade of granite stone. The work also includes dismantling of existing floor/wall tiles or stone from existing floor/wall/ staircase tread/ risers & removal of malba and disposal of the same to Dumping Yard.	Sq.mt	2.5		
<b>4</b>	<b>GRANITE NOSING</b>				
	Providing & fixing 1 1/2" thk. Double Granite molding (full round) as nosing on steps including polishing complete in all respects as/ drawing to the satisfaction of the Bank Engg./Architect.	Rmt	3		
<b>5</b>	<b>FLOORING IN THE CORRIDOR WITH ENDURA TILES</b> Providing and laying with Endura tiles (300 mm x 300 mm) thickness 12 mm rate inclusive of dismantling old flooring and preparing new base (30 mm thick).	Sq.mt	30.00		
<b>6</b>	<b>CIVIL WORKS</b>				
i.	Demolishing brick work manually/by mechanical means including disposal of material away from site. <b>PLEASE VISIT THE CITY FOR DUMPING YARD</b>	Job	1		
ii.	11.43 Cm thick Brick wall with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in superstructure above plinth level laid in 1:4 cement sand mortar in super-structure. 8 mm steel bar should be used after every 3rd course. The rate shall be inclusive of any scaffolding required, curing etc, complete.	Sq.mt	20.5		
iii.	22.86 Cm thick Brick wall with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in superstructure above plinth level laid in 1:4 cement sand mortar in super-structure. The rate shall be inclusive of any scaffolding required, curing etc, complete.	Sq.mt	2.5		
vi	Providing and laying in position PCC 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate) upto any height including dismantling of old floor, compacting and curing. The work shall be complete in all respects to the satisfaction of the Architect and Bank Engineer.	Cu.mt	2		
v	Providing and Applying 12 mm Cement Plaster in mix 1:6 (1 cement: 6 fine sand) on Brick Work complete in all respects.	Sq.mt	75		
vi	Dismantling of Conc. Slab upto 150mm thk. & removal of malba and disposal of the same away from site	Sq.mt	5		
viii.	Casting RCC 230mm x 230mm RCC lintel beam /counter slab comprising of 12mm dia steel bars (4 NOS.) with 8mm dia stirrups in 1:2:4 cement concrete. The work includes shuttering/framework/curing and floor screed complete in all respects to the satisfaction of the Architect and Bank Engineer.	Cu.mt	0.67		

S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
x.	Supplying & applying waterproofing treatment with 'Polymer Modified Cementitious Coating (Brush Bond of Fosroc/BASF/SIKA make or equivalent) including base preparation, coating with compatible primer applicable on floor & wall, where and as specified by the Architect and testing the same for performance as required. The treatment to be continued 300mm into the wall.	Sq.mt	8		
xi.	Dismantling G.I. pipes (internal & external work) with removal of all CP fittings including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge. <b>Please visit the site for inspection.</b>	Job	1		
xii.	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes also dismantling of flushing cistern of all types (C.I./ PVC/vitreous China) with removal of all chinaware fitting & lead at site within 50 meter lead as per direction of Engineer-in-charge. <b>Please visit the site for inspection.</b>	Job	1		
7	<b>RENOVATION OF TOILETS</b>				
i	WALL HUNG WC WITH UF soft close seat cover, hinges, accessories set, SIZE:670X390X760 MM NAME CLAIR/CALIBRE (Make: CERA) equivalent of HINDWARE/KOHLER/ JAQUAR	No's	3		
ii	HAND SHOWER (HEALTH FAUCET) with 8mm dia 1.2 meter long flexible tube and wall hook ALD-CHR-573 (Make: JAQUAR) equivalent of HINDWARE/KOHLER/CERA	No's	3		
iii.	Providing and fixing Wall Hung Integrated Basin ARS-WHT-39803 JAQUAR MAKE OR KOHLER/HINDWARE/CERA	No's	3		
iv	Valentina single lever basin mixture for wash basin with base flanges (F1013451 CERA ) Make JAQUAR OR KOHLER/ HINDWARE/ CERA	No's	3		
v	WASTE COUPLE 32mm HALF THREAD ALD-CHR-709 (Make: JAQUAR) equivalent of HINDWARE/KOHLER	No's	3		
vi	C.P Bottle Trap " JAQUAR make" Code: ALD 769 MAKES CERA	No's	3		
vii	Urinal with fixing Accessories Set Size: 3 x 315 x 620mm CARYS/CHRYS make: CERA or equivalent of HINDWARE/KOHLER/JAQUAR.	No's	1		
viii.	Angular stop cock with wall flange (Make: JAQUAR) equivalent of HINDWARE/KOHLER/CERA	No's	14		
ix	TOILET PAPER HOLDER (Make: JAQUAR ARTIZE QUA 61753) equivalent of HINDWARE/KOHLAR	No's	3		
x	PAPER TOWEL Dispensers (Make: JAQUAR DT0106CS) equivalent of HINDWARE/KOHLAR	No's	3		
xi	SOAP DISPENSER - (Make: JAQUAR AKP 35735P) equivalent of	No's	3		
xii.	Providing & fixing CP Jali, complete in all respects.	each	7		
xiii	Providing & fixing 1/2" and 3/4" CPVC pipes (make: KITEC/ VECTUS/SUPEREME/DIPLAST) OR equivalent for distribution in toilets including chase cutting, chase filling, proper insulation for pipes. The rate shall include all accessories like tees, unions, elbows, bends etc. required to make the system operational and complete <b>Please visit the site for inspection.</b>	Rmt	75		
xiv	Providing & fixing A TYPE PVC pipes of supreme/prince make or equivalent in position of required size and length with special fittings, traps, bends, y's, floor & nahani traps etc. Including chemical sealed joints as required at site making necessary connections upto manhole or for WC & waste water lines, chambers to be constructed wherever necessary, unused lines for WC & waste water to be removed, the rate shall include all incidental work, cutting & making good walls & floors etc. Complete. <b>Please visit the site for inspection.</b>	No's	8		



S. N	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
xv	Providing and fixing in position best indian make bevelled edge 5.5mm thick mirror mounted on asbestos sheet ground fixed in position by means of 4.no Chromium plated brass screws & washers over rubber washers & rawl plug embedded in the wall or Chromium plated brass clamps with c.p. brass screws (as required by the Architect/Engineer-In-Charge) complete including cutting & making good walls ect. Size (600x910mm)	Sq.mt	5		
8	<b>EXTERIOR PAINT</b> Providing & applying a coat of EXTERIOR PAINT (ASIAN- APEX) on wall, columns & ceilings. The rate shall include scrapping, leveling & preparing the surface with JK/ ASIAN/ BIRLA WHITE putty. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided. Note: (i) The rate shall be inclusive of cost of scaffolding wherever required. (ii) And all the workers at site shall have health insurance done by the contractor. (iii) Measurement of only exterior visible surfaces will be considered for payment purposes. Please visit the site for inspection.	Sq.mt	250		
	<b>TOTAL AMOUNT PART 2</b>				
	<b>DISCOUNTS IF ANY</b>				
	<b>GRAND TOTAL FOR CIVIL WORKS PART 2</b>				
	<b>GRAND TOTAL PART 1+ PART 2</b>				
	<b>GST Extra as/ applicable</b>				

IN WORDS (RS)

SIGNATURE OF CONTRACTOR  
NAME OF CONTRACTOR  
ADDRESS OF CONTRACTOR