

PRICE BID FOR ROOF TRUSS WORK AT SBILD KITCHEN IN THE FIRST FLOOR OF SBILD THIRUVANANTHAPURAM

No	Description of work	Unit	Qty	Rate (excl. GST)	Amount Rs.)
1	Dismantling of existing GI sheet and fixing 0.45 mm GI trafford sheet of matt finish and of approved make and shade fixed to the purlins with hot dipped galvanized self drilling fastners with integral EPDM washers and silicone. The rate shall also be including providing 2"x2" GI tube purlins at a distance of 3' both ways in between the existing C channel rafters and painting the whole structure including the existing rafters with one coat epoxy primer and 2 coat enamel paint of approved make and shade etc complete. Rate shall also include necessary scaffolding cost, conveyance of all materials and labour charges etc complter as per specifications. Measurement will be taken at slopping length.	Sq.M.	284		
2	Supplying, laying and jointing 160 mm dia unplasticised Rigid P V C rain water pipes 15 gauge of approved quality and ISI marks and specials such as tees, bends, elbows, checknuts etc with clamps including cutting and making good the walls, floors, scaffolding etc complete as per the direction of Engineer-in-charge	RM	80		
Total Amount					
GST extra					