

<b>Bill of Quantities FOR INTERIOR WORKS –IN THE NEW PREMISES OF RF ROADTADIPATRI BRANCH, ANTAPURAM DIST, AP.</b>					
Banks Uniform Layout Policy Colour Scheme to be followed.					
All contractors are requested to understand the uniform layout policy colour scheme and the specifications of the SBI before quoting the rates. They are also advised to see and understand some branches where Interior already done and approved by the					
Item No	Description	QTY	UNIT	Rate	Amount
<b>1</b>	<b>FULL HEIGHT PARTLY GLAZED PARTITIONS:</b>				
	Providing & fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs / tracks or channel at doors and other openings. B) 11 mm MDF plywood of banks approved branch and variant fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on both sides (Banks uniform colour layout colour scheme) up to false ceiling level. D) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm teak wood jamb and 12 X 12 mm teak wood beading. E) All teak wood members to have melamine polish finish. Doors in partitions wherever required to be provided with 35 mm thick solid core ISI approved allround teak wood lipping, allround fixed in a concealed door frame of best quality teak wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout colour scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb allround the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make & quality, melamine spray polish finish to all teak wood members etc. complete as directed. F)Door Closer of heavy duty 'Godrej' make heavy duty or equivalent to be fixed. Length X height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an to termite solution before use in the work. Old and existing partitions to be dismantled and stacked at site and charges for the same to be included in the quoted rate.				
		<b>75.00</b>	SMT		
<b>2</b>	<b>FULL HEIGHT PARTLY GLAZED PARTITIONS:( BM cabin)</b>				
	SAME SPECIFATIONS AS ABOVE BUT IN SIDE THE PARTITION FINIHED WITH 4MM THCK TEAK VENEERED PLY INSTEAD OF 1MIM LAMINATE , OTHER SPECIFICATIONS REMAIN AS ABOVE.				
		<b>33.00</b>	SMT		
<b>3</b>	<b>LOW HEIGHT PARTITIONS</b>				

<p>Providing &amp; fixing metal stud low height partitions with following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 11 mm plywood MDF of banks approved brand and variant grade with 1mm laminate (as per banks uniform colour scheme) on both sides. d) 12mm glass of 12"height on top of low height partition (total height to be 4'6" to 5') with necessary CP brass "D" brackets and etching work wherever required also to be fixed. Anti termite solution to be sprayed before using the ply wood in the work. A pin up board of size about of 2' x18" vertical or vice versa to be made on low hot partician one sode (nearer to sitting stations), with soft board and Lenin cloth of superior quality with elegant beading around, one for each work station. Wicket Gate consisting of same construction of low height partitions of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. Each wicket gate must be provided with necessary hardware of cp brass aldrop, tower bolt, autom atic mortice latch of banks approved make and model . The edges shall be finished with teak wood beading polished. Its cost to be included in the quoted rate of low ht partition. Dismantling of old partitons (low or any height) to be included in the quoted rate.</p>				
	35.00	SMT		
<p><b>4 FULL HEIGHT PARTITIONS WITH BISON PANELS BOTH SIDES(UPS- first floor)</b></p>				
<p>Providing &amp; fixing metal stud low height partitions with following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 11 mm BISON wood panels of banks approved brand and variant grade with 1mm laminate (as per banks uniform colour scheme) on both sides. c) bison wood beading to shape d) 12mm glass of 12"height on top of low height partition (total height to be 4'6" to 5') with necessary CP brass "D" brackets and etching work wherever required also to be fixed. Anti termite solution to be sprayed before using the ply wood in the work. Wicket Gate consisting of same construction of low height partitions of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. Each wicket gate must be provided with necessary hardware of cap brass aldrop, tower bolt, autom atic mortice latch of banks approved make and model . The edges shall be finished with bison wood beading polished. Its cost to be included in the quoted rate of low ht partition. Dismantling of old partitons (low or any height) to be included in the quoted rate. o wo shouldbeued under this item</p>				
	30.00	SMT		
<p><b>5 VOUCHER WRITING TABLE</b></p>				
<p><u>Voucher Writing Table:-</u> Supplying &amp; fixing cheque writing table as per the standard design.(1) Floor mounter type-circular type with 12mm toughened glass on top and 8 pigeon hole racks, standing type, top dia 90cm, ht 36"-42" white/blue laminated over 18mm ply work as per banks standard design. (2) Wall mounted type- 3' long, 1' width 6 nos of vouches racks, ht 36-42" ht. top with 12mm toughened glass as per banks standards with white and blue laminated over 18mm ply wood as per banks standards.(please quote average rate of circular and rectangular type. Ply wood to be MDF of banks approved brand and variant.(GROND FLOR: 1- circular, 1- wall standing, FIRST</p>				
	2.00	EACH		
<p><b>6 ROLLER BLINDS VISTA MAKE SCREEEN WHITE EP 001 SHADE )</b></p>				

	Roller Blinds:- Supplying & fixing in position of Roller Blinds of "Vista" shade model- screen white EP 001 model etc. complete. Window opening sizes shall be measured and the blind must extend up to 3" beyond the edges of opening on all the four sides. SBI LOGO AS PER BANKS STANDARD SPECIFICATION TO BE PRINTED AS DIRECT.				
		15.00	SMT		
<b>7</b>	<b>SUGGESTION BOX</b>				
	Suggestion box as per banks standard size, model in blue/ green laminate with locking arrangement.				
		1.00	EACH		
<b>8</b>	<b>WALL PANELLING</b>				
	Wall Panelling with ply and 1mm laminate: Providing & fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 11 mm MDF panels fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body, in designs) up to false ceiling level. e) All teak wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy colour scheme to be followed. Aspecail panel of size about 8' long and 5' height to be made consisting of allround boarder 6" width and 3" projected from wall blue laminated, internal panel area plane while laminated, The extra costs of the same to be added in the quoted rate. Wall panelling should not be done behind the side units, back units, sides of tables if leaning against walls, since will not be paid.				
		150.00	SMT		
<b>9</b>	<b>WALL PANELLING WITH 4mm THICK TEAK VENERED PLY)</b>				
	B) WALL PANELLING ( BM CABIN) with same construction as above but with 4mm one side veneered teak ply( basic rate Rs 100/ sft) on 11 mm thick MDF panels , laminate as mentioned in wall panelling work above.				
		25.00	SMT		
<b>10</b>	<b><u>B) COLUMN PANELLING</u></b>				
	Column Panelling with frame work, 11mm thick bison panels , laminate as mentioned in wall panelling work above. Design shall be as directed by the bank. Flexi ply to be used for circular panelling work for circular columns.				
		20.00	SMT		
<b>11</b>	<b>STORAGE UNITS</b>				

<p>Storage Units: A) Providing, making and placing in position low height storage units up to 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDFOf banks approved brand and variant ply covered with (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminate of half white shade. <b>STORAGES SHOULD NOT BE FIXED TO WALLS/FLOORS AND TO BE PLACEABLE NY WHERE ELS SO, LENGTH TO BE DINE NOT EXCEEDING 5' EACH.</b></p>				
	20.00	SMT		
<p><b>12 Storage Units: WITH 4MM OST PLY(BM CABIN)</b></p>				
<p><u>Storage Units: WITH 4MM OST PLY(BM CABIN)</u> A) Providing, making and placing in position low height storage units up to 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDFOf banks approved brand and variant ply covered with 4 MM OST NATURAL TEAK VENEERD PLY at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminate</p>				
	5.00	SMT		
<p><b>13 SINGLE WINDOW COUNTERS</b></p>				

<p><u>Single Window Counters:</u> Providing &amp; fixing 5ft-5 1/2 ft. wide Single Window Counters with table top to be made of 25 mm MDF + 1 mm lamination finish as per the layout and as per the standard design with, drawers, ready made keyboard tray and ready made MS CPU stand of heavy duty / high quality in ivory colour. The front glass shall be 12 mm thick up to 5 ft. height from the floor level and a 15" wide horizontal g side unit consist of 4' long, 16" wide and 30" height made out of 18mm ply and external surfaces 1mm thick with shelve and drawer arrangement along with necessary hardware to be done. Glass of same thickness shall be provided at 3'-6" level. The rate to include for back doors with 'Godrej' night latch. Special locks to be fixed which can opened with single key.Cash counter will have Dural make cash closing door(booking counter door closure). Side unit consisting of 4' long, width 16" and height 30" with top two drawers and bottom shelf arrangement to be fixed for each counter. Table and side unit all internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. (Low height partitions shall be paid for separately). side unit, table should be separatable and laminated all over including leaning side of the partitions. A vertical glass 12mm toughened should be fixed as per the design between the counters on front with suitable beadings/supporting structures. The counters front curved part ply to be done using flexible plywood. One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long. Banks Uniform lay out policy scheme to be implemented strictly with out any deviation hence the contractors are requested to understand in detail before quoting the rate.(clear inside to side the length of counter shall be measured). Complete structure to be done with 18/19 mm thick MDF of banks approved brand and variant. Changes for dismantling the old counters to be included in the quoted rate.</p>				
	<b>6.00</b>	RMT		

14	<p>BRANCH MANAGER TABLE (Size 1800 X 900 X 750 mm, Side table 1200X450X750mm): Providing, making &amp; placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and <b>4 MM OST OF NATURAL TEAK VENEERED PLY</b>, (basic rate shall be Rs 100-120 / sft plus gst shall be selected) all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) Side table made with 18 mm MDF of banks approved brand and exposed surfaces finished with <b>4 MM OST OF NATURAL TEAK VENEERED PLY</b> and exposed members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) 6mm thick lacquered glass fixed with cp studs for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.</p>				
		1.00	EACH		
15	<p><b>OFFICER TABLESWIHT SIDE UNITS</b></p>				
	<p>OTHER TABLES (Size 1200 X 750 X 750 mm, with out Side table): Providing, making &amp; placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and covered with b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) No side table is required. All tables shall have necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) With other parts of the cabin of approved shade and brand. 6mm thick lacquered glass for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.</p>				
		3.00	EACH		
16	<p><b>SERVICE TABLES FOR HEAVY CASH, CROSS SELING, MESSENGER) WITH OUT SIDE UNIT BUT WITH CORIAN TOP; 1200 MM X 750 MM X750 MM</b></p>				

<p>OTHER TABLES (Size 1200 X 750 X 750 mm, with out Side table):          Providing, making &amp; placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and. b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) No side table is required. All tables shall have necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. With other parts of the cabin of approved shade and brand. 6mm thick lacquered glass for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased</p>				
	2.00	SMT		
<p><b>17 PLAIN FALSE CEILING:</b></p>				
<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm La Gyp / Boral Plaster Boards fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cut-outs for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. All legroom internal area and drawer internal area to be finished with 0.8 mm thick half white laminate after spraying anti termite solutions. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materials.</p>				
	60.00	SMT		
<p><b>18 GRID TYPE FALSE CEILING</b></p>				

	<u>SILHOUTE Grid False Ceiling</u> :- Providing and fixing in true horizontal level false ceiling grid system (SILHOUTE) of Armstrong World Industries/ Daikin / CEPro etc. The suspension system shall be silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess colour, black or white revealed. Silhouette main runners and cross tees to have mitered ends with “birds mouth “ notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier micro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materials.				
		<b>165.00</b>	SMT		
<b>19</b>	<u>Table for 'Grahak &amp; Tech. Mitra'</u> :- Providing table for grahak Mitra in curve shape as per the standards. Size 1500X680X750 with a drawer unit.				
		<b>1.00</b>	EACH		
<b>20</b>	Buy back of old furniture in the existing premises: including removing and stacking out side as advised by the branch. While removing and stacking at site, no damages to be caused to the walls, floors and furniture. Removal should be done in phased manner as advised by the branch.				
		<b>-1.00</b>	LOT		
<b>21</b>	Providing and fixing 3.5 / 4mm MDF boards and 1mm lamination on old furniture such as tables, low ht / full hot partitions, side units or any such furniture items of the works including modification and removing from old premises and refixing in the new premises etc complete with set of new beading and hardware etc. complete. to renew any furniture if found good I condition instead of disposing off				
		<b>15.00</b>	SMT		
<b>22</b>	PROVIDING AND FIXING 12MM THICK TOUGHENED GLASS FOR MAIN ENTRENCE DOORS AND ATM AS PER BANKS STANDARD SPECIFICATIONS				
		<b>15.00</b>	SMT		
<b>23</b>	ACP WORK WITH 3MM THICK AND FRAME WORK				



