

Date:

SBI, R F ROAD BRANCH, TADIPATRI
ESTIMATE FOR AIR CONDITIONING WORKS

Sl.No.	Description	UOM	Qty.	Rate (Rs.)
Part A:				
1	Supply of inverter type Cassette type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity.			
	3.0 TR Capacity	Set	5	
2	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Minimum 3 star rating			
	1.5 TR capacity	Set	4	
	Sub Total Part A			
Part B:				
1	Installation, testing and commissioning of Cassette and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.			
A	3.0 TR capacity Cassette type	Set	5	
B	1.5 TR capacity HWM type	Set	4	
2	Supply and erection of suitable size of MS stand for outdoor units	Set	9	
3	Supply, installation, testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and outdoor air cooled condensers of the following sizes			
A	Suction line & liquid line for Cassette units	RM	75	
B	Suction line & liquid line for hi-wall mounted units	RM	30	
4	Drain line from indoor to outdoor machines as per standards	RM	120	
5	Supply, laying, testing and commissioning of flexible cable of suitable size for cassette units	RM	100	
6	Supply, laying, testing and commissioning of flexible cable of suitable size for HWM units	RM	50	
7	Supply, installation, testing and commissioning of 24 HR duty timer for cyclic operation of Acs at ATM	Nos.	1	
	Sub Total Part B			
	Grand Total (Part A + Part B)			

