

Tender Id: LHO/CHA/AKB/2024/08/01  
Date: 07.08.2024



The Assistant General Manager,  
(Premises &  
Estates) State  
Bank of India,  
Local Head Office, Sector 17,  
CHANDIGARH

## **PART-B: PRICE BID**

**TENDER FOR PROPOSED EXTERNAL PAINTING OF  
SBILD JAMMU AT BANTALAB (J&K)  
(OFFLINE TENDER)**

**BOQ FOR EXTERNAL PAINTING OF SBILD JAMMU AT BANTALAB**  
**(J&K)**

<b>S No.</b>	<b>ITEM</b>	<b>UNIT</b>	<b>QTY</b>	<b>RATE</b>	<b>AMOUNT</b>
1.	<p><b>Painting Work - Distempering (in Basement only)</b> Distempering with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification including preparation, removing base old paint distemper/ whitewash etc. (Two or more coats) <b>Make: Asian or its equivalent in, Nerolec/Berger/JSW.</b> The rate shall include for scaffolding platform making for workmen properly cleaning of the site after completion of the aforementioned work. The contractor is strictly advised to take all the safety measures for labour to carry out the work, etc. all complete as directed by Bank's Engineer.</p>	Sqm	1600.00		
2.	<p>Painting work exterior paint Providing and applying two or more coats of 100% water proof Premium acrylic smooth exterior emulsion paint with silicon additive (Two or more coats applied @ 1.67 ltr/ 10 sqm) after primer (one or more coat) as per the manufacturer specifications/tender part I specification of approved make and shade by using exterior approved quality roller/ painting brush as per site conditions to achieve the desired finish. etc. all complete as required at site as directed by the Bank's Engineer-in- Charge including minimum 7 year warranty. Make: Asian apex ultima or its equivalent in <b>Nerolec/Berger/JSW.</b> The rate shall include for scaffolding, platform making for workmen. properly cleaning of the site after completion of the aforementioned work The contractor is strictly advised to take all the safety measure for labour to carry out the work, etc. all complete as directed by Bank's Engineer.</p>	Sqm	2700.00		

3	<b>Enamel Paint</b> on doors/grills/gates Satin Finish Enamel Painting the Existing Grills, railing, exterior windows/ external members ect with two coats of Satin finish Enamel paint including Removing/scraping/cleaning the existing metallic/wooden surface, prepare even surface by using putty up to required level. Providing and applying a base coat approved quality primer (wooden primer or metal primer as the case may be) and two or more coats of 1st quality synthetic enamel paint of approved make and shade to steel and wood work, viz. grills, gates, weld-mesh, doors, windows etc. (exterior surfaces only) all as per manufacturers specifications (approved brands mentioned in list of approved materials). The rate shall include for scaffolding, platform making for workmen. properly cleaning of the site after completion of the aforementioned work. The contractor is strictly advised to take all the safety measure for labour to carry out the work, etc. all complete as Idirected by Bank's Engineer. Make:	Sqm	40		
	TOTAL				
	Discount if Any				
	GRAND TOTAL				
				Say	
GST (as applicable) shall be paid extra by the bank to the Contractor					
FINAL BILL WILL BE PAID AS PER ACTUAL MEASURED AREA ON SITE					