

INTERIOR WORK AT SME MORENA BRANCH

S. No	ITEMS	QTY	UNIT	ESTIMATE	
				RATE	AMOUNT
1	Gypsum Board false Ceiling: Providing, fabrication and fixing in position of false ceiling at a height of 8 to 10'-0" from floor (or the height will be decided on the spot as per site conditions) by fixing 12 mm Th. Gypsum Board sheets on frame work of GI sheet section. The main runners of 22 gauge GI sheet and cross runners of 24 gauge GI sheet must be framed to form a mesh of 2'0"x2'0" c/c. The Gypsum Board must be fixed to the GI frame and joint to be properly filled in with POP paste and paper tape to get a leveled smooth ceiling. Recessing of the Gypsum Board for light fixtures must be done along with extra frame work of GI sheet section to hold the concealed light fixtures etc. including cost of two or more coats to give an even shade of plastic paint on ceiling complete with designer ceiling (with part ply and laminate) as required and directed by the Bank.	880	Sqft	0	0.00
2	Armstrong/ Everest Ceiling/India Gypsum mineral fibre tiles : Providing fabricating and fixing of false ceiling at all height as directed of 600 mmx 600 mmx 15 mm Armstrong/ Everest mineral fiber tegular ceiling tiles of type classic lite RH- 99 laid on Armstrong/ Everest prelude XL exposed grid system with 9 mm wide T section flanges color white. The framework comprises of main runner spaced at 1200 mm centre. Hanger (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450 from the adjacent wall. Flush fitting 1200 mm long cross tees (with double stitching)to be interlocked between main runner at 600mm center from 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently 600mm x 600 mm modules to be formed by fitting 600 mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Armstrong/ Everest wall angle secured to walls at 450 mm maximum centers.	1320	Sqft	0	0.00

3	<p>Providing and fabrication of 8'-0" or as per site requirement SWO Counters with counter body of 18mm, 12mm & 6mm thk plywood. The counter top (the working top to be of 19mm thk block board 3'0" wide working top must be at 2'6"ht from the floor. A ready made metallic keyboard tray EBCO make and a drawer unit having 3nos of drawers provided with Godrej/Clik multi (automatic) lock. Top drawer to have cash separation arrangement. A round PVC cable crossing socket must be fixed on the table top for power/data cable crossing. A foot rest made of 19mm thk block board (box type) to be fixed and a ready made CPU carrier/ Trolley with wheels to be provided. All the exposed surfaces to be covered with 1 mm thick laminate. All inside/ hidden surfaces/ drawers must be finished with 0.8 mm thick white laminate. All the corners/ edges of plywood and block board to be protected with 6mm thick teak wood plain beads. The counter must be provided coloured (approved blue) 1mm thick laminate at front face of counter with cuts & slides cost of all Hings, Hardware, Locks, Handles & fastners etc. er requirement. Complete as per bank's requirements.</p>	1	No	0	0.00
4	<p>Glazing in front of counter: Providing, fabrication and fixing of 12 mm thick plan glass in the branch frontage/in front of single window counters / fixed glazing for wall opening. The glass may have a service window if required. The top edge and the edges of the service window to be machine polished. The glass must be fixed in position with D-brackets/ wooden beading with melamine polish as directed. Rate inclusive of providing and fixing frosted film as per bank's requirements.</p>	50	Sqft	0	0.00
5	<p>Full Hegt Partly Glazed Partition: Providing and fixing at site fully/partely glazed partition strictly as per the design & drawing to be made up of 2"x2" Aluminum hollow section (medium weight), finished with 9mm thick MDF board (Bison, green, Century or equivalent brand) on both side finished with 1mm thick approved shade of lamination on all the sides as per the drawing with provision of fixing of large size glass. The float glass should be 8mm thick with approved etching pattern. The glass is to be fixed to main frame with 1"x1", 2nd class TW beading. All exposed wooden members or beading to have 3 coats of melamine polish. Glass to be fixed in partition above 3' and up to door height complete as per drawing and direction. The frame should be fixed in slab but ply will be fixed up to false celing height.(measurement taken upto finish level)</p>	270	Sqft	0	0.00

6	<p>LOW HEIGHT PARTITION Do as above item but of as per given design & 4'-6" high 12 mm plan glass (having it top edge machine polished) to be fixed over the flush partition. Necessary provision shall be made for fixing. No separate measurement shall be made for glass portion.</p>	200	Sqft	0	0.00
7	<p>Providing and installation and fixing 12 mm thick Toughened Glass (Glass Make:- Saint Gobain) partitions upto 3.00 M with proper machine edge finish in angle & fixed in the flooring with Aluminium 'U' channel & flushed with the ceiling. Glass panels to be formed as per approved modules 12 mm thick clear toughened glass edge polished and accurate designed holes to be installed by means of steel angle or spider fittings of an approved make Saint Gobain / Asahi or equivalent. The structural Glass walls system shall be complete with proper water tight silicon sealants /gaskets. M.S Brackets to support the structure system shall be hot dipped galvanized and slots in the brackets to be pre drilled not flame cut. All bolts,nuts,washers shall be 300 series non magnetic stainless steel and lock washers to be provided at all bolting connections. All anchor fasteners shall be of Hilti/Fisher make. All structural silicone shall be of Dow Corning make. The Rates includes all material, Labour, Wastages, Cost of scaffoldingincludes cost of all Hings, Hardware, Locks, Handles & fastners e</p>	50	Sqft	0	0.00
8	<p>Design,Providing, installation and fixing 12 mm thick Toughened Glass (Glass Make:- Saint Gobain) DOORS upto 2.10 M with all as per required arrangement & proper machine edge finish in angle & fixed in the flooring side with Aluminium 'U' channel . Glass panels to be formed as per approved modules 12 mm thick clear toughened glass edge polished and accurate designed holes to be installed by means of steel fittings of an approved make Saint Gobain / Asahi or equivalent. Including Floor spring (make:- Dorma or equivalent), Lock Godrej or approved make, Door Handle both side (SS make), all works including labour, wastages, cost of scaffolding, finishing etc. complete.</p>	35	Sqft	0	0.00
9	<p>Wicket gate: Providing, fabrication and fixing of flush type wicket gate made exactly as item no. 6 above but without glass. Including cost of brass hinges, tower bolts, self locking arrangement (Godrej) and handles, as directed.</p>	30	Sqft	0	0.00

10	<p>TABLES</p> <p>Providing and fabricating of table with key board tray having table body of 18mm, 12mm & 6mm thk plywood and the drawer sliders. A readymade metallic keyboard tray EBCO make (as and where required) must be fixed under table top. The table top and all other exposed surfaces to be covered with 1.0mm thk laminate. All inside/hidden surfaces to be finished with 0.8 mm thick laminate. All the edges and corners of plywood to be protected with 6mm thick plain teak wood bead. All the exposed teak wood to be finished with 3 coats of melamine polish. Multipurpose lock and handle must be fixed on shutters and drawers.</p>	0		0	0.00
10a	6'x3'0"x2'6" for Branch Manager Table	1	No.	0	0.00
10b	5'X2'3"X2'6" for office's	9	No	0	0.00
10c	4'X2'X2'6" for back office	2	No	0	0.00
11	Providing and fabrication of table for Grahak Mitra with 12mm thick glass top of 300mm wide support with ss stuts, other specification same as above but 4' wide as per approved design and direction on Bank.	1	No	0	0.00
12	Side unit with three drawers including locking arrangements (Godrej) for Officers, SWO & Asstt. 3'3" x 1'3" x 2'6" specification same as item no 10.	11	No	0	0.00
13	Providing, fabrication and fixing of 6mm th. Plywood around the columns as per the drawing with Aluminum 40 x 25mm hollow section (medium weight) to be nailed at 3'0"x2'0"c/c and all the plugs to be cut after levelling them with line dori along the diagonals of the wall, such that the gap between the wall and the ply board is by screwing on the levelled plugs such that the final surface of the ply is smooth and in uniform level. The entire exposed ply to be covered with 1mm thick laminate 4" high skirting of 6mm th. Plywood to be fixed on exposed surfaces and it to be covered with 1mm thick laminate. The top edge of the skirting to be protected with 12mm x 12mm quarter round bead of teak wood. All the teak wood to be finished with melamine polish.	900	Sqft	0	0.00
14	Providing making and fixing of writing platform 4'-0" wide top, made of 18mm plywood. The sloping 12 mm glazed writing top at 3' 9" ht from the floor and pockets for keeping the vouchers on it must be fixed. An open (with shutter) cabinet must be made under the platform to keep dustbins. The writing top and all the external exposed surfaces must be covered with 1mm th. Laminate. All the internal/ hidden surfaces must be finished with 0.8mm thick laminate. Complete in all respect.	1	No.	0	0.00

15	Finishing walls with Plastic emulsion paint of Asian/ Nerolac/ Berger/ ICI to give an even shade three or more coats including putty and finishing the wall surface smooth complete work	2500	Sqft	0	0.00
16	Preparing earlier treated surface by scraping with sand paper, cleaning, repairing cracks/knots if any with putty and applying two coats of synthetic enamel paint to doors/windows grills etc. complete. (Asian paint - Apcolite, Berger paint - Luxol, Goolas, Nerolac paint – Nerolac	50	Sqft	0	0.00
17	Providing and fixing in position Designer Roller Blinds manufactured by VISTA or equivalent, as per choice of Bank/ Architect.	50	Sqft	0	0.00
18	STORAGE CABINETS: Providing & fixing storage cabinets upto required height & 600mm deep as per architects drawings. architects cabinets shall be made of 19mm thick MR Ply with approved laminate on Top and all exposed surfaces. The cabinets shall be 2mtr. High & shall have lockable shutters in the front duly laminated on front face and painted at the back face with superior quality synthetic enamel paint of approved shade & quality it shall have storage shelves at every 35cm gap. For vertical storage of files. All the skeleton work to be done with 19mm thick MR Ply of superior make and the back shall be 8mm thick MR ply of superior make good for pasting laminate. The shutters shall have locking arrangement with superior quality brass mortice lock Godrej or equivalent The shutter shall be fixed on sides of the cabinet with superior quality brass. All the exposed faces shall be same laminated and other faces duly painted with superior quality synthetic enamel paint (Asian, J&N, Dulux or Berger). The cost includes cost of all Hings, Hardware, Locks, Handles & fastners etc.	150	Sqft	0	0.00
19	Supplying, Fabrication and Installation of Dupont Corian of 6mm thk. Applied on table Top, Sides and any where wall, Logo etc. To minimis material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in – Salt (Translucent series), Azure & Diamond Blue.	50	Sqft	0	0.00

20	Providing and fixing 3 mm thick ACP (Aluminium Composite Panel) panelling, aluminum foil thickness to be min. 0.20mm on both side , bright silver shade or by Bank's approval. with Aluminum Hollow section frame of 1.5'x 1' (medium weight) at 2'x2'c/c both ways. ACP to be in full size panels fixed to the frame with 3M or equivalent adhesive. All joints to be filled/ finished with silicone based sealant. The provision for fixing AC units with extra frame to be fixed. (Eurobond, Fujibond, Alcobond, etc. or equivalent) complete work as directed.	200	Sqft	0	0.00
21	Providing and fixing Digital Glass Frosting Film (3M) for frosting as per design in all shapes including curve shapes etc. complete to the satisfaction of Architect/Bank's Engineer.	100	Sqft	0	0.00
22	Providing and Supplying S.S. Dustbins, avg. 1 mm thick & avg. 200 mm dia. mouth tapering bucket type of avg. height 310 mm; as per approved pattern, with all turned, well-formed and moulded edges at the bucket rim. Item to include sample approval from Architect/Bank.	11	No	0	0.00
23	Providing and fixing 35mm thick flush door openable /sliding with 1mm thick laminate on bath side cost shall be inclusive all accessories like ss hinges, mortise handle/lock, latches, stopper, tower bolt etc. complete	105	Sqft	0	0.00
24	MDF Work:			0	
25	a. 12mm HDF in grooved b. HDF shall be fitted over plywood structures on Groove pattern c. Note- include all recommended adhesives, nailing, screwing, edge finishing etc. complete, as and in the manner required for proper and seamless fitting.	150	Sqft	0	0.00
26	chairs for Visitors and Officers, Nylon back support, with breathable mesh to keep you sweat free, adjustable height, Smart Tilting Mechanism with locking feature and Smooth 360 degree Swivel. Seat and Base : 2 inch Thick Foam Cushion Padded Seat for your long hours comfort Pneumatic Hydraulic with 3 inch seat height adjustment Breathable contoured Mesh Back Fabric Chair comes with Sturdy Metal Base for extra strength Lumbar Adjustments : Lumbar adjustments can be pushed upward, down for better supports to the back. Height Suitability : 5 ft to 6 ft Weight Capacity : 105 Kgs Make: Godrej, Geeken, Neelkamal or equivalent	0	No.	0	0.00

27	chairs for AGM Make: Frame Material: Polyamide & GF Nylon Structure with breathable mesh Size: High Back Swivel: 360° swivel Mechanism: Butterfly Gas-lift : Re-engineered class-3 gas lift Base: Nylon wheelbase Castors: White Nylon castors/wheels 3D Adjustable Armrest Height Adjustable PU Lumbar Support Adjustable Headrest Maximum Weight Capacity: Upto 125Kgs Height Suitability: 5ft to 6ft Godrej, Geeken, Neelkamal or equivalent	0	No	0	0.00
28	Table : Color = As directed by Engineer/Branch Manager Coffee Table - Portable Wooden Centre Table with Storage & Open Rack - Sofa Tea Poyee Table for Office (L 101 x B 40 x H 47 cm) Modern Contemporary design with a pre-laminated matte finish 2 top shelf compartments that are open and semi-open 1 bottom shelf compartment that is semi-open with access from the front and back 1 large compartment that is open with access from front and back	2	No	0	0.00
29	Providing & fixing Sofa as per design & approval of the Architect. Standard features expected include, teak wood / S.S.legs with composite frame work of treated teakwood & marine ply, with 40 density PU foam seat & 32 density PU foam back with Arms fully upholstered in Leatherite as per approval of the Architect, complete with all necessary hardware etc. as per design & instructions of the Engineer			0	0.00
30	As specified above Single Seater Sofa chair in composite leather	0	Nos	0	0.00
31	As specified above Two Seater Sofa in composite leather as per design.	0	Nos	0	0.00
32	As specified above Three Seater Sofa in composite leather as per design.	0	Nos	0	0.00
33	Corner Tables of size 450 mm x450mm made of glass top and Powder coated MS Based.	0	Nos	0	0.00
34	Total Rs.				0.00