Price Bid for Interior Furnishing works at SBI-Bolangir ADB Branch No Description of work Unit Quantity Rate Amount Plain Gypsum False Ceiling: Providing and fixing Concealed Grid 129.37 Sqm suspended ceiling system of 12.5mm India Gypsum Plaster Boards fixed to Frame Work of the company, Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, two coats of emulsion paint over a coat of primer etc., complete as directed. 2 0.600mX0.600m (2'-0"X2'-0") Silhouette Sqm 73.61 Grid False Ceiling:-Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries/Insula/Daikin etc.. The suspension system shall be 2'-0"X2'-0" plain grid system with 15mm wide flanges main runners and cross tees to have mitred ends with "birds mouth ' notches to provide mitred cruciform junctions. Main runners to be spaced at 4'-0" fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 4'-0" c/c maximum and 4'-0" cross tee of size 15mm x 44mm x 1200mm at every 2'-0" c/c maximum and 2'-0" cross tee of size 15mm x 44mm x 600mm at every 4'-0" c/c maximum and 19mm x 19mm x 3000mm wall angle alround the wall to form grid size of 2'-0" x 2'-0" and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 4' 0" intervals at the main tee and laying of 15 mm thick mineral fiber tiles manufactured by Armstrong/Insula/Daikin etc. of size 2'-0"X 2'-0" 15mm over the formed grid etc., complete as directed. 3 Flush Door Work: P&F 35mm thickness BWP grade flush door finished Sam 7.81 with 6mm thick teak wood lipping on all edges duly polished, three SS Hinges for each door, one door stopper, one mortise lock combo set per door finished with 1mm thickness laminates on both sides of approved shade and colour (solid and glazed with 5.5mm thickness float glass). Make: Kitply/ Mayor/Sylvam as approved, Hinge: Dorset/ equiv, Lock: Godrej/ Dorset (Inspire). If required, glazing of required size shall be given. Main Entrance door: P&F 12mm toughened glass in Main entrance Sam 9.11 door with patch fittings, SS handles of 200mm duly supported by pivot at top and bottom with floor springs and top chord aluminium powder coated section/ plv wood/ local hard wood duly finished as directed by engineer with edge polish. Cost of floor spring shall be paid extra. 5 Floor Spring: P&F floor springs of Hafele / Dorma/Ozone heavy duty to Nos 2.00 glass door including cutting the floors (granite/ tiles/ concrte floors) and embedding the floor springs and grouting the area by approved tile adhesive matching with existing floors complete. **Door Closure:** P& fixing Door Closure of Haffel/ Dorma/Ozone heavy Nos 4.00 duty to glass door including cutting the floors and embedding the floor springs and grouting the area by tile adhesive of latecrete matching with tile colour etc complete Roller Blinds: P&F roller blinds of Vista/ Marble/ D Décor with colour Sam 4.39 and shade as approved along with all accessories. 8 Frosted Film: P&F frosted film of 3-M/ LG make of approved design 21.00 Sqm pattern, shade and colour to glass panels including cleaning glass

Nos

1.00

panels etc complete.

Soft board: of size 1500X1200 as directed.

Price Bid for Interior Furnishing works at SBI-Bola	angir AD	B Branch	

No	Description of work	Unit	Quantity	Rate	Amount
10	Cheque Writing Table:- Supplying & fixing cheque writing table as per		1.00	Nato	Amount
10	the standard design.	/100	1.00		
11	Cheque drop/Suggesion box:	Nos	1.00		
111	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm		1.00		
	x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard				
	, , , , , , , , , , , , , , , , , , , ,				
	and the curved portion at top made out of 90 mm x 90 mm C.Pteak				
	wood section. A slit opening of 10 mm x 150 mm is to be provided at the				
	top of the box. An openable shutter of 259 mm x 262 mm size made of 1				
	9 mm thick phenol formaldehyde bonded block board is to be provided				
	at 1.50 mm above finished floor level. All the exposed timber surfaces				
	including. all free edges are to be finished with 1 rnm thick laminate				
	sheet of combination shade .Inner faces of block board surfaces are to				
	be finished with minimum two coats of synthetic enomal. paint of				
	approved shade and quality over a coat of approved primer.Rate .to				
	include cost of necessary hardware fittings e.g. brass hinges, lock, knob				
	etc. of approved.designand quality.				
12	Work Station: Officers/ Associate work station 5'x2-6" x2'6"along with		4.00		
	side unit of 18"x42"x2'6": Made with 19mm MR grade BB in table top,				
	sides with one drawer unit of 450mm x 150mmx450mm with sliding				
	channels and one cup board. The side units shall have one drawer with				
	one shutter with provision of storage units . Table shall be provided with				
	storage unit(450x450x750). All necessary hardware's, locks, handles,				
	PVC KBT of approved make shall be provided including foot rest. Front				
	modesty panel shall be 12mm MR grade ply. All exposed surfaces shall				
	be finished with 1mm thick laminate. Inside surface of table units shall				
	be pasted with inner laminate of 0.6 mm thick. A 40mm drop shall be				
	provided on customer side with 19mm BB and laminate. Edges shall be				
	finished with half round wood lipping on writing desk side and PU				
	polished for smoothness. Drawers shall be finished with lipping polished.				
	10 mm thick glass shall be proided for the table top (Cost of glass shall				
	be paid extra).Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green/ Saburi,				
	and laminate: Green/ Marino/ Century/Kit ply as approved.				
	and animates every manner contary, map by ac approved.				
13	Work Station without side table: Officers/ Associate work station 5'x2-	Nos	5.00		
	6" x2'6" made with 19mm MR grade BB in table top, sides with one				
	drawer unit of 450mm x 150mmx450mm with sliding channels and one				
	cup board. All necessary hardware's, locks, handles, PVC KBT of				
	approved make shall be provided including foot rest. Front modesty				
	panel shall be 12mm MR grade ply. All exposed surfaces shall be				
	finished with 1mm thick laminate. Inside surface of table units shall be				
	pasted with inner laminate of 0.6 mm thick. A 40mm drop shall be				
	provided on customer side with 19mm BB and laminate. Edges shall be				
	finished with half round wood lipping on writing desk side and PU				
	polished for smoothness. Drawers shall be finished with lipping polished.				
	10 mm thick glass shall be proided for the table top (Cost of glass shall				
	be paid extra).Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green/ Saburi,				
	and laminate: Green/ Marino/ Century/Kit ply as approved.				
	<u> </u>	<u> </u>	ļ		

Price Bid for Interior Furnishing works at SBI-Bolangir ADB Branch

No	Description of work		1	Poto	Amount
14	Side Credenza: Providing and fixing of side credenza of size 18"x 3'-6" x2'-6" made with 19mm MR grade BB in table top, sides with one drawer unit of 450mm x 150mm x 450mm with sliding channels and one cup board. Back to be provided with 6 mm ply. All necessary hardware's, locks, handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of side units shall be pasted with inner laminate of 0.6 mm thick. Edges shall be finished with half round wood lipping and PU polished for smoothness. Drawers shall be finished with lipping polished.Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green/ Saburi, and laminate: Green/ Marino/ Century/Kit ply as approved.	Nos	5.00	Rate	Amount
15	BM Table: BM table (as per drawing) along with side unit of 20"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units (450x450x650). Main table shall have one drawer unit of three drawers of 450 mm wide. All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished. A 40mm drop shall be provided on customer side with 19mm BB and laminated. Edges shall be finished with teak wood beading 6mm thick polished for smoothness. Drawers shall be finished with lipping polished. 10 mm thick glass shall be proided for the table top (Cost of glass shall be paid extra) Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green, and laminate: Green/ Marino/ Century/Kit ply as approved	Nos	1.00		
16	Single Window Counters: SWO Counter(5'x3'x2'6" and side unit of 3' to 3'6"x16"x30"): Made with 19mm MR grade BB table top, sides and 12mm thick ply on front modesty panel; with three equal depth drawer units (400x450 with depth as directed by engineer) with auto locking system, telescopic sliding channels, one PVC KBT, cable manager. Customer side shall be rounded with 6mm flexi ply (350 to 400mm depth) followed by 6mm ply duly supported on each side by a profile frame of 19mm BB and as directed by engineer. Round / curve shape shall be made after 3' width of table top. 12mm thick toughened glass shall be provided at 2'6"distance thus leaving 6" for customer desk space. (Cost of glass shall be paid extra). All the exposed surfaces shall be finished with 1mm thick laminate bi-colour as directed by engineer. 6mm teak wood lipping shall be provided in all drawer edges, exposed edges of counter including side unites. Side unit shall have one cupboard with shutter fitted with all accessories s directed by engineer. All inside surfaces shall be pasted with 0.6 mm laminate. Make: MR Ply/BB: Kit ply/Century/green/mayoor, Laminate: Kit ply/century/green/Marino: Hardware Godrei/ebco/ Hettich as approved.		5.00		
17	Toughened Glass Partition: P&F 12mm thick Toughened glass partition with patch fittings at floor, top and side walls for full height Cabins, main entrance doors and other locations as directed by engineer. The glass shall be Saint Gobain / TATA while patch fittings shall be Godrej/ Ebco/ Dorma/ equiv. The glass panels shall be rigidly fixed to walls, floors and ceiling runners in proper alignment.		7.20		
18	Grahak Mitra Counter: Providing, fitting & Fixing Grahak Mitra Table as per the design from 18 mm thick block board finished with 1 mm thick laminate		1.00		

Price Bid for Interior Furnishing works at SBI-Bola	ngir AD	B Branch	
			_

No	Description of work	Unit	Quantity	Rate	Amount
19	Partitions: Full height and Low height Partition: (75mm thick) Providing and fixing solid and glazed partition made with GI Channel / localy available aluminium channel of 50mm X 25mm and 2mm thickness (section 50mmx25mmx0.55mm for GI) spaced at 600mmx600mm grid and duly finished with 12 mm MR grade ply and 1mm thick laminate (colour & shade approved by engineer as solid/ teak wood / texture premium quality on each side. The frame shall be properly anchored at true ceiling, wall/ column sides and floor with long screws at 900mm centres. The glass panel shall be 5.5 to 8 mm thick with frosted film design as directed between 1050 X 2000 mm level in specified areas fixed with 85 X 15 mm teak wood jamb and 12 X 12 mm teak wood beading duly supported by 9 mm MR ply and finished with laminate. Make: GI section Jindal/ Saint Gobain/ India gypsum, MR ply: Century/ Green/ Kit ply/Mayoor, Laminate: Century/ Green/ Kit ply/ Marino as approved. Partial glazing shall be decided by the Engineer-In-Charge.	Sqm	73.86	itate	AHIVAIIL
	mm flush door finished with I mm lamination on both the sides and edges covered with beech wood beading. The rate to include for providing 'Godrej' night latch, all hardware etc. complete				
21	Wicket Gate: Providing & fixing Wicket Gate made out of 32 mm flush door finished with 1 mm lamination of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. The edges shall be finished with beech wood beading polished.		1.25		
22	12 mm thick Glass for Table Top: Providing and fixing in position 12 mm thick clear float glass of approved make in table top with required etching of SBI emblem & border on the glass as directed and with machine polish finish edges. All glasses should be clean, beveled edges and machine cut and machine moulded. No extra payment will be made on this account. Allowable tolerence for glass thick- ness is + 0.3 mm.The glass shall be clear float glass and should be ap- proved by the Engineer in Charge. It shall be clear, float transparent and free from cracks, flaws, Bubbles or Vision defects. The float glass shall conform to the IS 14900.		12.78		
23	Panneling Work: Wall/ Column panelling with MDF board: Providing and fixing aluminium frame 25mmx40mmx0.80mm with a grid of 600mmx600mm duly anchored with wall screws to the walls and finished with 9.75mm MDF board and 1mm thick laminate of approved colour and shade. Make: MR Ply: Kit ply/Century/Mayoor/Green and laminate: Kit ply/Century/Green/Marino.		65.57		
24	Storage Units: Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by auto closing hinges. All inside surface shall be finished with 0.80mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardwraes like locks, handles shall be provided. Make: Mr Ply: Kit ply/Century/green/mayoor, Laminate: Kit ply/century/green/ Marino; Hardware Godrej/ebco/ Hettich as approved Make:		9.53		

Price Bid for Interior Furnishing works at SBI-Bolangir ADB Branc	Price Bid for Interio	r Furnishing works	at SBI-Bolangir	<b>ADB Branch</b>
---	-----------------------	--------------------	-----------------	-------------------

No	Description of work	Unit	Quantity	Rate	Amount
25	Metal Fire Door (For Record Room/Document Room/UPS Room):	Nos	3.00		
	Supplying and installation of 40/60 mm thick galvanized steel fire				
	resistant door shutters of 120 minutes Fire rating confirming to IS 3614				
	(Part II) with suitably mounting on door frame, consisting of vertical				
	styles, top rail & side rail of 60 mm x 60 mm wide and bottom rail of 110				
	mm x 60 mm made out of 1.2 mm thick G.I. sheet (zinc coating not less				
	than 120 gsm/sqm) duly filled mineral wool insullation having density				
	minimum 96 kg/cum and fixing with necessary stainless steel ball				
	bearing hinges of approved make, clear fire rated 6 mm thick glass with				
	metal vision panel of size 200 x 300 mm, Anchor fastner, fire door				
	clouser, pair of SS tower bolt of 300 mm long, mortise dead lock with				
	70mm cylinder both side, SS D handle (19 x 250 mm) followed by				
	applying a coat of approved fire resistant primer or powder coating not				
	less than 30 micron etc. all complete of approved make and shade as				
	per manufacturer specifications or as directed by EIC.				
26	Putty & Priming Work: Finishing the wall surface, gypsum ceiling and	Sqm	107.90		
	other locations with two or more coat of wall primer including scrapping				
	the area as site conditions and applying 2mm thick putty to the finished				
	surafce				
27	Interior Paint work: Finishing the wall and gypsum area with tractor	Sqm	107.90		
	emulsion pants of Asian or berzer as approved with colour and shade in				
	two or more coats using roller application				
28	Solid Surface Work: Installation of 6 mm thick solid surface over the	Sqm	8.22		
	furniture as directed by the Engineer Incharge as per specification of				
	manufacturer. Make: corian/du-point/ green/ merino of approved shade.				
29	ACP Work: Providing fitting and fixing ACP panelling on the interior	sqm	16.36		
	walls by using ACP in metallic colour of approved shades made out of				
	4mm thick aluminium composite panel material consisting of 3mm thick				
	FR grade mineral core sandwiched between two Aluminium sheets				
	(each 0.5mm thick). The aluminium composite panel cladding sheet				
	shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoro				
	polymer resin coating of approved colour and shade inclusive of screws,				
	nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc.				
	and complete as per the instruction of the engineer in charge for walls				
	where instructed by the engineer incharge				
	Tatal				
	Total				
	Gross Total (Excluding GST)				