BOQ FOR ROOF SHEDDING WORK AT					
01.11	GENERAL MANAGER (NW-1) RESIDENCE, BELT				
SI.No	Description of items  Providing and laying reinforced cement croncrete works in columns,	Unit	Qnty	Rate (Rs.)	Amount (Rs.)
1	pillars,post and struts etc up to floor five level including curing complete but excluding cost of centring, shuttering and reinforcement.	Cum	5.5		
	(a) M20 grade concrete ( prop: 1: 1.5: 3)				
2	Providing form work of 12mm thick Plywood Board so as to give a rough finish including centering, shattering, strutting and propping etc., height of propping and centering below supporting floor to ceiling not exceeding 4.0M and removal of the same for in situ reinforced concrete and plain concrete work in:  Columns, Pillars, Posts & Strut of square/ rectangular/ polygonal in plan or any shape like Tee/L etc. having plane vertical face.	Sqm	78		
3	Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) TATA/SAIL/Esser Steel/ Jindal steel/Shyam steel/RINL	kg	644		
4	15 mm thick Cement plaster 1:4 (1 cement : 4 sand) in single coat on single or half brick wall for interior plastering up to 5th floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed.		78		
5	Applying one coat of distemper primer of approved brand and manufacture on wall surface after throughly brushing the surfaces free from mortar droppings and other foreign matter and including preparing the surface even and sand papered smooth.		78		
6	Wall painting (two coats) with acrylic emulsion paint approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) on new surface to give an even shade after throughly brushing the surfaces free from mortar droppings and other foreign matter and sand papered smooth.	Sgm	105		
7	Steel work in builtup tubular trusses including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer welded and bolted including special shaped washers etc complete.		2614		
8	Providing Dyna roofing fixed with galvanised iron J or L jooks, bolts & nuts 8mm dia with bitumen and G.I. limpet washers excluding the cost of purlins, rafters and trusses.  (a) 0.50 mm thick dyna roof colour sheet		259		
			T	OTAL	