

**Price Bid FOR INTERIOR FURNISHING WORKS AT SBI RACC-KOTTAYAM AT 2ND FLOOR OF KOTTAYAM TOWN BRANCH
PREMISES, AS PER UNIFORM LAYOUT**

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	Vitrified tile flooring : Providing and fixing first quality Vitrified floor tiles (minimum basic value should be @ Rs.600/m ²) conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades, size as specified by Engineer in charge , over 12mm thick bed of cement mortar 1:3 and jointing with grey cement slurry @ 3.3 Kg per sqm, including pointing in white cement mixed with pigment of matching shade complete for bath room walls. Approved brand : Cera / johnson / bell or equivalent.	160	Sqm		
2	LOW HEIGHT PARTITION : Providing and fixing of Low height partitions of 1200 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1200 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 750 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thickness of approved brand with etching shall be fixed with SS D Brackets for a height of 450 mm above the solid partition. Partition on rear similar to side partition, but solid partition.	12	Sq.M		
3	Custom Made Full Height Solid Partition: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beddings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	32	Sq.M		

**Price Bid FOR INTERIOR FURNISHING WORKS AT SBI RACC-KOTTAYAM AT 2ND FLOOR OF KOTTAYAM TOWN BRANCH
PREMISES, AS PER UNIFORM LAYOUT**

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
4	Partly solid and partly glazed partition:- Supply and set in position of custom made partly solid and partly glazed full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves . 12 mm thick toughened glass of good quality to be provided at a height of 90cm from FFL to 210 cm from FFL, including 3M Vinyl sticker / etching as per approved colour design / patterns etc complete.. Measurement for the partition area shall be considered from floor level to false ceiling level only.	40	Sq.M		
5	Providing and fixing AAC block partition blocks (auto claved aerated concrete) of size 600x200x200mm jointed with webar lock set etc complete.Rate should be inclusive of materials,labour, transportation etc	32	Sq.M		
6	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	4	Sq.M		
7	Records Room Door - Fabricating and installing metal door (in UPS room) of size 0.9mX 2.1m ,double skin using 1" square tubes for frame work and two horizontal members at equidistant and a central vertical member of same section.16 gauge sheet to be welded on both sides of framework. proper hinges and padocking system to be provided.Suitable metal cutla to be provided .Eye vision glass to be provided at suitable height.	1	No.		
8	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	4	Sq.M		

**Price Bid FOR INTERIOR FURNISHING WORKS AT SBI RACC-KOTTAYAM AT 2ND FLOOR OF KOTTAYAM TOWN BRANCH
PREMISES, AS PER UNIFORM LAYOUT**

SI.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
9	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	35	Sq.M		
10	Gypsum Board False Ceiling: Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.	75	Sq.M		
11	BM Table : Providing and fixing Branch Manager's table of size 2000 x 800 X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.Aqua blue shade of saint Gobain (or) equivalent toughened glass panel to be fixed on the 18mm thick ply on front vertical laminated Plywood Board with SS studs. Additional horizontal support to be provided below the table top in order to avoid sagging.	1	No.		

**Price Bid FOR INTERIOR FURNISHING WORKS AT SBI RACC-KOTTAYAM AT 2ND FLOOR OF KOTTAYAM TOWN BRANCH
PREMISES, AS PER UNIFORM LAYOUT**

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
12	Side Tables For BM: Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1200mm x 600 mm made of 25 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		
13	Officers Table : Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.13 above. 12 mm thick glass with polished edges to be provided on table top.	6	No.		
14	Side Tables - Providing and fixing side unit for Officer table to detail as per drg. of size 120 x 45 cm as per specification in item no.14 above	4	No.		
15	Side Tables - Providing and fixing side unit for Officer table to detail as per drg. of size 100 x 45 cm as per specification in item no.14 above	2	No.		
16	Low Level Storage : Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	12	Sq.M		
17	Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate over aluminium frame works as per standard design.	52	Sq.M		
18	Providing and Fixing 100 mm wide Vertical Blinds of Vista Levton or approved equivalent make and colour.	10	Sq.M		
19	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	100	Sq.M		
20	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade over a coat of putty including cleaning the surface.	250	Sq.M		
21	Enamel painting : Painting with 2 coats of synthetic enamel paint over a coat of wood primer after cleaning the surface.Approved make : Asian, Berger, Nerolaco or equivalent	10	Sq.M		
	TOTAL (Excluding GST)				

GST at applicable rates will be extra