

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
BRANCH -INTERIOR WORKS					
A	INTERIOR WORKS: Dismantling				
1	All existing loose furnitures, Partitions to be purchased by the contractor on lumpsum basis inclusive of all cost for dismantling and removing the same from the site to a distant location of their choice. The cost also to include the removal of false ceiling and wall panelling with supports without damaging the building structure.	0.00	LS		
A2					
1	PARTITION				
1.1	<p>FULL HEIGHT PARTITIONS - PARTLY GLAZED: Providing and fixing metal stud dry wall partition with following specifications: Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings. 12mm Exterior Grade MDF (EG-MDF) Board fixed on both sides with 25mm dry wall screws for the entire height of the partition. Partition fixed with 1.0mm laminate sheet on both sides as per the following : Skirting level upto 100 mm from FFL to have 1.0mm laminate of dark blue colour. From 100mm to 300mm level to have 1mm Laminate (aqua blue color) From 300mm level to 1070mm level to have 1mm thick Laminate (white color) From 1070mm level to 2135mm level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. The glass sizes subject to design drawing etc. From 2250mm level to 2350mm level 1mm thick Laminate (aqua blue color) on both sides as shown in drawing. From 2135mm level to 2235mm level 1mm Laminate (aqua blue color) on both sides as shown in drawing. Partition above 2235mm level to have 1mm Laminate (white color) as shown in drawing. All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish. All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p>	20.00	SQM		
1.2	<p>FULL HEIGHT PARTITIONS - SOLID Same as full height partition partly glazed above but for Fully Solid Partitions without glass panels and other specifications remaining the same. Glass panel area from 1100mm lv to 2250mm lv to be replaced with solid partition with 1mm thick Laminate (white color)</p>	0.00	SQM		
1.3	<p>HALF HEIGHT PARTITIONS This item includes partitions for SWO counters, officer cubicles etc as per the layout plan. Height of the partitions shall be as mentioned in the drawings. Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following: Laminate capping of 75mm on top, 50mm bands of 1mm Laminate on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete. From desired(as per Engineer's advise) level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. The glass sizes subject to design drawing etc. Partition fixed with 1.0mm laminate sheet on both sides as per the following : Skirting level upto 100mm from FFL. From 100mm to 300mm level to have 1mm Laminate (aqua blue color). From 300mm level to 1070mm level to have 1mm Laminate (white color). From 1070mm level to 1170mm level 1mm Laminate (aqua blue color) From 1170mm level to 1220mm level to have 1mm thick laminate on both sides as shown in drawing.</p>	15.00	SQM		
1.4	DOORS IN PARTITIONS				

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1.4.1	<p>32MM DOORS IN PARTITIONS - with glass panel: Providing and fixing 32mm thick solid core flush shutter with 85mm x 35mm beech wood frame with rebate around the jamb and shutter fixed with 1mm Laminat as specified on both sides with glass panel of 8mm clear float glass fixed with 19 x 19mm beading on both sides and glass pasted with 3M privacy film as per design.</p> <p>The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.</p>	2.00	SQM		
1.4.2	<p>WICKET GATE - for SWO Counters Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably.</p> <p>Providing wicket gate made of 32mm solid flush door with around BW/PVC edge lipping and height to match low height partitions. Wicket gate shall be fixed to partition with 85mm x 35mm beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement.</p>	5.00	SQM		
1.4.3	<p>FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS):Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be fixed onto the ply/Exterior Grade MDF base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.</p>	2.00	SQM		
1.4.4	<p>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR Providing, making and fixing Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two leaves. The entire work to be done as per site conditions with following specifications etc., complete as directed.</p> <p>(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 1200mm x 2400mm - 2250mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.</p> <p>(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>	3.00	SQM		
2	<p>WALL PANELLING IN BANKING HALL Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise all Exterior Grade MDF cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete. The work to be carried out after removing the existing panelling</p> <p>Providing 18mm thick Exterior Grade MDF jamb for door and window openings of suitable depth as per site conditions and laminated with 1mm thk laminate to match design as per partitions.</p> <p>All beech wood members to have NO VOC or LOW VOC white duco paint finish.</p>	30.00	SQM		
3	<p>COLUMN PANELLING Providing and fixing metal stud column panelling with following specifications. To be carried out after removing existing panelling</p> <p>Support metal framework on 2 shorter sides made of the following</p> <p>Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs framework at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>12mm EG-MDF fixed on all four sides with 25mm dry wall screws for the entire height of the partition. The 12mm EG-MDF fixed onto the metal framework on the 2 shorter sides and directly onto the column on the 2 longer sides with levelling gattas etc as required</p> <p>Additional 12mm EG MDF - 100mm high fixed at skirting level</p> <p>Column panelling to be finished as per the following :</p>	0.00	Sq.M.		

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	Skirting level upto 100mm from FFL to have 1.0mm laminate of dark blue colour				
	From 100mm to 2135mm level to have 12mm MDF Grill board (JALI type MDF sheet) fixed on the EG-MDF on the two longer sides of the column as shown in drawing and painted with white duco paint. The base EG-MDF shall be painted with premium emulsion paint of colour - CORAL RADIANCE-code No 2015 of Asian Apcolite Emulsion or equivalent - before fixing the MDF Grill board				
	Column Panelling to have 6mm toughened lacquered glass - ONE SINGLE PIECE for each side, pasted with adhesive/sealant onto the existing EG-MDF and of blue colour as per Colour Code No. RAL 5017-Traffic Blue - fixed on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete with 12mm x 12mm button beading on the corners				
	Column Panelling above 2135mm level to have 1mm White colour, Matt finish Laminate on all four sides as shown in drawing.				
	All beech wood members and MDF Grill Board to have minimum two coats of LOW VOC or NO VOC white duco paint finish.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
4	WALLPAPER Providing and fixing approved quality wall paper of washable grade including all adhesive, cutting, pasting etc complete. (Basic price Rs 1100 per smt excluding tax, transportation,wastage, loading / unloading, etc.,) Note : Measurement will be taken only for wall paper actually pasted at site.	3.00	SQM		
4.10	BAND with 12mm Exterior Grade MDF and Lamination				
	Providing and fixing laminated band onto the existing walls with 12mm Exterior grade MDF fixed directly onto the wall surface and finished with 1.0mm laminate sheet. Including all necessary levelling, additional framework/gattas etc if required etc complete. MDF edges finished with PVC edge banding				
4.11	100mm high	45.00	Rmt		
4.12	300mm high	0.00	Rmt		
5	FALSE CEILING:				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete after removing the existing false ceiling.				
5.1	Grid False Ceiling : Mineral Fibre Tile	90.00	SQM		
	Providing & Fixing (at a height of approximately 13') of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.				
	The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.				
	The installation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				
	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				
5.2	PLAIN GYPSUM FALSE CEILING	10.00	SQM		
	Providing and fixing (at a height of approximately 13') Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:				

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.				
	The ceiling shall be finished with 2 coats of premium emulsion paint over primer putty etc complete				
5.3	VERTICAL FACES IN FALSE CEILING - UPTO 150mm HEIGHT Same as Plain false ceiling above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.	45.00	Rmt		
6	STORAGE UNITS:				
6.1	LOW HEIGHT STORAGE UNITS Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in 18mm EG-MDF to all members except table top and 25mm block board for table top and 8mm EG-MDF for backing sheet . All faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete. Storage units shall have a internal horizontal shelf of 19mm block board finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished malanine finish	3.00	SQM		
6.2	FULL HEIGHT STORAGE UNITS Same as low height storage unit above but for 2.1m height without internal shelves, and other specifications remaining the same. Door shutter shall have SS grill at top and bottom for ventilation and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc.	0.00	SQM		
7	TABLES / COUNTERS				
7.1	BRANCH MANAGER TABLE:	1.00	Each		
	Table : 1950 - 2130mm x 900mm x 760mm				
	Side Runner : 1065 - 1220mm x 450mm x 760mm				
	Providing, making and placing in position Executive Table and Side Table with following specifications.				
	The "" L "" shaped table top on the back side to have 50mm edge alround and to be cladde with 1mm laminate.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm Laminate .				
	All the edges of 18mm EG-MDF to have PVC edge banding / BW lipping 20mm x 6mm maline polished .				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.,				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding / 20mm x 6mm beec				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG-MDF and 19mm plywood all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC ed				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
7.2	OTHER OFFICER'S EXECUTIVE TABLES:	1.00	Each		
	Table : 1500 - 1650mm x 760mm x 760mm				
	Side Runner : 915 - 1050mm x 450mm x 760mm				
	Providing, making and placing in position Executive Table and Side Table with following specifications.				
	The "" L "" shaped table top on the back side along with side tabe to have 49mm edge alround, which is to be achieved by adding a 75mm piece of 18mm EG-MDF to the table top from bottom.				

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1.0mm laminate as specified.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood lipping /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have 3 equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1 no internal shelf made with 18mm EG-MDF and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
7.3	CLERK TABLE	0.00	Each.		
	Same as Officer and Executive table above but for Table top size 1375mm x 610mm x 760mm (h) but without side runner and other specifications remaining the same.				
7.4	CROSS SELLING COUNTER				
	Same as Officer and Executive table above but for Table top size as given below and with one pedestal unit for every 1050mm length but without side runner and other specifications remaining the same.				
	1200mm x 610mm x 760mm (h) with centre vertical support of 18mm thk Exterior Grade MDF laminated	1.00	Each.		
7.5	GRAHAK MITRA TABLE:	1.00	Each.		
	Size : 1220-1525mm x 610-760mm x 760mm				
	Providing, making and placing in position Grahak Mitra Table with following specifications.				
	Main Table Top to have 25mm block board with 1mm thick laminate. The vertical supports of the table is to be made with two side boxing of 75mm x 700mm x 950 mm made with 18mm EG-MDF and the front side boxing to 100mm x 400mm x 950mm on either				
	The front of the table to have a 420mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick colour RAL-5017-Traffic Blue blue colored lacquered glass.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm Laminate as specified to be used.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.,				
	One pedestal of 400mm width having Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, ha				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
7.6	SINGLE WINDOW COUNTERS:	3.00	Each.		
	Counter : 1500-1650mm x 900-975mm x 760mm				
	Side Runner : 1050 - 1220mm x 450mm x 760mm.				
	Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.				
	Table top of main table and side table to be made in 25mm block board with 1mm thick laminate and double thickness at edges around. The laminate to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	All other members to be with 18mm EG-MDF / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm Laminate as specified in the drawing to be used.				
	Front of SWO Counter to have about 100mm high skirting made of 12mm EG-MDF board fixed at floor level and finished with 1.0mm laminate of dark blue colour				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.,				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	One Side Table with shutters made with 25mm block board top and 18mm EG-MDF for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.				
	Each Single Window Counter to have provision for 12mm thick clear float glass in the front and sides as per relevant item measured separately.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
8	DINNING TABLE (SIZE 2100 X 900 X 760mm) Providing and fixing Dining Table with Table top of 25mm thk BB of size as given below and fixed on the BEECHWOOD supporting frame with screws, bolts etc and PVC edge banding / beading as required. Supporting frame made of 50mm x 50mm beechwood - 4nos legs joined together allround at top/ bottom with 50mmx50mm beechwood members for fixity. All visible surfaces to be finished with 1.0mm thk laminate sheet and all internal and underside surfaces to be fixed with 0.8mm thick lamination sheet with matching grains & grooves polished with melamine spray. All wooden members to be polished with melamine finish complete.	0.00	Each		
9	12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS: Providing, making and fixing in position 12mm thick toughened clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size 1650mm x 500mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.	3.00	Each		
10	12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):(incl 2 nos glass) Providing, making and fixing in position 12mm thick clear float glass in the front side and shall be in 2 nos of separate sizes. Lower part shall be fixed with a glass panel of size 1500-1650 x 380mm with a central cut out of 200mm x 150mm. Uppper part shall be fixed with a glass panel of size 1500-1650 x 450mm. A gap of 50mm shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.	3.00	Each		
11	12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS: Providing, making and fixing in position 12mm thick toughened clear float glass in sizes as per design with cut out of 200mm x 150mm at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. Glass size shall be as per length of low height partiton after leaving about 300mm solid portion at both ends Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW/PVC edge lipping beading etc and fixed onto the low partition with all hardware etc complete	5.00	SQM		

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
12	<p>FLOOR MOUNTED WRITING DESK: Providing, making and placing in position Floor Mounted Writing Desk 760mm x 300mm x 450mm with following specifications. A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm EG-MDF cladded with 1mm Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board cladded with 1mm Laminate which will have verticals made with 12mm EG-MDF cladded with 1mm Laminate upto the table top level of 1050mm from floor level. The entire unit is to be made with 18mm Exterior Grade MDF Board cladded with 1mm Laminate as per drawing.The Writing Desk Circular Top to have 12mm thk toughened clear float glass with 25mm chamfered bull nosing alround. All members to be with 18mm Exterior Grade MDF Board and all exposed faces to have 1mm Laminate as specified. All the edges of 12mm / 18mm Exterior Grade MDF Board to have 20mm x 6mm beech wood/PVC edge lipping. All the unexposed faces to have 0.8mm Laminate OR and members of beech wood to have minimum two coats of NO VOC or LOW VOC white duco paint finish. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>	1.00	Each.		
13	BLINDS				
13.1	ROLLER BLINDS	18.00	Sq.M.		
	<p>Providing and fixing in position of Roller Blinds of approved Fabric of Hunter Douglas / Mac / Vista Levalor make or approved equivalent of approved shade etc., as directed.</p>				
14	<p>DESIGNER FILM WORK Providing and fixing in position Designer Film on all glasses as per drawings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.</p>	20.00	SQM		
15	<p>SOFT BOARD (size 1500X1200) : Shall be made up of 12mm thick soft board & finished with fabric of approved colour not less than Rs.125/mtr. The beading/frame work shall be made all around the soft board as suggested by the officer in charge.</p>	0.00	Each		
16.00	ACRYLIC LOGO:	1.00	Nos / each		
	<p>Providing SBI Logo-diameter as indicated below, made with 6mm Blue color (as per SBI standard logo colour) acrylic sheet, and fixed onto the existing base ACP / wall / partitions as per site and as per drawings and directions etc., complete.</p>				
	SIZE (apprx) - 600 x 1220 mm				
17.00	SHUTTER BOXING WITH TRAP DOOR				
	<p>Providing & fixing ..shutter boxing in position made of 9mm ply with framing of Aluminium Tube sections of min 50mm x 25.4mm and 20 gauge 600mm C/C both ways.Laminate thickness of 1 mm „minimum. Laminate Brand & Shades to be as per bank's approval. Trap door will be 19 mm marine ply finished with Laminate with required accesories & locking arrangement, complete as directed by Engineer</p>	7	Sq.M.		
18	ACP CLADDING WORK	5.00	SQM		
	<p>Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work but excluding cost of structural steel fabrication, if any. ACP Cladding - 4 mm thick.</p>				
19	PLASTIC EMULSION PAINTING	185.00	SQM		
	<p>Plastic Emulsion painting: Cleaning the surface of the wall & then applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.</p>				

SCHEDULE OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORKS FOR STATE BANK OF INDIA, SUDAMBI BRANCH					
SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
19	CLEARANCE OF DEBRIS	3.00	loads		
	Clearance of Debris and all Waste materials generated during the execution of the work by Vendors of ALL TRADES, including loading, unloading, carting away, transportation and disposal to suitable location as per site conditions etc				
	<i>(Measurement shall be for Number of Loads of tempo / mini truck actually carried away and duly certified by Bank authorities / Security with GATE PASS.)</i>				
	TOTAL FOR BRANCH (excluding GST)				
	Signature of Contractor				