

**PRICE BID**

**NAME OF WORK: DESIGN, SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF ONE NUMBER ELEVATOR (GEARLESS & MACHINE ROOMLESS) AT ADMINISTRATIVE OFFICE BUILDING, HYDRABAD, ANDHRA PRADESH.**

S No	Description	Qty
1	<p><b>Design, fabricating, supply, installation, testing &amp; commissioning</b> of one number Electric Traction Passenger Elevator (Machine room less) with all accessories about minimum of 884.0 Kgs.(13 passengers) @ 1.00 metre per second speed for Office building (B + G + 3 floors) with 5 stops and 5 openings (All openings on the same side). 415 Volts, 3 phase, 50 Hertz Alternating Current, Variable Voltage Variable Frequency (with speed encoder). Simplex Full Collective, microprocessor based moulder control system, gearless with permanent magnet motor of adequate rated. Scratch resistant, Stainless steel hair finish Car body with mirror, stainless steel handles on three sides with Granite/ Vitrified tiles flooring and stainless steel false ceiling.</p> <p>Overload warning indication, Floor annunciator with music, Simplex selective collective control with/ without attendant, Car entrance is protected by centre opening stainless steel doors with clear opening about 900 mm wide x 2000 mm high with view panel. The door operation should be with infrared Electronic door protection, 2 hours fire rated. Full height car operating panel with micro stroke call push buttons (located on side panel), Door open and door close button on the car operating panel, 2-way intercom with Press &amp; Speaking COP, Dot matrix position indicator display integrated within the car operating panel, Battery operated Alarm/ bell and emergency light, Fireman's switch at the main lobby. Automatic rescue devices, Indirect lighting system with LED, fan with automatic control etc. Providing sufficient lighting inside the well.</p> <p>Rate shall including cost and conveyance of all materials to site, labour charges for erection, lead, lift, transportation, handling charges, scaffolding cost and liaisoning charges for obtaining approval from electrical inspectorate etc. complete.</p>	2
2	Rebate for dismantling and taking away all equipment's of existing lift without damages of lift well and bank proprieties.	-2
<b>A</b>	<b>TOTAL AMOUNT</b>	
3	<b>Comprehensive AMC</b> for the above minimum 884 Kgs 13 Passenger lift after completion of warranty period of <b>24 Months</b> . CAMC WILL START AFTER EXPIRY OF TWO YEARS OF WARRANTY PERIOD	
a	Third Year	1
b	Fourth Year	1
c	Fifth Year	1
d	Sixth Year	1
e	Seventh Year	1
<b>B</b>	<b>TOTAL AMOUNT</b>	
	<b>GRAND TOTAL AMOUNT EXCLUDING</b>	

GST WILL BE PAID EXTRA AS APPLICABLE

**Note:**

- (i) All the vendors must quote their rates for the above work duly after inspection of the : variation/ deviation will be entertained later.
- (ii) Price quoted should be inclusive of all Taxes, duties and transportation charges except G The Vendor must quote for AMC charges for the new lift per year and GST is payable e rates at the time. No revision of AMC will be done subsequently as AMC is considered tender.
- (iii) The L1 contractor will be finalized upon the grand total amount.
- (iv) The works required for erection of lift like scaffolding, grouting, all civil works related t under scope of contractor.
- (v)

**IG of 2 No's 13 PASSENGER  
NG (06746) IN VISAKHAPATNAM,**

<b>UOM</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
No		0
No		0
<b>UNT FOR LIFT (Rs.)</b>		<b>0</b>
JOB		0
JOB		0
JOB		0
JOB		0
JOB		0
<b>UNT FOR CAMC (Rs.)</b>		<b>0</b>
<b>INCLUDING GST : (A + B)</b>		<b>0</b>

site. No further price

IST.

extra as per prevailing  
for arriving at the L1

to installation will be