

SCHEDULE OF QUANTITIES - CONSTRUCTION AND REPAIR OF DILAPIDATED BOUNDARY WALL AT JUBILEE BHAVAN, ERANHIPALAM

Civil Works:-					
Sr. No.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Demolishing the existing dilapidated boundary wall at sections identified by the EIC and disposing the waste away from site at contractors' own risk and cost.	1	LS		
2	Earth work excavation for basement and foundation in all kinds of soil including dressing of sides and ramming of bottom height including including getting out the excavated soil within a lead of 50m and lift of 1.5m etc complete. Rates to include bailing	25	M3		
3	Filling in foundation in plinth with excavated earth including watering, ramming, consolidation and leveling dressing etc. complete.	15	M3		
4	Providing random rubble masonry with hard stone in superstructure above plinth level and upto floor level, including levelling up with cement concrete 1:6:12 using 20mm nominal size coarse aggregates. Rates to include material, labour , shuttering etc.	37	M3		
5	Providing and laying ready mix concrete M 20 including cost of all form work watering, curing etc complete but excluding cost of reinforcement for beam & lintel.	17	M3		
6	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	970	Kg		
7	Solid block works of approved qty of size 30x20x15cm & of compressive strength not<35 kg/cm ² in in C.M. 1:6 in super-structure above plinth level (first floor level) including staging if required watering ,curing etc complete.	35	M3		
8	Plastering with Cement Mortar 1:4 ,12mm thick one coat floated hard and trowelled smooth including a neat cement flushing coat including 2% water proof compound by weight of cement	85	Sqm.		

9	Finishing New cement plastered wall with 1 coat of primer and painted with 2 coats of exterior emulsion paint.	100	Sqm.		
10	Removal and uprooting of trees along the boundary wall, disposal of the tree waste away from site. Cost to also include liasoning with local authorities for obtaining permission for uprooting the trees..	7	Nos		
Total amount (Excluding GST)					

* GST as applicable will be paid extra