

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
<b>A</b>	<b>INTERIORS / FURNISHING</b>				
1	<p><b>Officer's &amp; Staff Tables</b> Table made of 19 mm thk. Commercial ply (ISI Marked -MR grade) with Table Top, front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour &amp; shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels finished with laminate, as per manufacturers instructions / specifications.</p>				
	<p>A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick commercial ply finished with 1.0 mm thk. laminate and 3/4" x 1/4" teakwood lipping on all visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1.0 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. All the three sides of the drawer will be made of 12 mm commercial plywood and front side of 19 mm commercial ply with 1 mm thick laminate. The bottom of drawer shall be made of 6 mm thick commercial plywood. The drawer will be provided with handle / knob of good quality to be got approved before fixing with drawer channel of 18" length &amp; the counter should have provisions of foot rest , Space for CPU. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be spirit (natural) polish. Size &amp; shape of moulding to RM / AGM / CM may vary to 3" x 3" or as per drg. &amp; design.</p>				
a	A.G.M. - Size 7'0" X 3'6" X 2'6"	1.00	Nos.		
b	A.G.M. - Size 6'0" X 3'6" X 2'6"	1.00	Nos.		
c	O.T. / S.T. - Size 5'0" X 2'6" X 2'6"	6.00	Nos.		
d	Work station - Size 2'3" X 2'0" X 2'6"	1.00	Nos.		
2	<p><b>8.0 MM thk glass on top of tables.</b> All the edges of the glass shall be <b>Bevelled from all sides</b>, grinded polished including Hole for cable manager to all as per given below.</p>	120.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
3	<b>Side Credenza</b> Providing & fixing Side credenza ( 15" to 18" deep as directed) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontaly running on side mounting drawer slides /channels of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all Non-Visible / inside surfaces i.e. inside of drawer / cupboard / shelf etc. shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
a	Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-6"/ 4'-0" X 1'-6" / 1'-3" X 2'-6" / 2'-3" (W X D X H)	80.00	Sft.		
4	<b>Back credenza / Storage - (HT. - 2'3" / 3'0" / 4'0" or as specified)</b> Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 3'0" HT. & as specised made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible sides, with teak wood lipping on all edges including bottom touching floor. The back credenza will have cupboard with shutters and one shelf. The shutters with handle and magnetic catcher shall be provided beneath the drawers and Non-Visible / inside surfaces i.e. inside of cupboard & shelves shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment. The work includes following	280.00	Sft.		
i	The Back credenza will have three drawers, horizontaly running on side mounting drawer slides /channels of EBCO make in every / within 6'-0" running length.				
ii	For the Library unit will have cupboard with glazed shutters and shelf at every 12" height & vertical devisions as per drg.the shutters with handle and magnetic catcher shall be provided 5.0 mm thk glass fixed with 12mm x 12mm half round beading in 19 mm thick commercial ply board 3" to 4" members.				
5	<b>Display storage unit / Trophy Case</b> 8'-0" high for AGM office as per drawing. (4'-0"X1'-5" /1'-6"X 8'-0") Providing and fixing Display unit using 19mm commercial ply finished in 4.0 mm thick VENEER of approved Shade, Sides and top and bottom out of commercial ply and Veneer. Internal shelving (5 nos. internal shelves intermididte vertical & horizontal wooden members 38 mm thk. face & required toughened glass shelves. The unit using 12 mm thk. toughened polished glass in shelves (The Glass fixed with u brackets). Complete with provision of Coves & cove light, closing of all joints and accessories complete in all respect as per direction of Architect Engineer-In-Charge. Basic rate of Veneer Rs. 140 /sft.	30.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
6	<p><b>Pegion Box for storing news papers</b>  Providing and supplying Pegion Box of overall size 4'0" X 1'6" X 8'0", having 6 nos. of compartments horizontally and 3 nos. of compartments vertically or as per drawing with outer frame made of 19 mm thick commercial ply and 6 mm thick plywood on back side finished with 1.0 mm laminate on all outer visible surfaces with teak wood lipping on all edges of board. The inner surfaces of box shall be made of 19 mm thick commercial ply &amp; finished with 1.0 mm laminate. All the exposed edges of board shall be provided with teak wood lipping 5 mm thick shall be Spirit polished with matching pigment.</p>	50.00	Sft.		
7	<p><b>False Ceiling With Steps. &amp; Cove - Gypsum Board</b>  Providing and fixing suspended false ceiling (as per specification of manufacture) including steps &amp; cove as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).</p>	900.00	Sft.		
	<p>The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.</p>				

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps / Vertical bands / cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc.				
8	<b>Extra for cove over gypsum board false ceiling.</b> Providing and fixing cove in suspended false ceiling as instructed including all required extra sections / parameters & labour as per mentioned above to complete the job. Measurement shall be made from bottom external band only.	150.00	Rft.		
9	<b>False Ceiling - (Mineral Fibre)</b> Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm, RH 99 mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The frame work comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.	420.00	Sft		
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				
10	<b>Full Height Partitions with etching on glasses. - Solid / partialy glazed/ flush door.</b> Providing and fixing partition made of 50mm X 25 mm X 16 Gauge aluminium extruded sections @ 1'6" to 1'6" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching film as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1mm thk brushed steel finsih lamiante. Work also includes providing and fixing of door as per drawing and specifications. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality.	220.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
	All wood shall be finished with high gloss Spirit polished of approved shade. The rate shall also include for providing groves in veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling.				
11	<b>Low Height Partition with etching on glasses ( Height + 4'-0" )</b> Providing and fixing Low Height Partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. approved laminate as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1.0 mm thk brushed steel finish laminate. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. All teak veneer / ply / wood shall be finished with high gloss Spirit polished of approved shade.	150.00	Sft.		
12	<b>Paneling to wall &amp; Ceiling (including all kind of suspensions for all heights)</b> Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. Frame work for bands - 3" / 6" / 9" / 12" & 15" as required paid in sq. feet. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be Malamine polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc. Note - Panelling for AC duct covering - Aluminium frame work / section shall be supported to wall & soffit of RCC slab / beam etc. under False ceiling & payments shall be made only for exposed surfaces of teak ply / laminate.				
i.	Panelling finished with 1.0 mm thk. Approved shade & colour - suede / glossy / wood grains / veneer texture laminates.	600.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
ii	<p>Panelling with veneer / pine wood to wall &amp; Ceiling (including suspensions)            Providing &amp; fixing 4 MM thk. Veneer / pine wood ledge (pine wood ledge - size 60 mm to 150 mm wide &amp; 2500 mm length) of approved shade &amp; colour made to design &amp; desired grooves / patterns with fram work as mentioned above including required wooden framework made of hard wood, soft wood, commercial board &amp; ply of required size &amp; thickness finished with 4 mm thk venner over 8.0 mm thk commercial ply &amp; The Veneer needs to be prepared sanded and malamine polish. The wotk includes all kind of coves &amp; provisions of LED lights. The rate should be inclusive of making Coves for provision of LED / lighting / opening with frame etc. for electrical / air conditioner, A.C. grills &amp; trap door etc. venner / pine wood ledge &amp; Cove (s) / Steps / Vertical bands / shall be measured in square feet. Payments shell be made only for exposed surfaces &amp; actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc. Basic rate of Veneer Rs. 140 /sft.</p>	650.00	Sft.		
iii	<p><b>Extra for providing veneer with polish in ceiling -</b>            Providing and fixing 4 mm thk. Veneer in ceiling over 8 mm thk. commercial ply screwed to GI ceiling sections / aluminium section / tube (as per requirement) frame work work as item number above (Paneling to wall &amp; Ceiling / 12, i, ii). The work includes providing grooves as per pattern, Malamine polished of approved shade on the veneer surface. Payment shall be made for the visble finished area. The work should be complete as per instructions of Architect or Engineer in charge</p>	350.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
13	<b>Toughened Glass 12.0 mm thk. With etching film including all / as per given below</b>	110.00	Sft.		
i	Doors - Toughened Glass 12.0 mm thk. with etching Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700 mm X 2400 / 2100 mm all sides (as per drg. / instructions) edge grainded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete.				
ii	Fixed Glass / Glazing / Partition - Toughened Glass 12.0 mm thk. with etching film. Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grainded, polished to be fixed with necessary patch fittings / clamps at the bottom, the glazing to be to be fitted at top - horizontally / vertically with teak wood beading 30 mm x 30 mm as per instructions finished with sprit polish. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings / clamps etc. the rate shall be include necessary etching film / logo all inclusive, complete.				
iii	The modesty guard to officials Tables shall be finished with 12.0 mm thk. toughed glass in as required 2" / 3" / 4" wide S.S. Spacer.				
14	<b>Hardware &amp; Accessories for fixing Toughened Glass doors etc.</b> Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accomodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, SS stopper etc. all complete of godrej / dorma.	2.00	Job		
15	<b>Hardware &amp; Accessories for fixing Toughened Glass / glazing etc.</b> Superior quality stainless steel, S.S. Spacer / S.S. glass holders of required size & L - shaped lamps with cover / cap 2 no. on both sides to holding the front glass partition to S.W. Counter & fixed glazing including required glass holes to fix the clamps complete.	45.00	Nos.		
16	<b>Door Closer</b> - Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer - Godrej / Hyper / Dorma make to Doors complete in all respects.	2.00	Nos.		
17	<b>Mortice Lock</b> -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.	2.00	Nos.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	<b>BOQ -1</b>				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
18	<b>Painting Work – Texture Paint with white shade over coating</b> Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.	650.00	Sft.		
19	<b>ZEBRA BLINDS : SHEER DIMOUT BLINDS , Series - Essence of approved shade &amp; colour.</b> Providing, supplying & fixing Zebra Blinds of approved make - (Vista), shade etc as per the directions of the Bank at the predetermined locations. The fabric used should be dust, moisture resistant and the vendor to get the sample approved from the Bank before supplying the item. The work includes 40mm / required roller tube / round channel and mechanism and other fitting fixed in position as per manufacture's specification, including all required hardwarw & Scaffolding, complete in all respects to the satisfaction of Architect.	320.00	Sft.		
20	<b>Planter Housing</b> Providing and supplying planter housing of overall size (3'0"L X 1'6"W X 1'6"H) / (1'6"L X 1'6"W X 3'0"H) as per drawing & design - made to shaped with outer frame made of 19 mm thick commercial block board with 1.0 mm laminate on all outer visible surfaces. The inner surfaces of planter housing / box shall be lined / claded with 1.0 mm laminate or with aluminium sheet . All the exposed edges of board shall be provided with teak wood lipping of 12 mm thick and teak wood edges / lipping / beading shall be spirit polished natural / as per instructions with matching pigment to the satisfaction of the Architect / Engineer.	4.00	Nos.		
21	<b>Flush door shutters with veneer finish including polish</b> Providing and fixing ISI marked 32 mm flush door shutters conforming to IS : 2202 (Part I) non decorative type, core of block board construction with frame of 1st class hard wood and finished with veneer 3 mm / 4mm or ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 40 mm thick including Stainless Steel butt hinges (min 5 nos. with each shutter) with two ball bearings, 125mm X 75mm X 3mm of Ozone / KICH / Dorma / Hafele with necessary screws. (over all area of door shutter to be measured). the work includes Mealamine polishing on door by preparing the surface applying putty base course. prepare the surface smooth by sand papering and then applying mealamine polish with air compressor. Two or more coats on new works including a coat of wood filler. The work includes following- (basic Rate of veneer - 140.00 per Sft.).	50.00	Sft.		
i	Providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters .				
ii.	Providing and fixing approved brand and manufacture SS 304 grade Tower bolt 250mm long with 10mm dia fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge.				
iii	Providing and fixing approved brand and manufacture SS 304 grade Tower bolt 150mm long with 10mm dia fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge.				



Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
iv	Providing and fixing approved brand and manufacture SS 304 grade wall mounted door buffer fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge.				
v.	Providing and fixing approved brand and manufacture SS 304 grade Door Stopper - door mounted hanging type fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge.				
vi	Providing and fixing approved brand and manufacture SS 304 grade : Simax Stainless Steel Door Handle / Silver/ Size 8 Inch Stainless Steel, Steel Door Handle (Pair / Silver Pack of 1) fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge. Type: Door Handle, Material: Stainless Steel, Steel, Color: Silver, Finish: Matte, Weight: 200 g.				
vii	Providing and fixing approved brand and manufacture SS 304 grade : Simax Stainless Steel Door Aldrops & Latch / Silver/ Size 8 to 12 Inch Stainless Steel fixed with SS screws etc. complete in all respects as per manufacturers' specifications & as directed by Engineer-in-charge. Finish Type: Steel , Material: Stainless Steel, Design: Unique Design, Aldrop Size (in inch): Up to 8 to 12 Inch. Rod Thickness (in mm): 12 mm, Grade: 304.				
viii	The door fixed in the existing frame / chokhat including all repair of frame, beading , architrave & finished mealamine polish after removing of existing polish / paint.				
22	<b>Glass work</b> Replacement of required glasses 6.0 mm thk. / matching to existing of Modiguard / Saint Gobain in existing door and window shutter panes, glazing etc. The glass is fixed with required teak wood moldings / steel member / putty or with matching medium including all required hardwarw & Scaffolding, complete in all respects to the satisfaction of Architect.	100.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Deptt. –PR & Rajbhasha at LHO, Sector - 17, Chandigarh.				
	BOQ -1				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
23	<b>Covering for Fridge</b> Providing and fixing fridge covering as instructions with outer frame made of 19 mm thick commercial block board with 1.0 mm thick laminate on all outer visible surfaces as per pattern / design / Battens for ventilation. The inner surfaces shall be finished with liner of 0.7 to 0.8 mm thk. off white / white colour. Work also includes providing and fixing of door with S S hinges . All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall also include for providing groves in laminate & wood, hardware like hinges, handles, chitkney , magnatic catchers& locks etc. The work should be done to the entire satisfaction of the Architect / Engineer. For measurements front shall be measured.	25.00	Sft.		
24	Dismantalling of existing all required furniture, partitions, ceiling, electrical work, all kind of doos & windows, AC Units, AC duct required cutting & closed the void / vent of duct matching with existing material, hahging tight the remaining & Repairing. All old material hand over to the bank authorities.	1.00	Job		
25	<b>Flooring – Vitrified Tiles - (SNOW ALLURE / SNOW FLAIR), SIZE- 800 MM X 800 MM PREMIUM QUALITY - DOUBLE CHARGE WHITE COLOUR</b> Providing and laying approved vitrified tiles (Johanson) first quality / premium quality range Homogeneous size - 800 mm X 800 mm in floor and skirting laid on 20 mm. thick base of adhesive of 1st quality like Pidilite including - Dismantling of existing all kind of flooring / tiles / stone etc., filling depressions in floor level, preparing of surface & disposal of required malba from site to an unobjectionable place & out side of municipal Limits, including Pointing the joints with epoxy grout as directed etc. as per design pattern. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect. (skirting shall be paid in sq.feet), (Basic Rate @ 70.00 per sft.), (Rate for dismantling etc. @ 10.00 per sft.) The works include required sreed for filling of specified grade All work upto plinth level. 1:5:10 (1 cement: 5 coarse sand: 10 graded stone agreegate 20 mm nominal size.)	1200.00	Sft.		
26	<b>Painting Work – Plastic Emulsion</b> Applying three or more coats of plastic emulsion (Asian / Nerolac) including making of surfaces with oil based putty and rubbing, etc. in case where the surface has been white / colour washed, the old white / colour wash shall be entirely removed and surface broomed / scrapped down before the new paint is applied. Rates include Scaffolding for all heights, cleaning splashes from glass panes, floor, furniture , etc. The work shall be completed in all respects to the entire satisfaction of the Architect.	500.00	Sft.		
27	<b>Painting Work – Enamel Paint</b> Applying two or more coats of enamel paint (Asian / Nerolac) on wooden / steel surfaces including filling and making of surfaces smooth with oil based putty required to give even and smooth surface. Rates include Scaffolding for all heights, cleaning splashes from glass panes, floor, furniture etc.	500.00	Sft.		
	<b>Total (A)</b>				
	GST Extra as / applicable				