

**STATE BANK OF INDIA**  
**SCHEDULE OF WORKS : AC INSTALLATION WORKS**  
**PROJECT : DARBHANGA BRANCH**  
**UNDER RBO DARBHANGA, A.O. MUZAFFARPUR**

SR.	ITEM DESCRIPTIONS	UNIT	QTY.	RATE	AMOUNT
1	<b>Air Conditioners :-</b> Supply and installation of 2 TR capacity 4 way Copper Cassette type Air-Conditioners ( inverter,R32) of (Voltas/Blue star / hitachi / carrier / o-general / LG) including 5 KVA automatic stabiliser of v guard/Sen & Pandit and fixing of outdoor units with steel stand all accessories complete in all respect.	NO.	14		
2	Supply & installation of Extra copper pipe with insulation for cassette AC	MTR.	200		
3	Supply & installation of Extra drain pipe for Cassette AC	MTR.	200		
4	Supply & installation of Wire for cassette AC	MTR.	305		
				<b>TOTAL</b>	
<b>RS.(Total in word):-</b>					

**NOTE:-**

**\*All safety norms, I.S.Code, I.E.Rules must be followed. In case of any confusion please contact to the Bank's Engineer.**

**\* Rate are inclusive of transportation charge etc. but exclusive of GST.**