

Price Bid
Fabrication and Fixing of Weather Shed over Terrace of G-2 terrace Building at SBI Residential Colony Nerul

Sr. No.	Particulars	Quantity	Unit	Rate	Amount
1	Providing, detailing, composite fabricating members like Trusses, girders, bracings, supports, purlins, runners, vertical member and similar structural steel members fabricated using GI hollow tubular steel sections (circular & rectangular pipes), conforming to IS 1239 part 1 and 2 and of grade Fe 250 as per specifications and approved fabrication drawings (which are to be prepared by Contractor and got approved from Engineer), including transportation of the same to site, erection of structural steel members for all heights & at all levels (Terrace of building), provision of necessary erection anchor fastener in RCC member, bolts, fixing bolts, nuts, washers, cleats, stiffeners, gussets, base plate, and all necessary operations like preheating as per specifications, straightening, bending, cutting, drilling, grinding, machining if specified, welding, grinding, removing the welding burr and preparing surface for painting with wire brush cleaning and applying two coats of epoxy red oxide primer and two coats of Epoxy Corrosion Resistant Enamel paint of after fabrication etc complete as directed by Engineer. Rates are inclusive of polymer grouting of Anchor fastener holes.(JSW, TATA and SAIL)	2200	Kg		
2	Providing and fixing precoated galvanised iron profile sheet(size, shape and pitch of corrugation as approved by Engineer-in-charge) of 0.5 mm thick (+0.05 %) total coated thickness with zinc coating, in 240 mpa steel grade, epoxy primer on both side of the sheet and polyester top coat. The sheet should be supplied in single length upto 12 metre or as desired by E/IC. The sheet shall be fixed using J bolt with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. (JSW, TATA and SAIL)	5200	Sft		
3	Providing and fixing 110-150 mm dia PVC half round drainage channel with necessary fixture as bend, L-support etc complete and connected with main drain down take pipe	240	rft		
4	Providing and fixing 100 mm dia PVC round drainage downtake Pipe with necessary GI Bracket with U hook, fixture and connected with main drain channel.	150	rft		
5	Providing and laying in position M-30 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete if required to site of laying and the cost of centering, shuttering, finishing and excluding reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge.	2	cum		
	Total amount				
	Total amount in words				

GST will be extra as applicable