

**TENDER FOR PROPOSED RENOVATION OF CGM SUITE AT SBILD,PUNE**

Item No.	Items	Quantity	Unit	Rate	Amount
1	Demolition of , false ceiling etc. and carting away debris	1,200.00	Sqft		
2	Removing Existing tiles and providing and fixing new Italian marble slab of thickness 18-20mm of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and cleaning etc. complete. ( Including all debris removing from site ) consider basic rate of tiles Rs.80/sqft	300.00	Sqft		
3	Wooden flooring:Providing and laying Laminated Wooden flooring of approved make on floor in a design combination of two different colours as per the drawing & instructions on levelled floor including levelling the surface of application area with P.C.C, insulating the areas, surface preparation, bedding, finishing, polishing, cleaning including skirting patti as per manufacturers specifications, moulding etc complete as per the directions and instructions of the Consultant. The rate shall be inclusive of edge moulding & end strips at the junction between the floor and the vertical surfaces and mouldings, T grooves etc complete. (Basic rate of tiles = Rs. 180 / Sq Fts.)	700.00	Sqft		
4	Providing POP punning including scaffolding and curing etc. complete.	2,500.00	Sqft		
5	POP design as per design	2,500.00	Sqft		
6	Providing, fabrication and fixing in position of false ceiling at a height of 10'0" from floor (or the height will be decided on spot as per the site conditions) by fixing 12 mm Th. helix board sheets on frame work of GI sheet section. The main runners of 22 gauge GI sheet and cross runners of 24 gauge GI sheet must be framed to form a mesh of 600 x 600 mm c/c. The helix must be fixed to the GI frame and joints must be properly filled in with POP paste and paper tape, supplied by the manufacturer, to get a levelled smooth ceiling, including acrylic paint three or more coats. Recessing of the Gypsum Board for light fixtures must be done alongwith extra frame work of GI sheet section to hold the concealed light fixtures.	600.00	Sqft		
7	Providing and erecting false ceiling in Veneer with 12 mm thk marine ply backing on teak wood frame to be anchored to the main ceiling with cross runners tongued as per design	150.00	Sqft		
8	Lustre Paint: Providing & applying Lustre paint from approved manufacturer of desired colour shade including necessary wall scraping, primer coats 2 coats of paint complete.	2,500.00	Sqft		
9	showcase -Providing & fixing show case as per design finished in Corian lipping Patti matching polish & Veneer finish for top side with melamine polish and internal side exposed surface & 3 Nos Drawer unit below table 2 units with necessary Hardware as per approved design & Drawing .(Reception Table)	30.00	Rft		
10	display unit	50.00	Sqft		
11	TV panelling as per drawing	48.00	Sqft		
12	Sofa with centre table	16.00	Rft		
13	Decal on walls, paintings	80.00	Sqft		
14	Wall paper	1,500.00	Sqft		
	<b>Toilets - Civil work</b>				
15	Plastering	150.00	Sqft		
16	Providing and fixing bolt for geyser	2.00	Nos		
	<b>Sum Total</b>				-
	<b>Discount ,if any</b>				-
	<b>Total</b>				-