

STATE BANK OF INDIA					
RENOVATION OF HOSTEL BLOCK (RIGHT WING) AT SBILD MASULIPATNAM					
BILL OF QUANTITIES - INTERIOR WORKS					
S.No.	Description	Qty	Unit	Rate	Amount
1	Flush Door with frame				
	Providing and fixing Flush door with frame with 2nd class teak wood frame of size 70 x 50mm finished with 2 coats of enamel paint over a coat of primer. 32mm thick (finished) flush shutters in single leaf with external lipping, phenol formaldehyde bonding and finished with 1mm thick laminate of approved colour & shade on both side with necessary grooves. Dorma Make or equivalent make hardware fittings like locking arrangements, 22mm dia & 230mm high SS brush finish handles, door closer, Hinges, Tower bolts, etc. fixed to the shutters.	52.00	Sqm		
2	Re-Lamination of existing Flush Door				
	Alteration , Re-lamination, of existing flush Door using 1mm thick laminate of approved colour and shade on both side of the door. Rate inclusive of removing / Scratching existing laminate, necessary hardware fittings like Door lock, handle, door stopper, door closer, Hinges, wherever required to be replaced as per the Architect / Client requirement.	4.00	Sqm		
3	Toilet Door - BWR Ply with Frame				
	Providing and fixing BWR door with second class T.W. frame of size 70 x 50mm finished with 2 coats of enamel paint over a coat of primer. 32mm thick (finished) BWR shutters in single leaf with external lipping, phenol formaldehyde bonding and finished with 1mm thick laminate of approved colour & shade on both side with necessary grooves. Dorma Make or equivalent make hardware fittings like locking arrangements, 22mm dia & 230mm high SS brush finish handles, Hinges, Tower bolts, etc. fixed to the shutters.	39.00	Sqm		
4	Gypsum Board False Ceiling				
	Providing and fixing in position M / F suspended false ceiling to details per drawing with GI frame work and 12.5mm tapered type gyp board panels to form grids of 457mm x 1220mm as per manufacturer's specification including provision for stepped shaped ceiling for light trough comprising.				
	Frame work of intermediate channels (M.F.T.) at 1220mm centres along one direction M/F ceiling section MF5 at 457mm centres along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling, all to detail as per drawing.				

	The intermediate channels suspended from ceiling, through strap hangers 25 x 0.5mm (MF 8) at 1220mm centres connected to soffit cleats P534 (27 x 37 x 25 x 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 12mm dia and 17/16" long with necessary bolts and nuts etc., all connected with additional perimeter channels (MF 6A) for openings for light fixtures, AC ducts, vertical drops, offsets etc., wherever necessary all to detail and as per direction.				
	12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25mm screws to form grids of 457mm x 1220mm varied along wall ends etc. including Architectural boxing, design and painting the underside of gyp board with 2 coats of plastic emulsion paint of approved colour over a coat primer etc., complete. mode of measurement should be considered flat area only.	595.00	Sqm		
5	Mineral Fibre Board False Ceiling (Silhouette Exposed Grid)				
	Providing & Fixing Of Armstrong or equivalent make Mineral Fibre Acoustical Suspended Ceiling System With Fine Fissured / Pin hole / real sand / false sand acoustic mineral fibre ceiling board With Armstrong Silhouette Exposed Grid . Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The tile shall be laid on Armstrong Silhouette profile grid system with 15mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 45mm and a load carrying capacity of minimum 15.68 Kgs/m2.	68.00	Sqm		
6	Wall Panelling with frame - laminate finish				
	Providing and fixing laminate panelling on wall. Framing shall consist 25 x 50 x 1.5mm Aluminium frame at 600mm c/c. both ways horizontally and vertically on the wall. This framing should be covered by 9mm thick BWR ply finished with 1mm thick laminate of approved colour and shade. All concealed faces of BWR ply painted with one coat of wood preservative paint before fixing.	80.00	Sqm		
7	Texture paint				
	Prepare surface and paint two coats of Texure paint of approved colour and shade over a coat of primer including Alteck putty after thoroughly scrapping the existing internal walls.Rate including scaffolding at all levels	126.00	Sqm		

8	WPC Covering with laminate finish				
	Providing and fixing 18mm thk WPC covering to detail, 18mm thick WPC stiffner on horizontal and verticals on both ways fixed to wall with necessary screws, aluminium cleats, rawl plugs, etc., complete. 18mm WPC finished with 1mm laminate of approved colour and shade with necessary grooves and beading.	115.00	Sqm.		
9	Roller Blinds				
	Providing and fixing the Roller blinds of Approved Colour and shade with necessary fixing arrangement. Basic cost of Blinds Rs.700/sqm.	106.00	Sqm		
10	Wall Paper				
	Providing and fixing wall paper of approved design and pattern with necessary fixing arrangements and base preparations.	8.00	Sqm		
				TOTAL	