

Date:

**SBI, MINI RACPC & RACC, DHARMAVARAM**  
**ESTIMATE FOR AIR CONDITIONING WORKS**

Sl.No.	Description	UOM	Qty.	Rate (Rs.)	Amount (Rs.)
<b>Part A:</b>					
1	Supply of inverter type Cassettee type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity.				
	2.0 TR Capacity	Set	8		
2	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating				
	1.5 TR capacity	Set	4		
	Sub Total Part A				
<b>Part B:</b>					
1	Installation, testing and commissioning of Cassettee and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.				
A	2.0 TR capacity Cassettee type	Set	8		
B	1.5 TR capacity HWM type	Set	4		
2	Supply and erection of suitable size of MS stand for outdoor units	Set	12		
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes				
A	Suction line & liquid line for Cassettee units	RM	110		
B	Suction line & liquid line for hi-wall mounted units	RM	20		
4	Drain line from indoor to outdoor machines as per standards	RM	150		
5	Supply, laying, testingand commissioning of flexible cable of suitable size for casettee units	RM	120		
6	Supply, laying, testingand commissioning of flexible cable of suitable size for HWM units	RM	40		
	Sub Total Part B				
	<b>Grand Total (Part A + Part B)</b>				