

SCHEDULE-I

**BILL OF QUANTITY for Interior Works**

Sl. No	Description	Qty	Unit	Rate	Amount
<b>I</b>	<b>INTERIOR WORKS:</b>				
<b>A</b>	<b>FIXED FURNITURE:</b>				
1.00	<b>PARTITIONS</b>				
1.10	<b>FULL HEIGHT PARTITIONS - PARTLY GLAZED</b>	9.75	Sq.M.		
	Providing and fixing metal stud dry wall partition with following specifications:				
	Supporting system comprising of 50mm x50mm x 0.5mm <b>metal studs at 600mm c/c bothways</b> . The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	<b>12mm Exterior Grade MDF ( EG-MDF) Board</b> fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto <b>100 mm</b> from FFL to have <b>1.0mm</b> laminate of <b>dark blue colour</b>				
	From <b>100mm to 300mm</b> level to have <b>1mm Laminate</b> (aqua blue color)				
	From <b>300 mm level to 1070 mm</b> level to have 1mm Laminate (white color)				
	From <b>1070 mm level to 2135 mm</b> level to have 8mm clear float glass fixed with with 85mm x 15mm alround jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.The glass sizes subject to design drawing etc.				
	From <b>2135mm level to 2235mm</b> level <b>1mm Laminate</b> (aqua blue color) on both sides as shown in drawing.				
	Partition <b>above 2235mm</b> level to have <b>1mm Laminate (white color)</b> as shown in drawing.				
	All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
1.20	<b>FULL HEIGHT PARTITIONS - SOLID</b>	24.25	Sq.M.		
	Same as full height partition partly glazed above but for Fully Solid Partitions without glass panels and other specifications remaining the same. Glass panel area from 1220mm lvl to 2135mm lvl to be replaced with solid partition with 1mm Laminate (white color)				

Sl. No	Description	Qty	Unit	Rate	Amount
1.30	<b>HALF HEIGHT PARTITIONS</b>	<b>11.75</b>	<b>Sq.M.</b>		
	<i>This item <b>includes partitions for SWO counters, officer cubicles etc as per the layout plan.</b> Height of the partitions shall be as mentioned in the drawings.</i>				
	Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following:				
	<b>1mm thick laminate on top, 50mm bands of 1mm thick laminate</b> on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.				
	Partition fixed with 1.0mm laminate sheet on both sides as per the following :				
	Skirting level upto <b>100mm</b> from FFL to have <b>1.0mm laminate of dark blue colour</b>				
	From <b>100mm to 300mm</b> level to have <b>1mm Laminate</b> (aqua blue color)				
	From <b>300mm level to 1070mm</b> level to have <b>1mm Laminate</b> (white color)				
	From <b>1070mm level to 1170mm</b> level <b>1mm Laminate</b> (aqua blue color)				
	From <b>1170mm level to 1220mm</b> level to have 1mm thick laminate on both sides as shown in drawing.				
1.40	<b>DOORS IN PARTITIONS</b>				
1.41	<b>32MM DOORS IN PARTITIONS - with glass panel:</b>	<b>5.65</b>	<b>Sq.M.</b>		
	Providing and fixing <b>32mm thick</b> solid core flush shutter with <b>85mm x 35mm</b> beech wood frame with rebate around the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of <b>8mm clear float glass</b> fixed with 19 x 19mm beading on both sides and glass pasted with 3M <b>privacy film</b> as per design.				
	The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.				

Sl. No	Description	Qty	Unit	Rate	Amount
1.50	<b>WICKET GATE - for SWO Counters</b>	<b>2.50</b>	<b>Sq.M.</b>		
	<i>Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably</i>				
	Providing wicket gate made of <b>32mm solid flush door</b> with around PVC edge banding / BW lipping and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with <b>85mm x 35mm</b> beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have <b>self lock from inside fixed at lower height</b> as per instructions and Bank requirement				
1.60	<b>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</b>	<b>6.02</b>	<b>Sq.M.</b>		
	Providing, making and fixing in position Fixed <b>12mm toughened glass openable shutters work</b> as per specifications given below and for the openings mentioned. <b>Main Entrance Glass</b> Work comprising of Door opening of approximate size <b>1830mm x 2135mm - 2440mm</b> in two leaves, and <b>Partition Doors</b> of approximate size <b>900 - 1065mm x 2135mm - 2440mm</b> . The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1830mm - 1525mm x 2440mm - 2135mm and Single Door approx. Size: 900mm - 1220mm x 2440mm - 2135mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
2.00	<b>WALL PANELLING:</b>				
2.10	<b>WALL PANELLING IN BANKING HALL</b>	<b>22.80</b>	<b>Sq.M.</b>		
	Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise all <b>Exterior Grade MDF (EG-MDF)</b> cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete.				
	Providing <b>18mm thick Exterior Grade MDF jamb</b> for door and window openings of suitable depth as per site conditions and laminated with 1mm thk laminate to match design as per partitions.				
	All beech wood members to have NO VOC or LOW VOC white duco paint finish.				

Sl. No	Description	Qty	Unit	Rate	Amount
2.20	<b>BAND with 12mm Exterior Grade MDF and Lamination</b>				
	Providing and fixing laminated band onto the existing walls with 12mm Exterior grade MDF fixed directly onto the wall surface and finished with 1.0mm laminate sheet. Including all necessary levelling, additional framework/gattas etc if required etc complete. MDF edges finished with PVC edge banding				
	<b>100mm high</b>	<b>30.00</b>	<b>Rmt</b>		
3.00	<b>FALSE CEILING:</b>				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
3.10	<b>Grid False Ceiling : Mineral Fibre Tile</b>	<b>61.00</b>	<b>Sq.M.</b>		
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.				
	The tile shall be laid on <b><u>Microline / Silhouette profile grid system</u></b> with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.				
	The Installation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using <b><u>US Boral / Gyproc / Armstrong suspension system</u></b> (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				
	Flush fitting <b>1200mm long cross tees</b> to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				

Sl. No	Description	Qty	Unit	Rate	Amount
3.20	<b>PLAIN GYPSUM FALSE CEILING</b>	<b>33.60</b>	<b>Sq.M.</b>		
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:				
	<b>27 x 37 x 1.6mm</b> Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, <b>20 x 28 x 30 x 0.5mm</b> Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.				
	All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.				
	The ceiling shall be finished with <b>2 coats of premium emulsion</b> paint over primer putty etc complete				
3.30	<b>VERTICAL FACES IN FALSE CEILING - UPTO 150mm HEIGHT</b>	<b>30.00</b>	<b>Rmt</b>		
	Same as Plain false ceiling above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				
4.00	<b>STORAGE UNITS:</b>				
4.10	<b>LOW HEIGHT STORAGE UNITS</b>	<b>4.88</b>	<b>Sq.M.</b>		
	Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in <b>18mm EG-MDF</b> to all members except table top and <b>25mm block board</b> for table top and <b>8mm EG-MDF</b> for backing sheet . The top and front facia of the storage unit to have 1mm thick laminate. All other exposed faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete.				
	Storage units shall have a internal horizontal shelf of <b>19mm block board</b> finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished melanine finish				

Sl. No	Description	Qty	Unit	Rate	Amount
<b>B</b>	<b>LOOSE FURNITURE:</b>				
5.00	<b>TABLES / COUNTERS</b>				
5.10	<b>BRANCH HEAD TABLE:</b>	<b>1.00</b>	<b>Each.</b>		
	<b>Table : 1950 - 2130mm x 900mm x 760mm</b>				
	<b>Side Runner : 1065 - 1220mm x 450mm x 760mm</b>				
	Providing, making and placing in position <b>Executive Table and Side Table</b> with following specifications.				
	Main Table and side Table top and to be made in <b>25mm block board with 1mm thick laminate</b> . The front side of the table to have a inverted " C " made with 2 x <b>18mm thick EG-MDF</b> clad with 1mm thick laminate on the front and the verticals towards the modesty panel. The modesty panel to have <b>18mm EG-MDF</b> clad with 6mm thk toughened lacquered glass in blue colour as specified.				
	The " L " shaped table top on the back side to have 50mm edge around and to be clad with 6mm acrylic solid surface.				
	All other members to be with <b>18mm EG-MDF</b> and all exposed faces of the table to have 1mm thick laminate as specified.				
	All the edges of <b>18mm EG-MDF</b> to have PVC edge banding / BW lipping 20mm x 6mm maline polished .				
	One readymade <b>CPU mobile pedestal</b> .				
	One Molded <b>Key Board Tray</b> with channels etc.,				
	One Three Drawer Unit made with <b>18mm EG-MDF and 12mm EG-MDF</b> . The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding / 20mm x 6mm beech wood edge lipping etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with <b>18mm EG-MDF</b> and 19mm plywood all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC edge banding / 20mm x 6mm beech wood edge lipping etc				
	All the unexposed faces to have <b>0.8mm Laminate</b> .				
	Ready Made Modular <b>Foot Rest - 400mm x 350mm x 65mm</b> .				
	Table and runner top to have 8mm thk clear float glass				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
5.20	<b>Table : 1500 - 1650mm x 760mm x 760mm</b>	<b>2.00</b>	<b>Each</b>		
	Providing, making and placing in position <b>Table</b> with following specifications.				
	Main Table and side Table top and to be made in <b>25mm block board</b> with 1mm thick lamiate on top. The front side of the table to have a inverted " U " made with <b>2 x 18mm thick EG-MDF</b> finished with 1.0mm laminate including the verticals towards the modesty panel. The modesty panel to have <b>18mm EG-MDF</b> cladded with 1mm Laminate as specified.				
	The " L " shaped table top on the back side along with side tabe to have 49mm edge alround, which is to be achieved by adding a 75mm piece of <b>18mm EG-MDF</b> to the table top from bottom.				
	All other members to be with <b>18mm EG-MDF</b> and all exposed faces of the table to have 1.0mm laminate as specified.				
	All the edges of <b>18mm EG-MDF</b> to have 20mm x 6mm beech wood lipping /PVC edge banding.				
	One readymade <b>CPU mobile pedestal</b> .				
	One <b>Molded Key Board Tray</b> with channels etc.				
	One Three Drawer Unit made on each side table and main table with <b>18mm EG-MDF</b> and <b>12mm EG-MDF</b> . The unit to have 1 drawer and remaining with a shutter door with shelf. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular <b>Foot Rest - 400mm x 350mm x 65mm</b> .				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.30	<b>SINGLE WINDOW COUNTERS:</b>	<b>3.00</b>	<b>Each.</b>		
	<b>Counter : 1500-1650mm x 900-975mm x 760mm</b>				
	<b>Side Runner : 1050 - 1220mm x 450mm x 760mm.</b>				
	Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.				
	<b>Table top</b> of main table and side table to be made in <b>25mm block board with 1mm thick laminate</b> and double thickness at edges alround. The laminate to continue in the <b>front side with curvature</b> from the front table top to the modesty panel in front with cove lighting provision.				
	All other members to be with <b>18mm EG-MDF</b> / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm Laminate as specified in the drawing to be used.				
	Front of SWO Counter to have about <b>100mm high skirting made of 12mm EG-MDF board</b> fixed at floor level and finished with 1.0mm laminate of <b>dark blue colour</b>				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				

Sl. No	Description	Qty	Unit	Rate	Amount
	One readymade <b>CPU mobile pedestal.</b>				
	One Molded <b>Key Board Tray</b> with channels etc.,				
	One Three Drawer Unit made with <b>18mm EG-MDF and 12mm EG-MDF.</b> The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	One Side Table with shutters made with <b>25mm block board</b> top and 18mm EG-MDF for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the <b>unexposed faces to have 0.8mm Laminate.</b>				
	Ready Made <b>Modular Foot Rest</b> - 400mm x 350mm x 65mm.				
	All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.				
	Each Single Window Counter to have provision for <b>12mm thick clear float glass</b> in the front and sides as per relevant item measured separately.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
6.00	<b>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:</b>	<b>2.00</b>	<b>Each.</b>		
	Providing, making and fixing in position <b>12mm thick toughened</b> clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size <b>1650mm x 500mm - 100mm in tapered shape.</b> All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				



Sl. No	Description	Qty	Unit	Rate	Amount
7.00	<b>12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):</b>	2.00	Each.		
	Providing, making and fixing in position <b>12mm thick clear float glass</b> in the front side and shall be in <b>2 nos of separate sizes</b> . Lower part shall be fixed with a glass panel of size <b>1500-1650 x 380mm</b> with a central cut out of 200mm x 150mm. Upper part shall be fixed with a glass panel of size <b>1500-1650 x 450mm</b> . A <b>gap of 50mm</b> shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.		(incl 2 nos glass)		
8.00	<b>12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS:</b>	2.50	Sq.M.		
	Providing, making and fixing in position <b>12mm thick toughened</b> clear float glass in sizes as per design with <b>cut out of 200mm x 150mm</b> at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
	Glass size shall be as per length of low height partition after leaving about 300mm solid portion at both ends				
	Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW lipping /PVC edge banding etc and fixed onto the low partition with all hardware etc complete				
9.00	<b>WALL MOUNTED WRITING DESK:</b>	1.00	Nos / each		
	Providing, making and placing in position Wall Mounted Writing Desk 760mm x 300mm x 450mm with following specifications.				
	The entire unit is to be made with <b>18mm EG-MDF</b> clad with 1mm Laminate as per drawing.				
	The Writing Desk to have <b>12mm thick toughened</b> clear float glass with 25mm chamfered bull nosing around at top fixed with SS supports.				
	All members to be with <b>18mm EG-MDF</b> and all exposed faces to have 1mm Laminate as specified.				
	All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	All the unexposed faces to have 0.8mm Laminate OR and members of beech wood to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

Sl. No	Description	Qty	Unit	Rate	Amount
<b>C</b>	<b>OTHER WORKS:</b>				
10.00	<b>BLINDS</b>				
10.10	<b>ROLLER BLINDS</b>	<b>4.50</b>	<b>Sq.M.</b>		
	Providing and fixing in position of <b>Roller Blinds</b> of approved Fabric of Hunter Douglas / Mac / Vista Levalor make or approved equivalent of approved shade etc., as directed.				
11.00	<b>DESIGNER FILM WORK</b>	<b>8.00</b>	<b>Sq.M.</b>		
	Providing and fixing in position <b>Designer Film</b> on all glasses as per drawings and heights mentioned. The Designer Film is of <b>Harmony / 3M</b> or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
12.00	<b>ENTRANCE - VINYL SCRAPER MATTING:</b>	<b>1.00</b>	<b>Nos / each</b>		
	Providing, fixing in position 3M™ Nomad™ Scrapper Matting 7150, Gray / Red. <b>Entrance coiled vinyl scrapper matting</b> designed for heavy traffic applications over the existing flooring to a neat finished job as per drawings and directions etc., complete.				
	Size - 1200 x 600				
13.00	<b>CLEARANCE OF DEBRIS</b>	<b>2.00</b>	<b>loads</b>		
	Clearance of Debris and all Waste materials generated during the execution of the work by Vendors of ALL TRADES, including loading, unloading, carrying away, transportation and disposal to suitable location as per site conditions etc complete				
	<i>(Measurement shall be for Number of Loads of tempo / mini truck actually carried away and duly certified by Bank authorities / Security with GATE PASS.)</i>				
14.00	<b>Fire Door</b>	<b>2.10</b>	<b>Sq.M</b>		
	Providing & Fixing Fire retardent door frame of size 130MM x 65MM with 60 minutes fire retardent rating door shall be 55mm thick single shutter, stander manufactures specifications and finishing with laminate in approved colour door shall be fixed with handles, locks, hinges all hardwares complete etc.,The rate shall include fixing of frame to the masonry with 40mm x 6mm size flat iron hold fasts 450mm long embedded in 150mm thick cement concrete of mix 1:3:6 or as specified.				
				<b>TOTAL</b>	

Amount in words

**\* GST will be extra as applicable**